ALISAL MARKETPLACE MITIGATION MONITORING AND REPORTING PROGRAM

APNs 003-051-082-000, 003-051-083-000, 003-051-065-000, 003-051-054-000, 003-051-055-000, 003-051-008-000, 003-052-001-000, 003-052-002-000, 003-052-018-000, 003-052-019-000, 003-052-023-000, 003-052-032-000, 003-052-031-000, 003-041-029-000, 003-041-031-000, 003-041-001-000, 003-041-028-000 (GENERAL PLAN AMENDMENT 2022-002 AND REZONE 2022-002)

Mitigation Measures	Timing of	Responsible for		ation of eltion
	Verification	Verification	Date	Initials
Air Quality				
 Mitigation Measure AQ-1: Construction Air Quality. During construction, the applicant or successor in interest for each individual site shall: Limit grading to 8.1 acres per day, and limit grading and excavation to 2.2 acres per day. Provide watering trucks on site to maintain adequate soil moisture during grading and water graded/excavated areas at least twice daily, thus minimizing dust generation. In addition, the water trucks shall be used to wash down trucks and tractors, including earth loads, prior to entering public roadways. Prohibit all grading activities whenever wind speeds exceed 15 miles per hour (mph). Maintain a minimum of two feet for freeboard for all haul trucks. Cover all trucks hauling dirt, sand, or loose materials. Cover inactive storage piles. Enforce a 15-mph speed limit for all unpaved surfaces when visible dust clouds are formed by vehicle movement. Place gravel base near site entrances to clean tires prior to entering public roadways. 		Development and Engineering Services Department – Plan Check Service		

Mitigation Measure AQ-2: MBARD Health Risk Consultation. Prior to issuance of any grading permit and/or building permit for each individual site, the applicant or successor in interest shall consult with MBARD regarding the potential need for a diesel health risk assessment (HRA). If required, the applicant or successor in interest shall prepare a diesel HRA and shall implement the measures contained therein to ensure that project-specific emissions are below MBARD's established health risk thresholds: hazard index greater than 1 for acute or chronic impacts, and cancer risk greater than 10 in one million for long-term operational emissions or 1 per 100,000 population for temporary construction-related emissions. Measures may include, but would not be limited to: • Use of diesel-fueled equipment equipped with Tier 4 (or Tier 3 if the Tier 4 standard is unavailable) USEPA engine standards. The USEPA estimates that Tier 4 engines would reduce PM emissions by approximately 90 percent compared to the USEPA Tier 2 standards (USEPA 2008). • Retrofit off-road diesel equipment with Verified Diesel Emissions Control Strategy (VDECS) like Diesel Particulate Filters (DPF). Particulate Matter level 3 VDECS can provide at least an 85 percent reduction (CARB 2015). • Use alternatively fueled (e.g., natural gas) diesel construction equipment, including all off-road and portable diesel-powered equipment. • Use electrically driven equipment that is not powered by a portable generator set. • Limit the hours of operation for heavy-duty equipment and/or limit the quantity of heavy-duty equipment operating at the same time.	Prior to issuance of any grading permit and/or building permit; during construction.	Development and Engineering Services Department – Plan Check Services; MBARD		
Biological Resources		,		
Mitigation Measure BIO-1: Nesting Bird Surveys and Avoidance.	Not more than 14	Development and		
The Project shall implement the following measures to mitigate for	days prior to	Engineering Services		
loss of nesting habitat of the Project in compliance with the federal	vegetation	Department –		

Migratory Bird Treaty Act and relevant Fish and Game Codes:	clearance.	Community	
 Avoidance. In order to avoid impacts to nesting raptors 		Development	
and migratory birds, the Project will be constructed, if		Department	
feasible, from September 16th and January 31st, which is			
outside the avian nesting season.			
 Preconstruction Surveys. If Project activities must occur 			
during the nesting season (February 1-September 15), a			
qualified biologist will conduct preconstruction surveys for			
active raptor and migratory bird nests within 10 days prior			
to the start of these activities. The survey will include the			
proposed work area(s) and surrounding lands within 500			
feet, where accessible, for all nesting raptors and			
migratory birds. If no active nests are found within the			
survey area, no further mitigation is required.			
Establish Buffers. Should any active nests be discovered			
near proposed work areas, no disturbance buffers of 250			
feet around active nests of non-listed bird species and 500			
feet around active nests of non-listed raptors will be			
established. If work needs to occur within these no			
disturbance buffers, a qualified biologist will monitor the			
nest daily for one week, and thereafter once a week,			
throughout the duration of construction activity. Should the			
,			
nature of construction activity significantly change, such			
that a higher level of disturbance will be generated,			
monitoring will occur daily for one week and then resume			
the once-a-week regime. If, at any time, the biologist			
determines that construction activity may be compromising			
nesting success, construction activity within the designated			
buffer will be altered or suspended until the biologist			
determines that the nest site is no longer susceptible to			
deleterious disturbance.			
Cultural Resources			
CUL-1 Historical Resources Identification and Treatment Plan	Prior to permit	Development and	
Prior to permit approval for development on the Project site, a	approval.	Engineering Services	

	,	
historical resources evaluation shall be completed for that	Department –	
individual site to confirm if existing buildings and/or structures	Community	
withing these sites qualify as historical resources as defined by	Development	
Section 15064.5(a) of CEQA Guidelines. The evaluation shall be	Department	
prepared by a qualified architectural historian or historian who		
meets the Secretary of the Interior's Professional Qualifications		
Standards (PQS) in architectural history or history. The qualified		
architectural historian or historian shall conduct an intensive-level		
evaluation in accordance with the guidelines and best practices		
promulgated by the State Office of Historic Preservation to identify		
any potential historical resources within the proposed project area.		
All properties 45 years of age or older shall be evaluated within		
their historic context and documented in a report meeting the		
State Office of Historic Preservation guidelines. All evaluated		
properties shall be documented on Department of Parks and		
Recreation Series 523 Forms. The report shall be submitted to the		
City for review and concurrence.		
Any relocation, rehabilitation, or alteration of the resource shall be		
implemented consistent with the Secretary of the Interior's		
Standards for the Treatments of Historic Properties (Standards).		
In accordance with CEQA, a project that has been determined to		
conform with the Standards generally would not cause a		
significant adverse direct or indirect impact to historical resources		
(14 CCR Section 15126.4[b][1]). Application of the Standards shall		
be overseen by a qualified architectural historian or historic		
architect meeting the PQS. In conjunction with any development		
application that may affect the historical resource, a report		
identifying and specifying the treatment of character-defining		
features and construction activities shall be provided to the City		
for review and concurrence, in addition to the historical resources		
evaluation.		
If significant historical resources are identified on a development		
o.g o.g o.g o.g o.g a do tolo billott		

site and compliance with the Standards and or avoidance is not feasible, the applicant or developer shall provide a report explaining why compliance with the Standards and or avoidance is not feasible for the City's review and approval. Site-specific mitigation measures shall be established and undertaken, including, but not limited to, documentation of the historical resource in the form of a Historic American Buildings Survey-Like report. The report shall be commissioned by the project applicant or their consultant to comply with the Secretary of the Interior's Standards for Architectural and Engineering Documentation and shall generally follow the Historic American Buildings Survey Level III requirements, including digital photographic recordation, detailed historic narrative report, and compilation of historic research. The documentation shall be completed by a qualified architectural historian or historian who meets the PQS and submitted to the City prior to issuance of any permits for demolition or alteration of the historical resource. Mitigation Measure CUL-2 Phase I Cultural Resources Study Prior to the issuance of any grading or construction permits for each individual site, a Phase I cultural resources study shall be	Prior to issuance of grading or construction	Development and Engineering Services Department –	
shall generally follow the Historic American Buildings Survey			
research. The documentation shall be completed by a qualified			
1			
,		•	
•		•	
performed by a qualified professional meeting the Secretary of the	permits.	Community	
Interior's (SOI's) Professional Qualification Standards (PQS) for		Development	
archaeology (National Park Service 1983). The Phase I cultural		Department	,
resources study shall include a pedestrian survey of the project			_
site when appropriate and sufficient background research and			
field sampling to determine whether archaeological resources may			
be present. Archival research shall include a records search of the			
Northwest Information Center (NWIC) no more than two years old and a Sacred Lands File search with the NAHC. The Phase I			
technical report documenting the study shall include			
recommendations that shall be implemented prior to and/or during			
construction to avoid or reduce impacts to archaeological			,
I constituction to avoid of founds impacts to archaeological			· I
resources. Recommendations may include, but would not be			

		·	
training, or additional testing and mitigation (outlined in Mitigation Measures CUL-3 through CUL-7). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The City shall include recommendations in the Phase I technical report as Conditions of Approval to be implemented throughout all ground disturbance activities. The final report shall be submitted to the NWIC. Mitigation Measure CUL-3 Extended Phase I Testing If recommended by the Phase I study for each individual site	Prior to the issuance of a	Development and Engineering Services	
(Mitigation Measure CUL-2), the project applicant shall retain a qualified archaeologist to conduct an Extended Phase I (XPI) study to determine the presence/absence and extent of archaeological resources on the project site. XPI testing shall include a series of shovel test pits and/or hand augured units and/or mechanical trenching to establish the boundaries of archaeological site(s) on the project site. If the boundaries of the archaeological site are already well understood from previous archaeological work, an XPI will not be required. All archaeological excavation shall be conducted by a qualified archaeologist(s) under the direction of a principal investigator meeting the SOI's PQS for archaeology (National Park Service 1983). If an XPI report is prepared, it shall be submitted to the City for review and approval prior to the issuance of a grading or construction permit. Recommendations therein shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, site avoidance, Phase II Site Evaluation, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-4, CUL-5, CUL-7, and CUL-8). The final report shall be submitted to the NWIC.	grading or construction permit.	Department – Community Development Department	
Mitigation Measure CUL-4 Archaeological Site Avoidance Any identified archaeological sites (determined after implementing Mitigation Measures CUL-2 and/or CUL-3) or archaeological resources encountered during ground-disturbing activities shall be	During construction.	Development and Engineering Services Department – Community	

avoided by project-related construction activities, where feasible.		Development	
A barrier (temporary fencing) and flagging shall be placed		Department	
between the work location and any resources within 60 feet of a			
work location to minimize the potential for inadvertent impacts. If			
the resource cannot be avoided, Mitigation Measure CUL-5 shall			
be implemented.			
Mitigation Measure CUL-5 Phase II Site Evaluation	During	Development and	
If the results of any Phase I and/or XPI for each individual site	construction.	Engineering Services	
(Mitigation Measures CUL-2 and/or CUL-3) indicate the presence		Department –	
of archaeological resources that cannot be avoided by the project		Community	
(Mitigation Measure CUL-4) and that have not been adequately		Development	
evaluated for the NRHP or CRHR listing at the project site, the		Department .	
qualified archaeologist shall conduct a Phase II investigation to			
determine if intact deposits remain and if they may be eligible for			
the CRHR or qualify as unique archaeological resources. If the			
archaeological resource(s) of concern are Native American in			
origin, the qualified archaeologist shall confer with the City and			
local California Native American tribe(s).			
A Phase I evaluation shall include any necessary archival			
research to identify significant historical associations and mapping			
of surface artifacts, collection of functionally or temporally			
diagnostic tools and debris, and excavation of a sample of the			
cultural deposit. The sample excavation would be carried out to			
characterize the nature of the site(s), define the artifact and			
feature contents, determine horizontal and vertical boundaries,			
and retrieve representative samples of artifacts and other			
remains.			
If the archaeologist and, if applicable, a Native American monitor			
or other interested tribal representative determine it is appropriate,			
cultural materials collected from the site shall be processed and			
analyzed in a laboratory according to standard archaeological			
procedures. The age of the materials shall be determined using			
radiocarbon dating and/or other appropriate procedures; lithic			
artifacts, faunal remains, and other cultural materials shall be			

to the NWIC. Mitigation Measure CUL-6 Phase III Data Recovery Should the results of the Phase II site evaluation for each individual site (Mitigation Measure CUL-5) yield resources that meet CRHR significance standards and if the resource cannot be avoided by project construction in accordance with CUL-4, the project applicant shall ensure that all feasible recommendations for mitigation of archaeological impacts are incorporated into the final design and approved by the City prior to construction. Any necessary Phase III data recovery excavation, conducted to exhaust the data potential of significant archaeological sites, shall be carried out by a qualified archaeologist meeting the SOI's PQS for archeology (National Park Service 1983). Data recovery shall be conducted in accordance with a research design reviewed and approved by the City, prepared in advance of fieldwork, and using the appropriate archaeological field and laboratory methods consistent with the California Office of Historic Preservation Planning Bulletin 5 (1991), Guidelines for Archaeological
--

archaeological resource(s) of concern are Native American in origin, the qualified archaeologist shall confer with the City and local California Native American tribe(s). As applicable, the final Phase III Data Recovery reports shall be submitted to the City prior to issuance of any grading or construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities.	
local California Native American tribe(s). As applicable, the final Phase III Data Recovery reports shall be submitted to the City prior to issuance of any grading or construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities.	1
As applicable, the final Phase III Data Recovery reports shall be submitted to the City prior to issuance of any grading or construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities.	l
submitted to the City prior to issuance of any grading or construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities.	
construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities.	
implemented throughout all ground disturbance activities.	
Recommendations may include, but would not be limited to,	
Cultural Resources Monitoring, and/or measures for unanticipated	
discoveries (outlined in Mitigation Measures CUL-7 and CUL-8).	
The final report shall be submitted to the NWIC upon completion.	
Mitigation Measure CUL-7 Cultural Resources Monitoring During Development and	
If recommended by Phase I, XPI, Phase II, or Phase III studies for construction. Engineering Services	
each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, Department –	
and/or CUL-6), the project applicant shall retain a qualified Community	
archaeologist to monitor project-related, ground-disturbing Development	
activities which may include the following but not limited to: Department	
grubbing, vegetation removal, trenching, grading, and/or	
excavations. The archaeological monitor shall coordinate with any	
Native American monitor as required. Monitoring logs must be	
completed by the archaeologist daily. Cultural resources	
monitoring may be reduced for the project if the qualified	
archaeologist finds it appropriate to reduce the monitoring efforts.	
Upon completion of ground disturbance for the project, a final	
report must be submitted to the City for review and approval	
documenting the monitoring efforts, cultural resources find, and	
resource disposition. The final report shall be submitted to the	
NWIC.	
Mitigation Measure CUL-8 Unanticipated Discovery of Cultural During Development and	
Resources construction. Engineering Services	
If archaeological resources are encountered during ground- Department –	
disturbing activities, work within 50 feet shall be halted and the Community	
project archaeologist meeting the SOI's PQS for archeology Development	
(National Park Service 1983) shall immediately to evaluate the Department	

find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated discoveries shall be submitted to the City for review and approval and submitted to the NWIC after completion. Recommendations contained therein shall be implemented throughout the remainder of ground disturbance activities.				
Greenhouse Gas Emissions Mitigation Measure GHG-1: Future development shall install EV charging infrastructure according to the most ambitious voluntary standard in the California Green Building Standards Code at the time of project approval.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department		
Mitigation Measure GHG-2: Future development shall provide no more parking spaces than the off-street parking requirements established in the City of Salinas Municipal Code. Alternatively, multi-family residential development can choose to unbundle parking costs with costs to rent or own a residential unit instead of meeting the maximum off-parking requirement.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department		
Hazards and Hazardous Material			ļ	
Mitigation Measure HAZ-1: Prior to the obtaining grading permits or starting other ground disturbing work for each individual parcel, the City shall hire a qualified environmental professional to conduct a Phase I environmental assessment (ESA), consistent with the American Society for Testing Materials standards (ASTM E1527). The Phase I ESA shall evaluate the likelihood that	Prior to obtaining grading permits or starting other ground disturbing work for each individual parcel.	Development and Engineering Services Department – Community Development Department.		

hazardous chemicals are present and whether soil sampling is			
necessary. If the Phase I ESA indicates that contamination is			
unlikely, no further mitigation is necessary other than any			
recommendations identified in the Phase I ESA (such as stopping			
work if stained soil is encountered). If the Phase I ESA indicates			
that additional soil sampling or other further evaluation is			
necessary, the City and/or future developer shall hire a qualified			
environmental professional to conduct a Phase II ESA to			
determine the presence and extent of contamination. If the results			
indicate that contamination exists at levels above regulatory action			
standards, then the site shall be remediated in accordance with			
recommendations made by applicable regulatory agencies,			
including RWQCB and DTSC. The agencies involved shall			
depend on the type and extent of contamination. If remediation is			
necessary, the City shall hire a qualified environmental			
professional prior to obtaining grading permits or ground			
disturbance to prepare a work plan that identifies necessary			
remediation activities, including excavation and removal of on-site			
contaminated soils, appropriate dust control measures, and			
redistribution of clean fill material on the project site. The plan			
shall include measures that ensure the safe transport, use, and			
disposal of contaminated soil removed from the site. The plan			
shall also identify when and where soil disturbing construction			
activities may safely commence. The City shall review and			
approve the work plan prior to issuance of demolition or grading			
permits. The City shall require individual projects to comply with			
the work plan as a condition of approval.			
Hydrology and Water Quality			
Mitigation Measure HYD-1: Future Development projects on the	Prior to permit	Development and	
subject site that would demand an amount of water equivalent to,	approval.	Engineering Services	
or greater than, the amount of water required by a 500-dwelling		Department –	
unit project are required to prepare a Water Supply Assessment.		Community	
		Development	
		Department	

Noise		
 Mitigation Measure NOI-1: Prior to ground disturbing activities, the City of Salinas shall ensure the following with the Project proponent: Construction equipment, fixed of mobile, shall be outfitted with properly operating and maintained mufflers. Construction noise reduction methods such as shutting off idling equipment, installing temporary acoustic barriers around stationary construction noise sources, maximizing the distance between construction equipment staging areas and occupied residential areas, and using electric air compressors and similar power tools rather than diesel equipment shall be used. During construction, stationary construction equipment shall be located so that emitted noise is directed away from or shielded from sensitive noise receivers. 	During construction.	Development and Engineering Services Department — Community Development Department.
Mitigation Measure NOI-2: The use of heavy construction equipment within 25 feet of existing structures shall be prohibited.	During construction.	Development and Engineering Services Department — Community Development Department.
Transportation		
Mitigation Measure TRANS-1: To maintain safety standards at all intersections and roadway segments pursuant to implementation actions identified in the Vision Zero Action Plan, a traffic impact study shall be required for all development projects anticipated to generate 110 or more new daily vehicle trips within the Project Area, unless not required by the City. Depending on the results of this study, future developments may be required to construct or contribute to street safety improvements to meet the demand generated by the project. Improvements shall be in accordance with the City of Salinas' Vision Zero Action Plan (i.e. pedestrian-	Prior to permit approval.	Development and Engineering Services Department –Traffic Engineering and Plan Check Services

activated crosswalk warning beacon, high visibility crosswalks,				
pedestrian hybrid beacon, reduced parking at intersection,				
intersection control, raised median and street trees, protected bike				
lanes, and lane reduction). These improvements shall be required				
as conditions of approval.				
Tribal Cultural Resources				
Mitigation Measure TCR-1 Inadvertent Discoveries During	During	Development	and	
Construction	construction.	Engineering Servi	ces	
In the event that cultural resources of Native American origin are		Department	_	
identified during grading or construction, all earth disturbing work		Community		
within the vicinity of the find shall be temporarily suspended or		Development		
redirected until a qualified archaeologist has evaluated the nature		Department.		
and significance of the find; an appropriate Native American				
representative, based on the nature of the find, is consulted; and				
mitigation measures are put in place for the disposition and				
protection of any find pursuant to Public Resources Code Section				
21083.2. If the City, in consultation with local Native Americans,				
determines that the resource is a tribal cultural resource and thus				
significant under CEQA, a mitigation plan shall be prepared and				
implemented in accordance with state guidelines and in				
consultation with local Native American group(s) prior to				
continuation of any earth disturbing work within the vicinity of the				
find. The plan shall include avoidance of the resource or, if				
avoidance of the resource is infeasible, shall outline the				
appropriate treatment of the resource in coordination with the				
appropriate local Native American tribal representative and, if				
applicable, a qualified archaeologist. Examples of appropriate				
mitigation for tribal cultural resources include, but are not limited				
to, protecting the cultural character and integrity of the resource,				
protecting traditional use of the resource, protecting the				
confidentiality of the resource, or heritage recovery.				
Utilities and Service Systems				_
Mitigation Measure UTL-1: New development generating	Prior to permit	Development	and	
wastewater flows that results in a downstream exceedance of	approval.	Engineering Servi	ces	

0.75 d/D shall construct system upgrades for those found to be	Department	
insufficient in capacity per the requirements of the Public Works		
Department. The flow shall be verified through a sewer modeling		
program during the planning and design phase, prior to		
entitlement approval. The model shall evaluate pipeline capacity,		
flow velocity, and maximum d/D ratio for normal, dry, and wet		
weather conditions.		

EDGE OF DOWNTOWN/FRONT AND JOHN STREETS MITIGATION MONITORING AND REPORTING PROGRAM

APNs 002-362-021-000, 002-362-008-000, 002-362-009-000, 002-362-015-000, 002-362-017-000, 002-362-019-000, 002-362-020-000, and 002-382-072-000

(GENERAL PLAN AMENDMENT 2022-002 AND REZONE 2022-002)

Mitigation Measures	Timing of	Responsible for Verification	Verifica Comp	ation of letion
	Verification	verilication	Date	Initials
Air Quality				
 Mitigation Measure AQ-1: Construction Air Quality. During construction, the applicant or successor in interest for each individual site shall: Limit grading to 8.1 acres per day, and limit grading and excavation to 2.2 acres per day. Provide watering trucks on site to maintain adequate soil moisture during grading and water graded/excavated areas at least twice daily, thus minimizing dust generation. In addition, the water trucks shall be used to wash down trucks and tractors, including earth loads, prior to entering public roadways. Prohibit all grading activities whenever wind speeds exceed 15 miles per hour (mph). Maintain a minimum of two feet for freeboard for all haul trucks. Cover all trucks hauling dirt, sand, or loose materials. Cover inactive storage piles. Enforce a 15-mph speed limit for all unpaved surfaces when visible dust clouds are formed by vehicle movement. Place gravel base near site entrances to clean tires prior to entering public roadways. 	During construction .	Development and Engineering Services Department – Plan Check Service		
Mitigation Measure AQ-2: MBARD Health Risk Consultation. Prior to issuance	Prior to	Development and		

of any grading permit and/or building permit for each individual site, the	issuance of	Engineering	
applicant or successor in interest shall consult with MBARD regarding the	any grading	Services	
potential need for a diesel health risk assessment (HRA). If required, the	permit	Department – Plan	
applicant or successor in interest shall prepare a diesel HRA and shall	and/or	Check Services;	
implement the measures contained therein to ensure that project-specific	building	MBARD	
emissions are below MBARD's established health risk thresholds: hazard	permit;		
index greater than 1 for acute or chronic impacts, and cancer risk greater than	during		
10 in one million for long-term operational emissions or 1 per 100,000	construction		
population for temporary construction-related emissions. Measures may			
include, but would not be limited to:			
 Use of diesel-fueled equipment equipped with Tier 4 (or Tier 3 if the 			
Tier 4 standard is unavailable) USEPA engine standards. The USEPA			
estimates that Tier 4 engines would reduce PM emissions by			
approximately 90 percent compared to the USEPA Tier 2 standards			
(USEPA 2008).			
Retrofit off-road diesel equipment with Verified Diesel Emissions			
Control Strategy (VDECS) like Diesel Particulate Filters (DPF).			
Particulate Matter level 3 VDECS can provide at least an 85 percent			
reduction (CARB 2015).			
Use alternatively fueled (e.g., natural gas) diesel construction			
equipment, including all off-road and portable diesel-powered			
equipment.			
 Use electrically driven equipment that is not powered by a portable 			
generator set.			
 Limit the hours of operation for heavy-duty equipment and/or limit the 			
quantity of heavy-duty equipment operating at the same time.			
Biological Resources			
	Not more	Davidonment and	
Mitigation Measure BIO-1: Nesting Bird Surveys and Avoidance. The Project		Development and	
shall implement the following measures to mitigate for loss of nesting habitat of	than 14	Engineering	
the Project in compliance with the federal Migratory Bird Treaty Act and	days prior to	Services	
relevant Fish and Game Codes:	vegetation	Department –	
Avoidance. In order to avoid impacts to nesting raptors and migratory	clearance.	Community	
birds, the Project will be constructed, if feasible, from September 16th		Development	
and January 31st, which is outside the avian nesting season.		Department	

 Preconstruction Surveys. If Project activities must occur during the nesting season (February 1-September 15), a qualified biologist will conduct preconstruction surveys for active raptor and migratory bird nests within 10 days prior to the start of these activities. The survey will include the proposed work area(s) and surrounding lands within 500 feet, where accessible, for all nesting raptors and migratory birds. If no active nests are found within the survey area, no further mitigation is required. Establish Buffers. Should any active nests be discovered near proposed work areas, no disturbance buffers of 250 feet around active nests of non-listed bird species and 500 feet around active nests of non-listed raptors will be established. If work needs to occur within these no disturbance buffers, a qualified biologist will monitor the nest daily for one week, and thereafter once a week, throughout the duration of construction activity. Should the nature of construction activity significantly change, such that a higher level of disturbance will be generated, monitoring will occur daily for one week and then resume the once-a-week regime. If, at any time, the biologist determines that construction activity may be compromising nesting success, construction activity within the designated buffer will be altered or suspended until the biologist determines that the nest site is no longer susceptible to deleterious disturbance. 			
Cultural Resources			
CUL-1 Historical Resources Identification and Treatment Plan Prior to permit approval for development on the Project site, a historical resources evaluation shall be completed for that individual site to confirm if existing buildings and/or structures withing these sites qualify as historical resources as defined by Section 15064.5(a) of CEQA Guidelines. The evaluation shall be prepared by a qualified architectural historian or historian who meets the Secretary of the Interior's Professional Qualifications Standards (PQS) in architectural history or history. The qualified architectural historian or historian shall conduct an intensive-level evaluation in accordance with the guidelines and best practices promulgated by the State Office of Historic Preservation to identify any potential historical resources within the proposed	Prior to permit approval.	Development and Engineering Services Department – Community Development Department	

	1	1	1	
project area. All properties 45 years of age or older shall be evaluated within				
their historic context and documented in a report meeting the State Office of				
Historic Preservation guidelines. All evaluated properties shall be documented				
on Department of Parks and Recreation Series 523 Forms. The report shall be				
submitted to the City for review and concurrence.				
Any relocation, rehabilitation, or alteration of the resource shall be				
implemented consistent with the Secretary of the Interior's Standards for the				
Treatments of Historic Properties (Standards). In accordance with CEQA, a				
project that has been determined to conform with the Standards generally				
would not cause a significant adverse direct or indirect impact to historical				
resources (14 CCR Section 15126.4[b][1]). Application of the Standards shall				
be overseen by a qualified architectural historian or historic architect meeting				
the PQS. In conjunction with any development application that may affect the				
historical resource, a report identifying and specifying the treatment of				
character-defining features and construction activities shall be provided to the				
City for review and concurrence, in addition to the historical resources				
evaluation.				
If significant historical resources are identified on a development site and				
compliance with the Standards and or avoidance is not feasible, the applicant				
or developer shall provide a report explaining why compliance with the				
Standards and or avoidance is not feasible for the City's review and approval.				
Site-specific mitigation measures shall be established and undertaken,				
including, but not limited to, documentation of the historical resource in the				
form of a Historic American Buildings Survey-Like report. The report shall be				
commissioned by the project applicant or their consultant to comply with the				
Secretary of the Interior's Standards for Architectural and Engineering				
Documentation and shall generally follow the Historic American Buildings				
Survey Level III requirements, including digital photographic recordation,				
detailed historic narrative report, and compilation of historic research. The				
documentation shall be completed by a qualified architectural historian or				
historian who meets the PQS and submitted to the City prior to issuance of any				
permits for demolition or alteration of the historical resource.				
Mitigation Measure CUL-2 Phase I Cultural Resources Study	Prior to	Development and		
Prior to the issuance of any grading or construction permits for each individual	issuance of	Engineering		

site, a Phase I cultural resources study shall be performed by a qualified professional meeting the Secretary of the Interior's (SOI's) Professional Qualification Standards (PQS) for archaeology (National Park Service 1983). The Phase I cultural resources study shall include a pedestrian survey of the project site when appropriate and sufficient background research and field sampling to determine whether archaeological resources may be present. Archival research shall include a records search of the Northwest Information Center (NWIC) no more than two years old and a Sacred Lands File search with the NAHC. The Phase I technical report documenting the study shall include recommendations that shall be implemented prior to and/or during construction to avoid or reduce impacts to archaeological resources. Recommendations may include, but would not be limited to, archaeological construction monitoring, sensitivity training, or additional testing and mitigation (outlined in Mitigation Measures CUL-3 through CUL-7). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The City shall include recommendations in the Phase I technical report as Conditions of Approval to be implemented throughout all ground disturbance activities. The final report shall be submitted to the NWIC.	grading or construction permits.	Services Department – Community Development Department	
Mitigation Measure CUL-3 Extended Phase I Testing If recommended by the Phase I study for each individual site (Mitigation Measure CUL-2), the project applicant shall retain a qualified archaeologist to conduct an Extended Phase I (XPI) study to determine the presence/absence and extent of archaeological resources on the project site. XPI testing shall include a series of shovel test pits and/or hand augured units and/or mechanical trenching to establish the boundaries of archaeological site(s) on the project site. If the boundaries of the archaeological site are already well understood from previous archaeological work, an XPI will not be required. All archaeological excavation shall be conducted by a qualified archaeologist(s) under the direction of a principal investigator meeting the SOI's PQS for archaeology (National Park Service 1983). If an XPI report is prepared, it shall be submitted to the City for review and approval prior to the issuance of a grading or construction permit. Recommendations therein shall be implemented for all ground disturbance activities. Recommendations may	Prior to the issuance of a grading or construction permit.	Development and Engineering Services Department – Community Development Department	

include, but would not be limited to, site avoidance, Phase II Site Evaluation, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-4, CUL-5, CUL-7, and CUL-8). The final report shall be submitted to the NWIC.			
Mitigation Measure CUL-4 Archaeological Site Avoidance Any identified archaeological sites (determined after implementing Mitigation Measures CUL-2 and/or CUL-3) or archaeological resources encountered during ground-disturbing activities shall be avoided by project-related construction activities, where feasible. A barrier (temporary fencing) and flagging shall be placed between the work location and any resources within 60 feet of a work location to minimize the potential for inadvertent impacts. If the resource cannot be avoided, Mitigation Measure CUL-5 shall be implemented.	During construction .	Development and Engineering Services Department – Community Development Department	
Mitigation Measure CUL-5 Phase II Site Evaluation If the results of any Phase I and/or XPI for each individual site (Mitigation Measures CUL-2 and/or CUL-3) indicate the presence of archaeological resources that cannot be avoided by the project (Mitigation Measure CUL-4) and that have not been adequately evaluated for the NRHP or CRHR listing at the project site, the qualified archaeologist shall conduct a Phase II investigation to determine if intact deposits remain and if they may be eligible for the CRHR or qualify as unique archaeological resources. If the archaeological resource(s) of concern are Native American in origin, the qualified archaeologist shall confer with the City and local California Native American tribe(s). A Phase I evaluation shall include any necessary archival research to identify significant historical associations and mapping of surface artifacts, collection of functionally or temporally diagnostic tools and debris, and excavation of a sample of the cultural deposit. The sample excavation would be carried out to characterize the nature of the site(s), define the artifact and feature contents, determine horizontal and vertical boundaries, and retrieve representative samples of artifacts and other remains. If the archaeologist and, if applicable, a Native American monitor or other interested tribal representative determine it is appropriate, cultural materials collected from the site shall be processed and analyzed in a laboratory	During construction .	Development and Engineering Services Department – Community Development Department	

	1		, , , , , , , , , , , , , , , , , , , ,	
according to standard archaeological procedures. The age of the materials shall be determined using radiocarbon dating and/or other appropriate procedures; lithic artifacts, faunal remains, and other cultural materials shall be identified and analyzed according to current professional standards. The significance of the site(s) shall be evaluated according to the criteria of the CRHR and if applicable, NRHP. The results of the investigations shall be presented in a technical report following the standards of the California Office of Historic Preservation publication "Archaeological Resource Management Reports: Recommended Content and Format (1990 or latest edition)." Recommendations in the Phase II report shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, Phase III Data Recovery, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-6 through CUL-8). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The final report shall be submitted to the NWIC.				
Mitigation Measure CUL-6 Phase III Data Recovery Should the results of the Phase II site evaluation for each individual site (Mitigation Measure CUL-5) yield resources that meet CRHR significance standards and if the resource cannot be avoided by project construction in accordance with CUL-4, the project applicant shall ensure that all feasible recommendations for mitigation of archaeological impacts are incorporated into the final design and approved by the City prior to construction. Any necessary Phase III data recovery excavation, conducted to exhaust the data potential of significant archaeological sites, shall be carried out by a qualified archaeologist meeting the SOI's PQS for archeology (National Park Service 1983). Data recovery shall be conducted in accordance with a research design reviewed and approved by the City, prepared in advance of fieldwork, and using the appropriate archaeological field and laboratory methods consistent with the California Office of Historic Preservation Planning Bulletin 5 (1991), Guidelines for Archaeological Research Design, or the latest edition thereof. If the archaeological resource(s) of concern are Native American in origin, the qualified archaeologist shall confer with the City and local California Native American tribe(s).	During construction .	Development and Engineering Services Department – Community Development Department		

As applicable, the final Phase III Data Recovery reports shall be submitted to	
	ļ
the City prior to issuance of any grading or construction permit.	ļ
Recommendations contained therein shall be implemented throughout all	
ground disturbance activities. Recommendations may include, but would not	
be limited to, Cultural Resources Monitoring, and/or measures for	
unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8).	Ų
The final report shall be submitted to the NWIC upon completion.	
Mitigation Measure CUL-7 Cultural Resources Monitoring During Development and	Ų
If recommended by Phase I, XPI, Phase II, or Phase III studies for each construction Engineering	
individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the Services	Ų
project applicant shall retain a qualified archaeologist to monitor project- Department –	Ų
related, ground-disturbing activities which may include the following but not Community	ļ
limited to: grubbing, vegetation removal, trenching, grading, and/or Development	ļ
excavations. The archaeological monitor shall coordinate with any Native Department	ļ
American monitor as required. Monitoring logs must be completed by the	ļ
archaeologist daily. Cultural resources monitoring may be reduced for the	ļ
project if the qualified archaeologist finds it appropriate to reduce the	ļ
monitoring efforts. Upon completion of ground disturbance for the project, a	ļ
final report must be submitted to the City for review and approval documenting	ļ
the monitoring efforts, cultural resources find, and resource disposition. The	ļ
final report shall be submitted to the NWIC.	ļ
Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources During Development and	
If archaeological resources are encountered during ground-disturbing construction Engineering	ļ
activities, work within 50 feet shall be halted and the project archaeologist . Services	Ų
meeting the SOI's PQS for archeology (National Park Service 1983) shall Department –	ļ
immediately to evaluate the find pursuant to Public Resources Code Section Community	ļ
21083.2. If necessary, the evaluation may require preparation of a treatment Development	ļ
plan and archaeological testing for CRHR eligibility. If the discovery proves to Department	ļ
be significant under CEQA and cannot be avoided by the project, additional	ļ
work may be warranted, such as data recovery excavation, to mitigate any	ļ
significant impacts to significant resources. If the resource is of Native	ļ
American origin, implementation of Mitigation Measures TCR-1 may be	ļ
required. Any reports required to document and/or evaluate unanticipated	ļ
discoveries shall be submitted to the City for review and approval and	I.

	1	T	1	
submitted to the NWIC after completion. Recommendations contained therein				
shall be implemented throughout the remainder of ground disturbance				
activities.				
Greenhouse Gas Emissions				
Mitigation Measure GHG-1: Future development shall install EV charging	Prior to	Development and		
infrastructure according to the most ambitious voluntary standard in the	permit	Engineering		
California Green Building Standards Code at the time of project approval.	approval.	Services		
	''	Department –		
		Community		
		Development		
		Department		
Mitigation Measure GHG-2: Future development shall provide no more parking	Prior to	Development and		
spaces than the off-street parking requirements established in the City of	permit	Engineering		
Salinas Municipal Code. Alternatively, multi-family residential development can		Services		
choose to unbundle parking costs with costs to rent or own a residential unit	аррготан.	Department –		
instead of meeting the maximum off-parking requirement.		Community		
instead of meeting the maximum on-parking requirement.		Development		
		Department		
		Department		
Noise				
Mitigation Measure NOI-1: Prior to ground disturbing activities, the City of	During	Development and		
Salinas shall ensure the following with the Project proponent:	construction	Engineering		
	CONSTRUCTION	Services		
Construction equipment, fixed of mobile, shall be outfitted with properly	•			
operating and maintained mufflers.		Department –		
Construction noise reduction methods such as shutting off idling		Community		
equipment, installing temporary acoustic barriers around stationary		Development		
construction noise sources, maximizing the distance between		Department.		
construction equipment staging areas and occupied residential areas,				
and using electric air compressors and similar power tools rather than				
diesel equipment shall be used.				
 During construction, stationary construction equipment shall be located 				
so that emitted noise is directed away from or shielded from sensitive				
noise receivers.				
1				

	I	· _ · · · · · · · · · · · · · · · · · ·	I
feet of existing structures shall be prohibited.	construction	Engineering	
	•	Services	
		Department –	
		Community	
		Development	
		Department.	
Transportation	<u> </u>	•	1
Mitigation Measure TRANS-1: To maintain safety standards at all intersections	Prior to	Development and	
and roadway segments pursuant to implementation actions identified in the	permit	Engineering	
Vision Zero Action Plan, a traffic impact study shall be required for all	approval.	Services	
development projects anticipated to generate 110 or more new daily vehicle	GP 1 C 1 G 1	Department –	
trips within the Project Area, unless not required by the City. Depending on the		Traffic Engineering	
results of this study, future developments may be required to construct or		and Plan Check	
contribute to street safety improvements to meet the demand generated by the		Services	
project. Improvements shall be in accordance with the City of Salinas' Vision		Gervices	
Zero Action Plan (i.e. pedestrian-activated crosswalk warning beacon, high			
visibility crosswalks, pedestrian hybrid beacon, reduced parking at intersection,			
intersection control, raised median and street trees, protected bike lanes, and			
lane reduction). These improvements shall be required as conditions of			
approval.			
Tribal Cultural Resources	T	1	1
Mitigation Measure TCR-1 Inadvertent Discoveries During Construction	During	Development and	
In the event that cultural resources of Native American origin are identified	construction	Engineering	
during grading or construction, all earth disturbing work within the vicinity of the		Services	
find shall be temporarily suspended or redirected until a qualified archaeologist		Department –	
has evaluated the nature and significance of the find; an appropriate Native		Community	
American representative, based on the nature of the find, is consulted; and		Development	
mitigation measures are put in place for the disposition and protection of any		Department.	
find pursuant to Public Resources Code Section 21083.2. If the City, in		•	
consultation with local Native Americans, determines that the resource is a			
tribal cultural resource and thus significant under CEQA, a mitigation plan shall			
be prepared and implemented in accordance with state guidelines and in			
consultation with local Native American group(s) prior to continuation of any			
earth disturbing work within the vicinity of the find. The plan shall include			
carti distribing work within the violinty of the find. The plan shall include			

avoidance of the resource or, if avoidance of the resource is infeasible, shall outline the appropriate treatment of the resource in coordination with the appropriate local Native American tribal representative and, if applicable, a qualified archaeologist. Examples of appropriate mitigation for tribal cultural resources include, but are not limited to, protecting the cultural character and integrity of the resource, protecting traditional use of the resource, protecting the confidentiality of the resource, or heritage recovery. Utilities and Service Systems			
Mitigation Measure UTL-1: New development generating wastewater flows that results in a downstream exceedance of 0.75 d/D shall construct system upgrades for those found to be insufficient in capacity per the requirements of the Public Works Department. The flow shall be verified through a sewer modeling program during the planning and design phase, prior to entitlement approval. The model shall evaluate pipeline capacity, flow velocity, and maximum d/D ratio for normal, dry, and wet weather conditions.	Prior to permit approval.	Development and Engineering Services Department	

FOODS CO SHOPPING CENTER MITIGATION MONITORING AND REPORTING PROGRAM

APNs 003-894-005-000, 003-894-006-000, 003-891-014-000, 003-891-015-000, 003-891-016-000, 003-891-017-000, 003-891-018-000, and 003-891-019-000

(GENERAL PLAN AMENDMENT 2022-002 AND REZONE 2022-002)

Mitigation Measures	Timing of Verification	Responsible for Verification	Verifica Comp	
	verillication	verincation	Date	Initials
Air Quality				
 Mitigation Measure AQ-1: Construction Air Quality. During construction, the applicant or successor in interest for each individual site shall: Limit grading to 8.1 acres per day, and limit grading and excavation to 2.2 acres per day. Provide watering trucks on site to maintain adequate soil moisture during grading and water graded/excavated areas at least twice daily, thus minimizing dust generation. In addition, the water trucks shall be used to wash down trucks and tractors, including earth loads, prior to entering public roadways. Prohibit all grading activities whenever wind speeds exceed 15 miles per hour (mph). Maintain a minimum of two feet for freeboard for all haul trucks. Cover all trucks hauling dirt, sand, or loose materials. Cover inactive storage piles. Enforce a 15-mph speed limit for all unpaved surfaces when visible dust clouds are formed by vehicle movement. Place gravel base near site entrances to clean tires prior to entering public roadways. 	During construction .	Development and Engineering Services Department – Plan Check Service		
Mitigation Measure AQ-2: MBARD Health Risk Consultation. Prior to issuance	Prior to	Development and		

of any grading permit and/or building permit for each individual site, the applicant or successor in interest shall consult with MBARD regarding the potential need for a diesel health risk assessment (HRA). If required, the applicant or successor in interest shall prepare a diesel HRA and shall implement the measures contained therein to ensure that project-specific emissions are below MBARD's established health risk thresholds: hazard index greater than 1 for acute or chronic impacts, and cancer risk greater than 10 in one million for long-term operational emissions or 1 per 100,000 population for temporary construction-related emissions. Measures may include, but would not be limited to: • Use of diesel-fueled equipment equipped with Tier 4 (or Tier 3 if the Tier 4 standard is unavailable) USEPA engine standards. The USEPA estimates that Tier 4 engines would reduce PM emissions by approximately 90 percent compared to the USEPA Tier 2 standards (USEPA 2008). • Retrofit off-road diesel equipment with Verified Diesel Emissions	issuance of any grading permit and/or building permit; during construction	Engineering Services Department – Plan Check Services; MBARD		
Control Strategy (VDECS) like Diesel Particulate Filters (DPF). Particulate Matter level 3 VDECS can provide at least an 85 percent reduction (CARB 2015).				
Use alternatively fueled (e.g., natural gas) diesel construction equipment, including all off-road and portable diesel-powered equipment.				
Use electrically driven equipment that is not powered by a portable generator set.				
Limit the hours of operation for heavy-duty equipment and/or limit the				
quantity of heavy-duty equipment operating at the same time.				
Biological Resources	N	D	T	
Mitigation Measure BIO-1: Nesting Bird Surveys and Avoidance. The Project	Not more	Development and		
shall implement the following measures to mitigate for loss of nesting habitat of	than 14	Engineering		
the Project in compliance with the federal Migratory Bird Treaty Act and relevant Fish and Game Codes:	days prior to	Services		
	vegetation	Department –		
Avoidance. In order to avoid impacts to nesting raptors and migratory hirds the Project will be constructed if feedible from Sentember 16th.	clearance.	Community		
birds, the Project will be constructed, if feasible, from September 16th		Development		
and January 31st, which is outside the avian nesting season.		Department		

 Preconstruction Surveys. If Project activities must occur during the nesting season (February 1-September 15), a qualified biologist will conduct preconstruction surveys for active raptor and migratory bird nests within 10 days prior to the start of these activities. The survey will include the proposed work area(s) and surrounding lands within 500 feet, where accessible, for all nesting raptors and migratory birds. If no active nests are found within the survey area, no further mitigation is required. Establish Buffers. Should any active nests be discovered near proposed work areas, no disturbance buffers of 250 feet around active nests of non-listed bird species and 500 feet around active nests of non-listed raptors will be established. If work needs to occur within these no disturbance buffers, a qualified biologist will monitor the nest daily for one week, and thereafter once a week, throughout the duration of construction activity. Should the nature of construction activity significantly change, such that a higher level of disturbance will be generated, monitoring will occur daily for one week and then resume the once-a-week regime. If, at any time, the biologist determines that construction activity may be compromising nesting success, construction activity within the designated buffer will be altered or suspended until the biologist determines that the nest site is no longer susceptible to deleterious disturbance. 			
Cultural Resources	I.		
CUL-1 Historical Resources Identification and Treatment Plan Prior to permit approval for development on the Project site, a historical resources evaluation shall be completed for that individual site to confirm if existing buildings and/or structures withing these sites qualify as historical resources as defined by Section 15064.5(a) of CEQA Guidelines. The evaluation shall be prepared by a qualified architectural historian or historian who meets the Secretary of the Interior's Professional Qualifications Standards (PQS) in architectural history or history. The qualified architectural historian or historian shall conduct an intensive-level evaluation in accordance with the guidelines and best practices promulgated by the State Office of Historic Preservation to identify any potential historical resources within the proposed	Prior to permit approval.	Development and Engineering Services Department – Community Development Department	

	1		,	1
project area. All properties 45 years of age or older shall be evaluated within				
their historic context and documented in a report meeting the State Office of				
Historic Preservation guidelines. All evaluated properties shall be documented				
on Department of Parks and Recreation Series 523 Forms. The report shall be				
submitted to the City for review and concurrence.				
Any relocation, rehabilitation, or alteration of the resource shall be				
implemented consistent with the Secretary of the Interior's Standards for the				
Treatments of Historic Properties (Standards). In accordance with CEQA, a				
project that has been determined to conform with the Standards generally				
would not cause a significant adverse direct or indirect impact to historical				
resources (14 CCR Section 15126.4[b][1]). Application of the Standards shall				
be overseen by a qualified architectural historian or historic architect meeting				
the PQS. In conjunction with any development application that may affect the				
historical resource, a report identifying and specifying the treatment of				
character-defining features and construction activities shall be provided to the				
City for review and concurrence, in addition to the historical resources				
evaluation.				
If significant historical resources are identified on a development site and				
compliance with the Standards and or avoidance is not feasible, the applicant				
or developer shall provide a report explaining why compliance with the				
Standards and or avoidance is not feasible for the City's review and approval.				
Site-specific mitigation measures shall be established and undertaken,				
including, but not limited to, documentation of the historical resource in the				
form of a Historic American Buildings Survey-Like report. The report shall be				
commissioned by the project applicant or their consultant to comply with the				
Secretary of the Interior's Standards for Architectural and Engineering				
Documentation and shall generally follow the Historic American Buildings				
Survey Level III requirements, including digital photographic recordation,				
detailed historic narrative report, and compilation of historic research. The				
documentation shall be completed by a qualified architectural historian or				
historian who meets the PQS and submitted to the City prior to issuance of any				
permits for demolition or alteration of the historical resource.				
Mitigation Measure CUL-2 Phase I Cultural Resources Study	Prior to	Development and		
Prior to the issuance of any grading or construction permits for each individual	issuance of	Engineering		
. The tree is a security of any grading of sentendent permits for saon marviadar	100001100 01			

site, a Phase I cultural resources study shall be performed by a qualified professional meeting the Secretary of the Interior's (SOI's) Professional Qualification Standards (PQS) for archaeology (National Park Service 1983). The Phase I cultural resources study shall include a pedestrian survey of the project site when appropriate and sufficient background research and field sampling to determine whether archaeological resources may be present. Archival research shall include a records search of the Northwest Information Center (NWIC) no more than two years old and a Sacred Lands File search with the NAHC. The Phase I technical report documenting the study shall include recommendations that shall be implemented prior to and/or during construction to avoid or reduce impacts to archaeological resources. Recommendations may include, but would not be limited to, archaeological construction monitoring, sensitivity training, or additional testing and mitigation (outlined in Mitigation Measures CUL-3 through CUL-7). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The City shall include recommendations in the Phase I technical report as Conditions of Approval to be implemented throughout all ground disturbance activities. The final report shall be submitted to the NWIC.	grading or construction permits.	Services Department – Community Development Department	
Mitigation Measure CUL-3 Extended Phase I Testing If recommended by the Phase I study for each individual site (Mitigation Measure CUL-2), the project applicant shall retain a qualified archaeologist to conduct an Extended Phase I (XPI) study to determine the presence/absence and extent of archaeological resources on the project site. XPI testing shall include a series of shovel test pits and/or hand augured units and/or mechanical trenching to establish the boundaries of archaeological site(s) on the project site. If the boundaries of the archaeological site are already well understood from previous archaeological work, an XPI will not be required. All archaeological excavation shall be conducted by a qualified archaeologist(s) under the direction of a principal investigator meeting the SOI's PQS for archaeology (National Park Service 1983). If an XPI report is prepared, it shall be submitted to the City for review and approval prior to the issuance of a grading or construction permit. Recommendations therein shall be implemented for all ground disturbance activities. Recommendations may	Prior to the issuance of a grading or construction permit.	Development and Engineering Services Department – Community Development Department	

include, but would not be limited to, site avoidance, Phase II Site Evaluation, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-4, CUL-5, CUL-7, and CUL-8). The final report shall be submitted to the NWIC.			
Mitigation Measure CUL-4 Archaeological Site Avoidance Any identified archaeological sites (determined after implementing Mitigation Measures CUL-2 and/or CUL-3) or archaeological resources encountered during ground-disturbing activities shall be avoided by project-related construction activities, where feasible. A barrier (temporary fencing) and flagging shall be placed between the work location and any resources within 60 feet of a work location to minimize the potential for inadvertent impacts. If the resource cannot be avoided, Mitigation Measure CUL-5 shall be implemented.	During construction .	Development and Engineering Services Department – Community Development Department	
Mitigation Measure CUL-5 Phase II Site Evaluation If the results of any Phase I and/or XPI for each individual site (Mitigation Measures CUL-2 and/or CUL-3) indicate the presence of archaeological resources that cannot be avoided by the project (Mitigation Measure CUL-4) and that have not been adequately evaluated for the NRHP or CRHR listing at the project site, the qualified archaeologist shall conduct a Phase II investigation to determine if intact deposits remain and if they may be eligible for the CRHR or qualify as unique archaeological resources. If the archaeological resource(s) of concern are Native American in origin, the qualified archaeologist shall confer with the City and local California Native American tribe(s). A Phase I evaluation shall include any necessary archival research to identify significant historical associations and mapping of surface artifacts, collection of functionally or temporally diagnostic tools and debris, and excavation of a sample of the cultural deposit. The sample excavation would be carried out to characterize the nature of the site(s), define the artifact and feature contents, determine horizontal and vertical boundaries, and retrieve representative samples of artifacts and other remains. If the archaeologist and, if applicable, a Native American monitor or other interested tribal representative determine it is appropriate, cultural materials collected from the site shall be processed and analyzed in a laboratory	During construction .	Development and Engineering Services Department – Community Development Department	

according to standard archaeological procedures. The age of the materials	
shall be determined using radiocarbon dating and/or other appropriate	
procedures; lithic artifacts, faunal remains, and other cultural materials shall be	
identified and analyzed according to current professional standards. The	
significance of the site(s) shall be evaluated according to the criteria of the	
CRHR and if applicable, NRHP. The results of the investigations shall be	
presented in a technical report following the standards of the California Office	
of Historic Preservation publication "Archaeological Resource Management	
Reports: Recommended Content and Format (1990 or latest edition)."	
Recommendations in the Phase II report shall be implemented for all ground	
disturbance activities. Recommendations may include, but would not be limited	
to, Phase III Data Recovery, Cultural Resources Monitoring, and/or measures	
for unanticipated discoveries (outlined in Mitigation Measures CUL-6 through	
CUL-8). The report shall be submitted to the City for review and approval prior	
to the issuance of any grading or construction permits. The final report shall be	
submitted to the NWIC.	
Mitigation Measure CUL-6 Phase III Data Recovery During Development and	
Should the results of the Phase II site evaluation for each individual site construction Engineering	
(Mitigation Measure CUL-5) yield resources that meet CRHR significance . Services	
standards and if the resource cannot be avoided by project construction in Department –	
accordance with CUL-4, the project applicant shall ensure that all feasible Community	
recommendations for mitigation of archaeological impacts are incorporated into Development	
the final design and approved by the City prior to construction. Any necessary Department	
Phase III data recovery excavation, conducted to exhaust the data potential of	
significant archaeological sites, shall be carried out by a qualified archaeologist	
meeting the SOI's PQS for archeology (National Park Service 1983). Data	
recovery shall be conducted in accordance with a research design reviewed	
and approved by the City, prepared in advance of fieldwork, and using the	
appropriate archaeological field and laboratory methods consistent with the	
California Office of Historic Preservation Planning Bulletin 5 (1991), Guidelines	
for Archaeological Research Design, or the latest edition thereof. If the	
archaeological resource(s) of concern are Native American in origin, the	
qualified archaeologist shall confer with the City and local California Native	
American tribe(s).	

he City prior to issuance of any grading or construction permit. Recommendations contained therein shall be implemented throughout all ground disturbance activities. Recommendations may include, but would not be limited to, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8). The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase II, Striphase II, Stri				
Recommendations contained therein shall be implemented throughout all ground disturbance activities. Recommendations may include, but would not be limited to, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8). The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery execavation, to mitigate any significant inder CEQ	As applicable, the final Phase III Data Recovery reports shall be submitted to			
ground disturbance activities. Recommendations may include, but would not be limited to, Cultural Resources Monitoring, and/or measures CUL-7 and CUL-8). The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to docume				
be limited to, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8). The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources II archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated				
unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8). The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated				
The final report shall be submitted to the NWIC upon completion. Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	be limited to, Cultural Resources Monitoring, and/or measures for			
Mitigation Measure CUL-7 Cultural Resources Monitoring If recommended by Phase I, XPI, Phase II, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project- related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8).			
If recommended by Phase I, XPI, Phase III, or Phase III studies for each individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's POS for archaeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEOA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	The final report shall be submitted to the NWIC upon completion.			
individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the project applicant shall retain a qualified archaeologist to monitor project-related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report shall be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeologiscal resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologis meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	Mitigation Measure CUL-7 Cultural Resources Monitoring	During	Development and	
project applicant shall retain a qualified archaeologist to monitor project- related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	If recommended by Phase I, XPI, Phase II, or Phase III studies for each	construction	Engineering	
related, ground-disturbing activities which may include the following but not limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the		Services	
limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOl's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	project applicant shall retain a qualified archaeologist to monitor project-		Department –	
limited to: grubbing, vegetation removal, trenching, grading, and/or excavations. The archaeological monitor shall coordinate with any Native American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOl's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated			Community	
American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated			Development	
American monitor as required. Monitoring logs must be completed by the archaeologist daily. Cultural resources monitoring may be reduced for the project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	excavations. The archaeological monitor shall coordinate with any Native		Department	
project if the qualified archaeologist finds it appropriate to reduce the monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	American monitor as required. Monitoring logs must be completed by the		·	
monitoring efforts. Upon completion of ground disturbance for the project, a final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	archaeologist daily. Cultural resources monitoring may be reduced for the			
final report must be submitted to the City for review and approval documenting the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	project if the qualified archaeologist finds it appropriate to reduce the			
the monitoring efforts, cultural resources find, and resource disposition. The final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated				
final report shall be submitted to the NWIC. Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	final report must be submitted to the City for review and approval documenting			
Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	the monitoring efforts, cultural resources find, and resource disposition. The			
If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	final report shall be submitted to the NWIC.			
If archaeological resources are encountered during ground-disturbing activities, work within 50 feet shall be halted and the project archaeologist meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources	During	Development and	
meeting the SOI's PQS for archeology (National Park Service 1983) shall immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	If archaeological resources are encountered during ground-disturbing	construction	Engineering	
immediately to evaluate the find pursuant to Public Resources Code Section 21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	activities, work within 50 feet shall be halted and the project archaeologist		Services	
21083.2. If necessary, the evaluation may require preparation of a treatment plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	meeting the SOI's PQS for archeology (National Park Service 1983) shall		Department –	
plan and archaeological testing for CRHR eligibility. If the discovery proves to be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	immediately to evaluate the find pursuant to Public Resources Code Section		Community	
be significant under CEQA and cannot be avoided by the project, additional work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	21083.2. If necessary, the evaluation may require preparation of a treatment		Development	
work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated	plan and archaeological testing for CRHR eligibility. If the discovery proves to		Department	
work may be warranted, such as data recovery excavation, to mitigate any significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated			-	
significant impacts to significant resources. If the resource is of Native American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated				
American origin, implementation of Mitigation Measures TCR-1 may be required. Any reports required to document and/or evaluate unanticipated				
required. Any reports required to document and/or evaluate unanticipated				
	discoveries shall be submitted to the City for review and approval and			

submitted to the NWIC after completion. Recommendations contained therein shall be implemented throughout the remainder of ground disturbance activities.			
Greenhouse Gas Emissions			
Mitigation Measure GHG-1: Future development shall install EV charging infrastructure according to the most ambitious voluntary standard in the California Green Building Standards Code at the time of project approval.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department	
Mitigation Measure GHG-2: Future development shall provide no more parking spaces than the off-street parking requirements established in the City of Salinas Municipal Code. Alternatively, multi-family residential development can choose to unbundle parking costs with costs to rent or own a residential unit instead of meeting the maximum off-parking requirement.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department	
Hydrology and Water Quality			
Mitigation Measure HYD-1: Future Development projects on the subject site that would demand an amount of water equivalent to, or greater than, the amount of water required by a 500-dwelling unit project are required to prepare a Water Supply Assessment.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department	
Noise			
Mitigation Measure NOI-1: Prior to ground disturbing activities, the City of Salinas shall ensure the following with the Project proponent: • Construction equipment, fixed of mobile, shall be outfitted with properly operating and maintained mufflers. • Construction noise reduction methods such as shutting off idling	During construction	Development and Engineering Services Department – Community	

 equipment, installing temporary acoustic barriers around stationary construction noise sources, maximizing the distance between construction equipment staging areas and occupied residential areas, and using electric air compressors and similar power tools rather than diesel equipment shall be used. During construction, stationary construction equipment shall be located so that emitted noise is directed away from or shielded from sensitive noise receivers. 		Development Department.	
Mitigation Measure NOI-2: The use of heavy construction equipment within 25 feet of existing structures shall be prohibited.	During construction .	Development and Engineering Services Department – Community Development Department.	
Transportation			
Mitigation Measure TRANS-1: To maintain safety standards at all intersections and roadway segments pursuant to implementation actions identified in the Vision Zero Action Plan, a traffic impact study shall be required for all development projects anticipated to generate 110 or more new daily vehicle trips within the Project Area, unless not required by the City. Depending on the results of this study, future developments may be required to construct or contribute to street safety improvements to meet the demand generated by the project. Improvements shall be in accordance with the City of Salinas' Vision Zero Action Plan (i.e. pedestrian-activated crosswalk warning beacon, high visibility crosswalks, pedestrian hybrid beacon, reduced parking at intersection, intersection control, raised median and street trees, protected bike lanes, and lane reduction). These improvements shall be required as conditions of approval.	Prior to permit approval.	Development and Engineering Services Department – Traffic Engineering and Plan Check Services	
Tribal Cultural Resources	T		
Mitigation Measure TCR-1 Inadvertent Discoveries During Construction In the event that cultural resources of Native American origin are identified during grading or construction, all earth disturbing work within the vicinity of the find shall be temporarily suspended or redirected until a qualified archaeologist	During construction	Development and Engineering Services Department –	

	has evaluated the nature and significance of the find; an appropriate Native American representative, based on the nature of the find, is consulted; and mitigation measures are put in place for the disposition and protection of any find pursuant to Public Resources Code Section 21083.2. If the City, in consultation with local Native Americans, determines that the resource is a tribal cultural resource and thus significant under CEQA, a mitigation plan shall be prepared and implemented in accordance with state guidelines and in consultation with local Native American group(s) prior to continuation of any earth disturbing work within the vicinity of the find. The plan shall include avoidance of the resource or, if avoidance of the resource is infeasible, shall outline the appropriate treatment of the resource in coordination with the appropriate local Native American tribal representative and, if applicable, a qualified archaeologist. Examples of appropriate mitigation for tribal cultural resources include, but are not limited to, protecting the cultural character and integrity of the resource, protecting traditional use of the resource, protecting the confidentiality of the resource, or heritage recovery.		Community Development Department.	
Ī	Utilities and Service Systems			
	Mitigation Measure UTL-1: New development generating wastewater flows that results in a downstream exceedance of 0.75 d/D shall construct system	Prior to permit	Development and Engineering	
	upgrades for those found to be insufficient in capacity per the requirements of	approval.	Services	
	the Public Works Department. The flow shall be verified through a sewer		Department	
	modeling program during the planning and design phase, prior to entitlement			
	approval. The model shall evaluate pipeline capacity, flow velocity, and			
	maximum d/D ratio for normal, dry, and wet weather conditions.			

LAUREL WEST SHOPPING CENTER MITIGATION MONITORING AND REPORTING PROGRAM

APNs 261-711-037-000, 261-711-070-000, 261-711-065-000, 261-711-024-000, 261-711-017-000, and 261-711-025-000 (GENERAL PLAN AMENDMENT 2022-002 AND REZONE 2022-002)

Mitigation Measures	Timing of	Responsible for	Verification of Completion	
	Verification	Verification	Date	Initials
Air Quality				
 Mitigation Measure AQ-1: Construction Air Quality. During construction, the applicant or successor in interest for each individual site shall: Limit grading to 8.1 acres per day, and limit grading and excavation to 2.2 acres per day. Provide watering trucks on site to maintain adequate soil moisture during grading and water graded/excavated areas at least twice daily, thus minimizing dust generation. In addition, the water trucks shall be used to wash down trucks and tractors, including earth loads, prior to entering public roadways. Prohibit all grading activities whenever wind speeds exceed 15 miles per hour (mph). Maintain a minimum of two feet for freeboard for all haul trucks. Cover all trucks hauling dirt, sand, or loose materials. Cover inactive storage piles. Enforce a 15-mph speed limit for all unpaved surfaces when visible dust clouds are formed by vehicle movement. 	During construction .	Development and Engineering Services Department – Plan Check Service		
 Place gravel base near site entrances to clean tires prior to entering public roadways. 				
Mitigation Measure AQ-2: MBARD Health Risk Consultation. Prior to issuance of any grading permit and/or building permit for each individual site, the	Prior to issuance of	Development and Engineering		

applicant or successor in interest shall consult with MBARD regarding the any grading Services
potential need for a diesel health risk assessment (HRA). If required, the permit Department – Plan
applicant or successor in interest shall prepare a diesel HRA and shall and/or Check Services;
implement the measures contained therein to ensure that project-specific building MBARD
emissions are below MBARD's established health risk thresholds: hazard permit;
index greater than 1 for acute or chronic impacts, and cancer risk greater than during
10 in one million for long-term operational emissions or 1 per 100,000 construction
population for temporary construction-related emissions. Measures may
include, but would not be limited to:
Use of diesel-fueled equipment equipped with Tier 4 (or Tier 3 if the
Tier 4 standard is unavailable) USEPA engine standards. The USEPA
estimates that Tier 4 engines would reduce PM emissions by
approximately 90 percent compared to the USEPA Tier 2 standards
(USEPA 2008).
Retrofit off-road diesel equipment with Verified Diesel Emissions
Control Strategy (VDECS) like Diesel Particulate Filters (DPF).
Particulate Matter level 3 VDECS can provide at least an 85 percent
reduction (CARB 2015).
Use alternatively fueled (e.g., natural gas) diesel construction
equipment, including all off-road and portable diesel-powered
equipment.
Use electrically driven equipment that is not powered by a portable
generator set.
Limit the hours of operation for heavy-duty equipment and/or limit the
quantity of heavy-duty equipment operating at the same time.
Biological Resources
Mitigation Measure BIO-1: Nesting Bird Surveys and Avoidance. The Project Not more Development and
shall implement the following measures to mitigate for loss of nesting habitat of than 14 Engineering
the Project in compliance with the federal Migratory Bird Treaty Act and days prior to Services
relevant Fish and Game Codes: vegetation Department –
Avoidance. In order to avoid impacts to nesting raptors and migratory clearance. Community
birds, the Project will be constructed, if feasible, from September 16th Development
and January 31st, which is outside the avian nesting season. Department
Preconstruction Surveys. If Project activities must occur during the

nesting season (February 1-September 15), a qualified biologist will conduct preconstruction surveys for active raptor and migratory bird nests within 10 days prior to the start of these activities. The survey will include the proposed work area(s) and surrounding lands within 500 feet, where accessible, for all nesting raptors and migratory birds. If no active nests are found within the survey area, no further mitigation is required. • Establish Buffers. Should any active nests be discovered near proposed work areas, no disturbance buffers of 250 feet around active nests of non-listed bird species and 500 feet around active nests of non-listed raptors will be established. If work needs to occur within these no disturbance buffers, a qualified biologist will monitor the nest daily for one week, and thereafter once a week, throughout the duration of construction activity. Should the nature of construction activity significantly change, such that a higher level of disturbance will be generated, monitoring will occur daily for one week and then resume the once-a-week regime. If, at any time, the biologist determines that construction activity may be compromising nesting success, construction activity within the designated buffer will be altered or suspended until the biologist determines that the nest site is no longer susceptible to deleterious disturbance.				
Cultural Resources			L	
	Duianta	Davidania ant and		
CUL-1 Historical Resources Identification and Treatment Plan	Prior to	Development and		
Prior to permit approval for development on the Project site, a historical	permit	Engineering Services		
resources evaluation shall be completed for that individual site to confirm if existing buildings and/or structures withing these sites qualify as historical	approval.	Department –		
resources as defined by Section 15064.5(a) of CEQA Guidelines. The		Community		
evaluation shall be prepared by a qualified architectural historian or historian		Development		
who meets the Secretary of the Interior's Professional Qualifications Standards		Department		
(PQS) in architectural history or history. The qualified architectural historian or				
historian shall conduct an intensive-level evaluation in accordance with the				
guidelines and best practices promulgated by the State Office of Historic				
Preservation to identify any potential historical resources within the proposed				
project area. All properties 45 years of age or older shall be evaluated within				

their historic context and documented in a report meeting the State Office of			
Historic Preservation guidelines. All evaluated properties shall be documented			
on Department of Parks and Recreation Series 523 Forms. The report shall be			
submitted to the City for review and concurrence.			
Any relocation, rehabilitation, or alteration of the resource shall be			
implemented consistent with the Secretary of the Interior's Standards for the			
Treatments of Historic Properties (Standards). In accordance with CEQA, a			
project that has been determined to conform with the Standards generally			
would not cause a significant adverse direct or indirect impact to historical			
resources (14 CCR Section 15126.4[b][1]). Application of the Standards shall			
be overseen by a qualified architectural historian or historic architect meeting			
the PQS. In conjunction with any development application that may affect the			
historical resource, a report identifying and specifying the treatment of			
character-defining features and construction activities shall be provided to the			
City for review and concurrence, in addition to the historical resources			
evaluation.			
If significant historical resources are identified on a development site and			
compliance with the Standards and or avoidance is not feasible, the applicant			
or developer shall provide a report explaining why compliance with the			
Standards and or avoidance is not feasible for the City's review and approval.			
Site-specific mitigation measures shall be established and undertaken,			
including, but not limited to, documentation of the historical resource in the			
form of a Historic American Buildings Survey-Like report. The report shall be			
commissioned by the project applicant or their consultant to comply with the			
Secretary of the Interior's Standards for Architectural and Engineering			
Documentation and shall generally follow the Historic American Buildings			
Survey Level III requirements, including digital photographic recordation,			
detailed historic narrative report, and compilation of historic research. The			
documentation shall be completed by a qualified architectural historian or			
historian who meets the PQS and submitted to the City prior to issuance of any			
permits for demolition or alteration of the historical resource.			
Mitigation Measure CUL-2 Phase I Cultural Resources Study	Prior to	Development and	
Prior to the issuance of any grading or construction permits for each individual	issuance of	Engineering	
site, a Phase I cultural resources study shall be performed by a qualified	grading or	Services	

professional meeting the Secretary of the Interior's (SOI's) Professional Qualification Standards (PQS) for archaeology (National Park Service 1983). The Phase I cultural resources study shall include a pedestrian survey of the project site when appropriate and sufficient background research and field sampling to determine whether archaeological resources may be present. Archival research shall include a records search of the Northwest Information Center (NWIC) no more than two years old and a Sacred Lands File search with the NAHC. The Phase I technical report documenting the study shall include recommendations that shall be implemented prior to and/or during construction to avoid or reduce impacts to archaeological resources. Recommendations may include, but would not be limited to, archaeological construction monitoring, sensitivity training, or additional testing and mitigation (outlined in Mitigation Measures CUL-3 through CUL-7). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The City shall include recommendations in the Phase I technical report as Conditions of Approval to be implemented throughout all ground disturbance activities. The final report shall be submitted to the NWIC.	construction permits.	Department – Community Development Department	
Mitigation Measure CUL-3 Extended Phase I Testing If recommended by the Phase I study for each individual site (Mitigation Measure CUL-2), the project applicant shall retain a qualified archaeologist to conduct an Extended Phase I (XPI) study to determine the presence/absence and extent of archaeological resources on the project site. XPI testing shall include a series of shovel test pits and/or hand augured units and/or mechanical trenching to establish the boundaries of archaeological site(s) on the project site. If the boundaries of the archaeological site are already well understood from previous archaeological work, an XPI will not be required. All archaeological excavation shall be conducted by a qualified archaeologist(s) under the direction of a principal investigator meeting the SOI's PQS for archaeology (National Park Service 1983). If an XPI report is prepared, it shall be submitted to the City for review and approval prior to the issuance of a grading or construction permit. Recommendations therein shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, site avoidance, Phase II Site Evaluation,	Prior to the issuance of a grading or construction permit.	Development and Engineering Services Department – Community Development Department	

During	Development and		
construction	Engineering		
	Services		
	Department –		
	Community		
	Department		
•	•		
construction			
	•		
	,		
	Department		
	_	construction . Engineering Services Department – Community Development Department During construction . Development and Engineering Services Department – Community Development Department Department Department	construction . Engineering Services Department — Community Development Department Development and Engineering Services Department — Community Development Development Department — Development Department Department Department

shall be determined using radiocarbon dating and/or other appropriate procedures; lithic artifacts, faunal remains, and other cultural materials shall be identified and analyzed according to current professional standards. The significance of the site(s) shall be evaluated according to the criteria of the CRHR and if applicable, NRHP. The results of the investigations shall be presented in a technical report following the standards of the California Office of Historic Preservation publication "Archaeological Resource Management Reports: Recommended Content and Format (1990 or latest edition)." Recommendations in the Phase II report shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, Phase III Data Recovery, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-6 through CUL-8). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The final report shall be submitted to the NWIC.			
Mitigation Measure CUL-6 Phase III Data Recovery Should the results of the Phase II site evaluation for each individual site (Mitigation Measure CUL-5) yield resources that meet CRHR significance standards and if the resource cannot be avoided by project construction in accordance with CUL-4, the project applicant shall ensure that all feasible recommendations for mitigation of archaeological impacts are incorporated into the final design and approved by the City prior to construction. Any necessary Phase III data recovery excavation, conducted to exhaust the data potential of significant archaeological sites, shall be carried out by a qualified archaeologist meeting the SOI's PQS for archeology (National Park Service 1983). Data recovery shall be conducted in accordance with a research design reviewed and approved by the City, prepared in advance of fieldwork, and using the appropriate archaeological field and laboratory methods consistent with the California Office of Historic Preservation Planning Bulletin 5 (1991), Guidelines for Archaeological Research Design, or the latest edition thereof. If the archaeological resource(s) of concern are Native American in origin, the qualified archaeologist shall confer with the City and local California Native American tribe(s). As applicable, the final Phase III Data Recovery reports shall be submitted to	During construction .	Development and Engineering Services Department – Community Development Department	

	1	1	1
the City prior to issuance of any grading or construction permit.			
Recommendations contained therein shall be implemented throughout all			
ground disturbance activities. Recommendations may include, but would not			
be limited to, Cultural Resources Monitoring, and/or measures for			
unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8).			
The final report shall be submitted to the NWIC upon completion.			
Mitigation Measure CUL-7 Cultural Resources Monitoring	During	Development and	
If recommended by Phase I, XPI, Phase II, or Phase III studies for each	construction	Engineering	
individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the		Services	
project applicant shall retain a qualified archaeologist to monitor project-		Department –	
related, ground-disturbing activities which may include the following but not		Community	
limited to: grubbing, vegetation removal, trenching, grading, and/or		Development	
excavations. The archaeological monitor shall coordinate with any Native		Department	
American monitor as required. Monitoring logs must be completed by the			
archaeologist daily. Cultural resources monitoring may be reduced for the			
project if the qualified archaeologist finds it appropriate to reduce the			
monitoring efforts. Upon completion of ground disturbance for the project, a			
final report must be submitted to the City for review and approval documenting			
the monitoring efforts, cultural resources find, and resource disposition. The			
final report shall be submitted to the NWIC.			
Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources	During	Development and	
If archaeological resources are encountered during ground-disturbing	construction	Engineering	
activities, work within 50 feet shall be halted and the project archaeologist		Services	
meeting the SOI's PQS for archeology (National Park Service 1983) shall		Department –	
immediately to evaluate the find pursuant to Public Resources Code Section		Community	
21083.2. If necessary, the evaluation may require preparation of a treatment		Development	
plan and archaeological testing for CRHR eligibility. If the discovery proves to		Department	
be significant under CEQA and cannot be avoided by the project, additional			
work may be warranted, such as data recovery excavation, to mitigate any			
significant impacts to significant resources. If the resource is of Native			
American origin, implementation of Mitigation Measures TCR-1 may be			
required. Any reports required to document and/or evaluate unanticipated			
discoveries shall be submitted to the City for review and approval and			
submitted to the NWIC after completion. Recommendations contained therein			

shall be implemented throughout the remainder of ground disturbance activities.		
Greenhouse Gas Emissions		
Mitigation Measure GHG-1: Future development shall install EV charging infrastructure according to the most ambitious voluntary standard in the California Green Building Standards Code at the time of project approval.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department
Mitigation Measure GHG-2: Future development shall provide no more parking spaces than the off-street parking requirements established in the City of Salinas Municipal Code. Alternatively, multi-family residential development can choose to unbundle parking costs with costs to rent or own a residential unit instead of meeting the maximum off-parking requirement.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department
Hydrology and Water Quality		
Mitigation Measure HYD-1: Future Development projects on the subject site that would demand an amount of water equivalent to, or greater than, the amount of water required by a 500-dwelling unit project are required to prepare a Water Supply Assessment.	Prior to permit approval.	Development and Engineering Services Department – Community Development Department
Noise		
 Mitigation Measure NOI-1: Prior to ground disturbing activities, the City of Salinas shall ensure the following with the Project proponent: Construction equipment, fixed of mobile, shall be outfitted with properly operating and maintained mufflers. Construction noise reduction methods such as shutting off idling equipment, installing temporary acoustic barriers around stationary 	During construction	Development and Engineering Services Department — Community Development

 construction noise sources, maximizing the distance between construction equipment staging areas and occupied residential areas, and using electric air compressors and similar power tools rather than diesel equipment shall be used. During construction, stationary construction equipment shall be located so that emitted noise is directed away from or shielded from sensitive noise receivers. 		Department.
Mitigation Measure NOI-2: The use of heavy construction equipment within 25 feet of existing structures shall be prohibited.	During construction	Development and Engineering Services Department – Community Development Department.
Transportation		
Mitigation Measure TRANS-1: To maintain safety standards at all intersections and roadway segments pursuant to implementation actions identified in the Vision Zero Action Plan, a traffic impact study shall be required for all development projects anticipated to generate 110 or more new daily vehicle trips within the Project Area, unless not required by the City. Depending on the results of this study, future developments may be required to construct or contribute to street safety improvements to meet the demand generated by the project. Improvements shall be in accordance with the City of Salinas' Vision Zero Action Plan (i.e. pedestrian-activated crosswalk warning beacon, high visibility crosswalks, pedestrian hybrid beacon, reduced parking at intersection, intersection control, raised median and street trees, protected bike lanes, and lane reduction). These improvements shall be required as conditions of approval.	Prior to permit approval.	Development and Engineering Services Department – Traffic Engineering and Plan Check Services
Tribal Cultural Resources		
Mitigation Measure TCR-1 Inadvertent Discoveries During Construction In the event that cultural resources of Native American origin are identified during grading or construction, all earth disturbing work within the vicinity of the find shall be temporarily suspended or redirected until a qualified archaeologist has evaluated the nature and significance of the find; an appropriate Native	During construction .	Development and Engineering Services Department – Community

		1	
American representative, based on the nature of the find, is consulted; and		Development	
mitigation measures are put in place for the disposition and protection of any		Department.	
find pursuant to Public Resources Code Section 21083.2. If the City, in			
consultation with local Native Americans, determines that the resource is a			
tribal cultural resource and thus significant under CEQA, a mitigation plan shall			
be prepared and implemented in accordance with state guidelines and in			
consultation with local Native American group(s) prior to continuation of any			
earth disturbing work within the vicinity of the find. The plan shall include			
avoidance of the resource or, if avoidance of the resource is infeasible, shall			
outline the appropriate treatment of the resource in coordination with the			
appropriate local Native American tribal representative and, if applicable, a			
qualified archaeologist. Examples of appropriate mitigation for tribal cultural			
resources include, but are not limited to, protecting the cultural character and			
integrity of the resource, protecting traditional use of the resource, protecting			
the confidentiality of the resource, or heritage recovery.			
Utilities and Service Systems	•		
Mitigation Measure UTL-1: New development generating wastewater flows that	Prior to	Development and	
results in a downstream exceedance of 0.75 d/D shall construct system	permit	Engineering	
upgrades for those found to be insufficient in capacity per the requirements of	approval.	Services	
the Public Works Department. The flow shall be verified through a sewer	' '	Department	
modeling program during the planning and design phase, prior to entitlement		'	
approval. The model shall evaluate pipeline capacity, flow velocity, and			
maximum d/D ratio for normal, dry, and wet weather conditions.			

SEARS (NORTHRIDGE MALL) MITIGATION MONITORING AND REPORTING PROGRAM APN 253-201-054-000 (8.41-ACRE PORTION) (GENERAL PLAN AMENDMENT 2022-002 AND REZONE 2022-002)

Mitigation Measures	Timing of	_	Responsible for	Responsible for Comu	cation of pletion	
	Verification	Verification	Date	Initials		
Air Quality						
 Mitigation Measure AQ-1: Construction Air Quality. During construction, the applicant or successor in interest for each individual site shall: Limit grading to 8.1 acres per day, and limit grading and excavation to 2.2 acres per day. Provide watering trucks on site to maintain adequate soil moisture during grading and water graded/excavated areas at least twice daily, thus minimizing dust generation. In addition, the water trucks shall be used to wash down trucks and tractors, including earth loads, prior to entering public roadways. Prohibit all grading activities whenever wind speeds exceed 15 miles per hour (mph). Maintain a minimum of two feet for freeboard for all haul trucks. Cover all trucks hauling dirt, sand, or loose materials. Cover inactive storage piles. Enforce a 15-mph speed limit for all unpaved surfaces when visible dust clouds are formed by vehicle movement. Place gravel base near site entrances to clean tires prior to entering public roadways. 		Development and Engineering Services Department – Plan Check Service				
Mitigation Measure AQ-2: MBARD Health Risk Consultation. Prior to issuance of any grading permit and/or building permit for each individual site, the	Prior to issuance of	Development and Engineering				

applicant or successor in interest shall consult with MBARD regarding the	any grading	Services		
potential need for a diesel health risk assessment (HRA). If required, the	permit	Department – Plan		
applicant or successor in interest shall prepare a diesel HRA and shall	and/or	Check Services;		
implement the measures contained therein to ensure that project-specific	building	MBARD		
emissions are below MBARD's established health risk thresholds: hazard	permit;			
index greater than 1 for acute or chronic impacts, and cancer risk greater than	during			
10 in one million for long-term operational emissions or 1 per 100,000	construction			
population for temporary construction-related emissions. Measures may				
include, but would not be limited to:				
Use of diesel-fueled equipment equipped with Tier 4 (or Tier 3 if the				
Tier 4 standard is unavailable) USEPA engine standards. The USEPA				
estimates that Tier 4 engines would reduce PM emissions by				
approximately 90 percent compared to the USEPA Tier 2 standards				
· · · · · · · · · · · · · · · · · · ·				
(USEPA 2008).				
Retrofit off-road diesel equipment with Verified Diesel Emissions Out the Office of the Control of the Co				
Control Strategy (VDECS) like Diesel Particulate Filters (DPF).				
Particulate Matter level 3 VDECS can provide at least an 85 percent				
reduction (CARB 2015).				
• Use alternatively fueled (e.g., natural gas) diesel construction				
equipment, including all off-road and portable diesel-powered				
equipment.				
Use electrically driven equipment that is not powered by a portable				
generator set.				
• Limit the hours of operation for heavy-duty equipment and/or limit the				
quantity of heavy-duty equipment operating at the same time.				
Biological Resources			l.	
Mitigation Measure BIO-1: Nesting Bird Surveys and Avoidance. The Project	Not more	Development and		
shall implement the following measures to mitigate for loss of nesting habitat of	than 14	Engineering		
the Project in compliance with the federal Migratory Bird Treaty Act and	days prior to	Services		
relevant Fish and Game Codes:	vegetation	Department –		
Avoidance. In order to avoid impacts to nesting raptors and migratory	clearance.	Community		
birds, the Project will be constructed, if feasible, from September 16th	3.341411001	Development		
and January 31st, which is outside the avian nesting season.		Department		
		Dopartinent		
 Preconstruction Surveys. If Project activities must occur during the 				

nesting season (February 1-September 15), a qualified biologist will conduct preconstruction surveys for active raptor and migratory bird nests within 10 days prior to the start of these activities. The survey will include the proposed work area(s) and surrounding lands within 500 feet, where accessible, for all nesting raptors and migratory birds. If no active nests are found within the survey area, no further mitigation is required. • Establish Buffers. Should any active nests be discovered near proposed work areas, no disturbance buffers of 250 feet around active nests of non-listed bird species and 500 feet around active nests of non-listed raptors will be established. If work needs to occur within these no disturbance buffers, a qualified biologist will monitor the nest daily for one week, and thereafter once a week, throughout the duration of construction activity. Should the nature of construction activity significantly change, such that a higher level of disturbance will be generated, monitoring will occur daily for one week and then resume the once-a-week regime. If, at any time, the biologist determines that construction activity may be compromising nesting success, construction activity within the designated buffer will be altered or suspended until the biologist determines that the nest site is no longer susceptible to deleterious disturbance.				
Cultural Resources			l l	
CUL-1 Historical Resources Identification and Treatment Plan	Prior to	Development and		
Prior to permit approval for development on the Project site, a historical	permit	Engineering		
resources evaluation shall be completed for that individual site to confirm if	approval.	Services		
existing buildings and/or structures withing these sites qualify as historical	approvai.	Department –		
resources as defined by Section 15064.5(a) of CEQA Guidelines. The		Community		
evaluation shall be prepared by a qualified architectural historian or historian		Development		
who meets the Secretary of the Interior's Professional Qualifications Standards		Department		
(PQS) in architectural history or history. The qualified architectural historian or		'		
historian shall conduct an intensive-level evaluation in accordance with the				
guidelines and best practices promulgated by the State Office of Historic				
Preservation to identify any potential historical resources within the proposed				
project area. All properties 45 years of age or older shall be evaluated within				

their historic context and documented in a report meeting the State Office of			
Historic Preservation guidelines. All evaluated properties shall be documented			
on Department of Parks and Recreation Series 523 Forms. The report shall be			
submitted to the City for review and concurrence.			
Any relocation, rehabilitation, or alteration of the resource shall be			
implemented consistent with the Secretary of the Interior's Standards for the			
Treatments of Historic Properties (Standards). In accordance with CEQA, a			
project that has been determined to conform with the Standards generally			
would not cause a significant adverse direct or indirect impact to historical			
resources (14 CCR Section 15126.4[b][1]). Application of the Standards shall			
be overseen by a qualified architectural historian or historic architect meeting			
the PQS. In conjunction with any development application that may affect the			
historical resource, a report identifying and specifying the treatment of			
character-defining features and construction activities shall be provided to the			
City for review and concurrence, in addition to the historical resources			
evaluation.			
If significant historical resources are identified on a development site and			
compliance with the Standards and or avoidance is not feasible, the applicant			
or developer shall provide a report explaining why compliance with the			
Standards and or avoidance is not feasible for the City's review and approval.			
Site-specific mitigation measures shall be established and undertaken,			
including, but not limited to, documentation of the historical resource in the			
form of a Historic American Buildings Survey-Like report. The report shall be			
commissioned by the project applicant or their consultant to comply with the			
Secretary of the Interior's Standards for Architectural and Engineering			
Documentation and shall generally follow the Historic American Buildings			
Survey Level III requirements, including digital photographic recordation,			
detailed historic narrative report, and compilation of historic research. The			
documentation shall be completed by a qualified architectural historian or			
historian who meets the PQS and submitted to the City prior to issuance of any			
permits for demolition or alteration of the historical resource.			
Mitigation Measure CUL-2 Phase I Cultural Resources Study	Prior to	Development and	
Prior to the issuance of any grading or construction permits for each individual	issuance of	Engineering	
site, a Phase I cultural resources study shall be performed by a qualified	grading or	Services	

		<u> </u>	
professional meeting the Secretary of the Interior's (SOI's) Professional Qualification Standards (PQS) for archaeology (National Park Service 1983). The Phase I cultural resources study shall include a pedestrian survey of the project site when appropriate and sufficient background research and field sampling to determine whether archaeological resources may be present. Archival research shall include a records search of the Northwest Information Center (NWIC) no more than two years old and a Sacred Lands File search with the NAHC. The Phase I technical report documenting the study shall include recommendations that shall be implemented prior to and/or during construction to avoid or reduce impacts to archaeological resources. Recommendations may include, but would not be limited to, archaeological construction monitoring, sensitivity training, or additional testing and mitigation (outlined in Mitigation Measures CUL-3 through CUL-7). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The City shall include recommendations in the Phase I technical report as Conditions of Approval to be implemented throughout all ground disturbance activities. The final report shall be submitted to the NWIC.	construction permits.	Department – Community Development Department	
Mitigation Measure CUL-3 Extended Phase I Testing If recommended by the Phase I study for each individual site (Mitigation Measure CUL-2), the project applicant shall retain a qualified archaeologist to conduct an Extended Phase I (XPI) study to determine the presence/absence and extent of archaeological resources on the project site. XPI testing shall include a series of shovel test pits and/or hand augured units and/or mechanical trenching to establish the boundaries of archaeological site(s) on the project site. If the boundaries of the archaeological site are already well understood from previous archaeological work, an XPI will not be required. All archaeological excavation shall be conducted by a qualified archaeologist(s) under the direction of a principal investigator meeting the SOI's PQS for archaeology (National Park Service 1983). If an XPI report is prepared, it shall be submitted to the City for review and approval prior to the issuance of a grading or construction permit. Recommendations therein shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, site avoidance, Phase II Site Evaluation,	Prior to the issuance of a grading or construction permit.	Development and Engineering Services Department – Community Development Department	

During	Development and		
construction	Engineering		
	Services		
	Department –		
	Community		
	Department		
_	<u> </u>		
construction			
	,		
	Department		
	During construction .	construction . Engineering Services Department – Community Development Department During construction . Development and Engineering Services Department – Community Development Department Department Department	construction . Engineering Services Department — Community Development Department Development and Engineering Services Department — Community Development Department — Community Development Department Department

shall be determined using radiocarbon dating and/or other appropriate procedures; lithic artifacts, faunal remains, and other cultural materials shall be identified and analyzed according to current professional standards. The significance of the site(s) shall be evaluated according to the criteria of the CRHR and if applicable, NRHP. The results of the investigations shall be presented in a technical report following the standards of the California Office of Historic Preservation publication "Archaeological Resource Management Reports: Recommended Content and Format (1990 or latest edition)." Recommendations in the Phase II report shall be implemented for all ground disturbance activities. Recommendations may include, but would not be limited to, Phase III Data Recovery, Cultural Resources Monitoring, and/or measures for unanticipated discoveries (outlined in Mitigation Measures CUL-6 through CUL-8). The report shall be submitted to the City for review and approval prior to the issuance of any grading or construction permits. The final report shall be submitted to the NWIC.			
Mitigation Measure CUL-6 Phase III Data Recovery Should the results of the Phase II site evaluation for each individual site	During construction	Development and Engineering	
(Mitigation Measure CUL-5) yield resources that meet CRHR significance		Services	
standards and if the resource cannot be avoided by project construction in		Department –	
accordance with CUL-4, the project applicant shall ensure that all feasible		Community	
recommendations for mitigation of archaeological impacts are incorporated into		Development	
the final design and approved by the City prior to construction. Any necessary		Department	
Phase III data recovery excavation, conducted to exhaust the data potential of			
significant archaeological sites, shall be carried out by a qualified archaeologist			
meeting the SOI's PQS for archeology (National Park Service 1983). Data			
recovery shall be conducted in accordance with a research design reviewed			
and approved by the City, prepared in advance of fieldwork, and using the			
appropriate archaeological field and laboratory methods consistent with the California Office of Historic Preservation Planning Bulletin 5 (1991), Guidelines			
for Archaeological Research Design, or the latest edition thereof. If the			
archaeological resource(s) of concern are Native American in origin, the			
qualified archaeologist shall confer with the City and local California Native			
American tribe(s).			
As applicable, the final Phase III Data Recovery reports shall be submitted to			

the City prior to issuance of any grading or construction permit.			
Recommendations contained therein shall be implemented throughout all			
ground disturbance activities. Recommendations may include, but would not			
be limited to, Cultural Resources Monitoring, and/or measures for			
unanticipated discoveries (outlined in Mitigation Measures CUL-7 and CUL-8).			
The final report shall be submitted to the NWIC upon completion.			
Mitigation Measure CUL-7 Cultural Resources Monitoring	During	Development and	
If recommended by Phase I, XPI, Phase II, or Phase III studies for each	construction	Engineering	
individual site (Mitigation Measures CUL-2, CUL-3, CUL-5, and/or CUL-6), the		Services	
project applicant shall retain a qualified archaeologist to monitor project-		Department –	
related, ground-disturbing activities which may include the following but not		Community	
limited to: grubbing, vegetation removal, trenching, grading, and/or		Development	
excavations. The archaeological monitor shall coordinate with any Native		Department	
American monitor as required. Monitoring logs must be completed by the			
archaeologist daily. Cultural resources monitoring may be reduced for the			
project if the qualified archaeologist finds it appropriate to reduce the			
monitoring efforts. Upon completion of ground disturbance for the project, a			
final report must be submitted to the City for review and approval documenting			
the monitoring efforts, cultural resources find, and resource disposition. The			
final report shall be submitted to the NWIC.			
Mitigation Measure CUL-8 Unanticipated Discovery of Cultural Resources	During	Development and	
If archaeological resources are encountered during ground-disturbing	construction	Engineering	
activities, work within 50 feet shall be halted and the project archaeologist		Services	
meeting the SOI's PQS for archeology (National Park Service 1983) shall		Department –	
immediately to evaluate the find pursuant to Public Resources Code Section		Community	
21083.2. If necessary, the evaluation may require preparation of a treatment		Development	
plan and archaeological testing for CRHR eligibility. If the discovery proves to		Department	
be significant under CEQA and cannot be avoided by the project, additional			
work may be warranted, such as data recovery excavation, to mitigate any			
significant impacts to significant resources. If the resource is of Native			
American origin, implementation of Mitigation Measures TCR-1 may be			
required. Any reports required to document and/or evaluate unanticipated			
discoveries shall be submitted to the City for review and approval and			
submitted to the NWIC after completion. Recommendations contained therein			

	I	T T
shall be implemented throughout the remainder of ground disturbance		
activities.		
Greenhouse Gas Emissions		
Mitigation Measure GHG-1: Future development shall install EV charging infrastructure according to the most ambitious voluntary standard in the California Green Building Standards Code at the time of project approval. Mitigation Measure GHG-2: Future development shall provide no more parking	Prior to permit approval.	Development and Engineering Services Department — Community Development Department Development and
spaces than the off-street parking requirements established in the City of Salinas Municipal Code. Alternatively, multi-family residential development can choose to unbundle parking costs with costs to rent or own a residential unit instead of meeting the maximum off-parking requirement.	permit approval.	Engineering Services Department — Community Development Department
Noise		
 Mitigation Measure NOI-1: Prior to ground disturbing activities, the City of Salinas shall ensure the following with the Project proponent: Construction equipment, fixed of mobile, shall be outfitted with properly operating and maintained mufflers. Construction noise reduction methods such as shutting off idling equipment, installing temporary acoustic barriers around stationary construction noise sources, maximizing the distance between construction equipment staging areas and occupied residential areas, and using electric air compressors and similar power tools rather than diesel equipment shall be used. During construction, stationary construction equipment shall be located so that emitted noise is directed away from or shielded from sensitive noise receivers. 	During construction .	Development and Engineering Services Department — Community Development Department.
Mitigation Measure NOI-2: The use of heavy construction equipment within 25 feet of existing structures shall be prohibited.	During construction	Development and Engineering

		Services	
		Department –	
		Community	
		Development	
		Department.	
Transportation			
Mitigation Measure TRANS-1: To maintain safety standards at all intersections	Prior to	Development and	
and roadway segments pursuant to implementation actions identified in the	permit	Engineering	
Vision Zero Action Plan, a traffic impact study shall be required for all	approval.	Services	
development projects anticipated to generate 110 or more new daily vehicle		Department –	
trips within the Project Area, unless not required by the City. Depending on the		Traffic Engineering	
results of this study, future developments may be required to construct or		and Plan Check	
contribute to street safety improvements to meet the demand generated by the		Services	
project. Improvements shall be in accordance with the City of Salinas' Vision			
Zero Action Plan (i.e. pedestrian-activated crosswalk warning beacon, high			
visibility crosswalks, pedestrian hybrid beacon, reduced parking at intersection,			
intersection control, raised median and street trees, protected bike lanes, and			
lane reduction). These improvements shall be required as conditions of			
approval.			
Tribal Cultural Resources		<u> </u>	
Mitigation Measure TCR-1 Inadvertent Discoveries During Construction	During	Development and	
In the event that cultural resources of Native American origin are identified	construction	Engineering	
during grading or construction, all earth disturbing work within the vicinity of the		Services	
find shall be temporarily suspended or redirected until a qualified archaeologist		Department -	
has evaluated the nature and significance of the find; an appropriate Native		Community	
American representative, based on the nature of the find, is consulted; and		Development	
mitigation measures are put in place for the disposition and protection of any		Department.	
find pursuant to Public Resources Code Section 21083.2. If the City, in			
consultation with local Native Americans, determines that the resource is a			
tribal cultural resource and thus significant under CEQA, a mitigation plan shall			
be prepared and implemented in accordance with state guidelines and in			
consultation with local Native American group(s) prior to continuation of any			
earth disturbing work within the vicinity of the find. The plan shall include			
avoidance of the resource or, if avoidance of the resource is infeasible, shall			

outline the appropriate treatment of the resource in coordination with the appropriate local Native American tribal representative and, if applicable, a qualified archaeologist. Examples of appropriate mitigation for tribal cultural resources include, but are not limited to, protecting the cultural character and integrity of the resource, protecting traditional use of the resource, protecting the confidentiality of the resource, or heritage recovery.			
Utilities and Service Systems			
Mitigation Measure UTL-1: New development generating wastewater flows that results in a downstream exceedance of 0.75 d/D shall construct system upgrades for those found to be insufficient in capacity per the requirements of the Public Works Department. The flow shall be verified through a sewer modeling program during the planning and design phase, prior to entitlement approval. The model shall evaluate pipeline capacity, flow velocity, and maximum d/D ratio for normal, dry, and wet weather conditions.	Prior to permit approval.	Development and Engineering Services Department	