

North

Vicinity Map



PUD 2025-003 & CUP 2025-025 200 Casentini Street

Exhibit A



Exhibit



Project Team:

Owner/ Developer

Milestone Housing Group
51 University Ave., Ste D
Los Gatos, CA 95030
Contact: Aaron Barger

Architecture

KTGY Group, Inc.
17911 Van Karman Ave, Ste 200
Irvine, CA 92614
Contact: Keith Labus

Civil

BKF Engineers
1646 N California Blvd, Suite 400
Walnut Creek, CA 94596
Contact: Kyle Christy, PE

Landscape

MJS Landscaping
507 30th Street,
Newport Beach, CA 92663
Contact: Mark Schattinger

SHEET INDEX

ARCHITECTURE

COVER SHEET

- A1.0 SITE PLAN
- A1.1 FIRE SAFETY MAP
- A1.2 OPEN SPACE EXHIBIT
- A2.0 BLDG. A ELEVATIONS
- A2.1 BLDG. B ELEVATIONS
- A2.2 AMENITY BLDG ELEVATIONS
- A2.3 DAYCARE BLDG ELEVATIONS
- A2.4 TRASH ENCLOSURE EXHIBIT

- A3.0 BLDG. A FLOOR PLANS
- A3.1 BLDG. B FLOOR PLANS
- A3.2 BLDG. B FLOOR PLANS
- A3.3 BLDG. B FLOOR PLANS
- A3.4 AMENITY BLDG FLOOR PLAN
- A3.5 DAYCARE BLDG FLOOR PLAN

UNIT PLANS


- A5.0 UNIT PLANS
- A5.1 UNIT PLANS
- A6.0 PERSPECTIVES
- A6.1 PERSPECTIVES

LANDSCAPE


- L1 CONCEPTUAL LANDSCAPE PLAN
- L2 Tree Plan
- L3 PLANTING SCHEDULE & NOTES
- L4 HYDROZONE PLAN
- L5 WALL & FENCE PLAN

CIVIL

- C1.0 EXISTING CONDITIONS
- C2.0 PRELIMINARY GRADING PLAN
- C3.0 PRELIMINARY UTILITY PLAN
- C4.0 PRELIMINARY STORMWATER CONTROL PLAN




VICINITY MAP | NTS



LEGEND
COMMON OPEN SPACE:
REQUIRED BY CITY OF SALINAS MUNICIPAL CODE
500 SF/DU, 88 DU
44,000 SF REQUIRED

PROVIDED:


OPEN SPACE AREA	SQ. FT.
Open Space 1	2,000.33
Open Space 2	2,408
Open Space 3	2,408
Open Space 4	2,408
Open Space 5	2,408
Open Space 6	2,408
TOTAL OPEN SPACE	12,032.13



1. FRONT ELEVATION




2. RIGHT ELEVATION



4. LEFT ELEVATION



3. REAR ELEVATION



KEY PLAN
N.T.S.

MATERIAL LEGEND


1. STUCCO 1 - SW 6148 Wool Skin or Similar
2. STUCCO 2 - SW 7038 Tony Taupe or Similar
3. STONE VENEER - Coronado, Rough Cut Wood, Rustic Cedar or Similar
4. DOOR - SW 6145 Thatch Brown or Similar
5. TRIM - SW 6145 Thatch Brown or Similar
6. WINDOW - VPI, Adobe or Similar
7. METAL RAILING - SW 6145 Thatch Brown or Similar
8. ROOF TILE - CertainTeed Landmark Solaris Weather Wood or Similar
9. LIGHT FIXTURE - James Allen Kent 17, Dark Bronze
10. STOREFRONT - Kawneer, Dark Bronze or Similar
11. AWNING - SW 6145 Thatch Brown or Similar
12. GARAGE OPENING - N/A
13. STUCCO (ACCENT) - SW 6664 Marigold



1. FRONT ELEVATION




2. RIGHT ELEVATION



4. LEFT ELEVATION





3. REAR ELEVATION




MATERIAL LEGEND


1. STUCCO 1 - SW 6148 Wool Skin or Similar
2. STUCCO 2 - SW 7038 Tony Taupe or Similar
3. STONE VENEER - Coronado, Rough Cut Wood, Rustic Cedar or Similar
4. DOOR - SW 6145 Thatch Brown or Similar
5. TRIM - SW 6145 Thatch Brown or Similar
6. WINDOW - VPI, Adobe or Similar
7. METAL RAILING - SW 6145 Thatch Brown or Similar
8. ROOF TILE - Certainteed Landmark Solaris Weather Wood or Similar
9. LIGHT FIXTURE - James Allen Kent 17, Dark Bronze
10. STOREFRONT - Kawneer, Dark Bronze or Similar
11. AWNING - SW 6145 Thatch Brown or Similar
12. GARAGE OPENING - N/A
13. STUCCO (ACCENT) - SW 6664 Marigold




1. FRONT ELEVATION



2. RIGHT ELEVATION




4. LEFT ELEVATION



3. REAR ELEVATION

MATERIAL LEGEND

1. STUCCO 1 - SW 6148 Wool Skin or Similar
2. STUCCO 2 - SW 7038 Tony Taupe or Similar
3. STONE VENEER - Coronado, Rough Cut Wood, Rustic Cedar or Similar
4. DOOR - SW 6145 Thatch Brown or Similar
5. TRIM - SW 6145 Thatch Brown or Similar
6. WINDOW - VPI, Adobe or Similar
7. METAL RAILING - SW 6145 Thatch Brown or Similar
8. ROOF TILE - Certainteed Landmark Solists Weather Wood or Similar
9. LIGHT FIXTURE - James Allen Kent 17, Dark Bronze
10. STOREFRONT - Kawneer, Dark Bronze or Similar
11. AWNING - SW 6145 Thatch Brown or Similar
12. GARAGE OPENING - N/A
13. STUCCO (ACCENT) - SW 6664 Marigold



The image contains two perspective drawings of a single-story house, each with numbered callouts pointing to specific exterior features. The house has a gabled roof, a chimney, and a front porch.

Left Drawing Callouts:

- 2: Front porch railing
- 5: Front porch door
- 8: Front porch roof

Right Drawing Callouts:

- 2: Front porch railing
- 3: Front porch door
- 5: Front porch roof
- 6: Front porch roof
- 6: Front porch roof
- 11: Front porch roof


A diagram of a house with numbered labels 2 through 6 pointing to various parts of the structure. Label 2 points to the front door, label 3 points to the front window, label 4 points to the roof, label 5 points to the side wall, and label 6 points to the back door.

MATERIAL LEGEND

1. STUCCO 1 - SW 6148 Wood Skin or Similar
2. STUCCO 2 - SW 7038 Tony Taupe or Similar
3. STONE VENEER - Coronado, Rough Cut Wood, Rustic Cedar or Similar
4. DOOR - SW 6145 Thatch Brown or Similar
5. TRIM - SW 6145 Thatch Brown or Similar
6. WINDOW - VPI Adobe or Similar
7. METAL RAILING - SW 6145 Thatch Brown or Similar
8. ROOF TILE - Painted Landmark Solaris Weather Wood or Similar
9. LIGHT FIXTURE - James Allen Kent 17, Dark Bronze
10. STOREFRONT - Kawneer, Dark Bronze or Similar
11. AWNING - SW 6145 Thatch Brown or Similar
12. GARAGE OPENING - N/A
13. STUCCO (ACCENT) - SW 6664 Marigold

Material Legend

1. Stucco 2 - SW 7038 Tony Taupe or Similar
2. 8" Masonry Block Construction
3. Split Paver Cap-SW 6145 Thatch Brown or Similar
4. Painted Heavy Metal Door with Metal Posts -SW 6145 Thatch Brown or Similar



Trash Enclosure - Floor Plan N.T.S. To Be Used for This Project per City Trash Standard No. 57A


Site Trash Summary

Residential Apartments: 2 trash enclosures*
Daycare Building: 1 trash enclosure*

Note:

*Each trash enclosure contains one 4-yard waste bin, one 4-yard organics bin, and one 4-yard recycling bin.



**Instructional signs shall be provided for recycling.





1. Front Elevation

2. Side Elevation

3. Rear Elevation





Building 'A' - Area	
Level 1	± 5,620 G.S.F.
Level 2	± 5,205 G.S.F.
Level 3	± 2,615 G.S.F.
Total	± 13,440 G.S.F.




Level 2









UNIT TYPE P2-1
2 BEDROOM / 2 BATHROOM
#838 NET SF
#850 GROSS SF



UNIT TYPE P3-1
3 BEDROOM / 2 BATHROOM
#1,008 NET SF
#1,022 GROSS SF



UNIT TYPE P1-1
1 BEDROOM / 1 BATHROOM
#641 NET SF
#743 GROSS SF



UNIT TYPE P2-2
3 BEDROOM / 2 BATHROOM
#899 NET SF
#914 GROSS SF

3-Story Walk-Up Apartment Building
w/ Tuck Under Parking-Typical





PERSPECTIVE
FRONT VIEW OF 3-STORY WALK-UP

SCHEMATIC DESIGN
FEBRUARY 19, 2026

RTS

CASENTINI STREET FAMILY APARTMENTS
SALINAS, CA

MILESTONE HOUSING GROUP

888.456.5849 | ktgy.com
No. 20240276


ktgy

A6.1



LANDSCAPE CALCULATIONS per SEC. 37-50.690:
• SEE SHEET L3 FOR LANDSCAPING AREA CALCULATIONS FOR OVERALL SITE
LANDSCAPE CALCULATIONS per SEC. 37-50.690(g)(3):
• SEE SHEET L3 FOR LANDSCAPING AREA CALCULATIONS FOR PARKING LOTS
REFERENCE NOTES:
• SEE SHEET L2 FOR PLANT PALETTE AND NOTES
• SEE SHEET L3 FOR HYDROZONE PLAN
• SEE SHEET L4 FOR WALL AND FENCE PLAN
EXISTING TREE SURVEY REPORT:
• PERFORMED BY SAWATREE ON 6/18/2025
BICYCLE PARKING NOTE:
BICYCLE PARKING REQUIRED: 12
BICYCLE PARKING PROVIDED: 12
ACCESSIBLE PATH OF TRAVEL
• • • • • PEDESTRIAN ACCESS TO PUBLIC SIDEWALK

MS



CONCEPTUAL LANDSCAPE PLAN
L-1

PLANNED UNIT DEVELOPMENT PERMIT
(PUD 2025-005) (SPR 2025-014) (ZONINGS: RA-2.1)
March 25, 2025

1" = 10' 0"

CASENTINI STREET FAMILY APARTMENTS • DAYCARE
SALINAS, CA

MILESTONE HOUSING GROUP
MONTEREY COUNTY HOUSING AUTHORITY
DEVELOPMENT CORPORATION

MS
LANDSCAPE
ARCHITECTURE

PLANT SCHEDULE				
SYMBOL	BOTANICAL / COMMON NAME	SIZE	WUCOLS	QTY
TREES				
	ABUTILUS X 'MARINA'	36" BOX	LOW	10
	MARINA STRAWBERRY TREE STANDARD	24" BOX	MODERATE	19
	CECIS CANADENSIS 'FOREST PANET'	24" BOX	VERY LOW	24
	FOREST PANET EASTERN REDBUD	24" BOX	MODERATE	6
	CECIS OCCIDENTALIS	24" BOX	LOW	18
	WESTERN REDBUD	24" BOX	MODERATE	6
	GINKGO BILOBA 'AUTUMN GOLD'	24" BOX	LOW	18
	AUTUMN GOLD MAIDENHAIR TREE	24" BOX	MODERATE	6
	ASTROPHILES ANUTIFOLIA	24" BOX	LOW	18
	TOYON	24" BOX	MODERATE	6
	OLEA EUROPAEA 'SWAN HILL'	48" BOX	MODERATE	6
	SWAN HILL FRUITLESS OLIVE	48" BOX	MODERATE	6
	PSTACIA CHINENSIS 'KEITH DAVEY'	36" BOX	LOW	8
	KEITH DAVEY CHINESE PISTACHE	36" BOX	LOW	8
	PLATANUS RACHIOSA	24" BOX	LOW	5
	CALIFORNIA SYCAMORE	24" BOX	LOW	5
	QUERCUS AGRIFFOLIA	24" BOX	LOW	7
	COAST LIVE OAK	24" BOX	LOW	7
	QUERCUS SHUMARDII	24" BOX	MODERATE	18
	SHUMARD OAK	24" BOX	MODERATE	18
SCREENING				
	QUERCUS NOBILIS	15 GAL	LOW	41
	O BAY LAUREL - COLUMNAR	15 GAL	LOW	41
STREET TREES				
	LIQUIDAMBAR STRACIFOLIA	24" BOX	MODERATE	7
	'NOT UNUSUALIA'	24" BOX	MODERATE	7
	SWHET GUM	24" BOX	MODERATE	7
	STREET TREE IN S' PARKWAY	24" BOX	MODERATE	7
TOTAL QTY: 189				
SHRUBS				
	SEE SHEET L3 FOR PROPOSED SHRUB LIST	4" O.C. SPACING	APPROX. 5,598	



LANDSCAPE SECTION

SCALE: 1" = 1'-0"

Labels in drawing: FOREGROUND SHRUBS, MIDDLE GROUND TREES, BACKGROUND SHRUBS

CONCEPTUAL PLANS DEMONSTRATE THAT THIS DEVELOPMENT SATISFIES THE FOLLOWING GUIDELINES:

1. PROVIDES VISUAL SCREENING, PRIVACY, AND NATURAL SURVEILLANCE, WHERE NEEDED
2. DEFINES PEDESTAL PATHWAYS AND OPEN SPACE AREAS WITH LANDSCAPE MATERIALS
3. PROVIDES FOCAL POINTS WITH A DEVELOPMENT, SUCH AS SPECIEM TREES, HEDGES, FLOWERING PLANTS, AND PEDESTRIAN AMENITIES.
4. USES A COMBINATION OF PLANTS FOR YEAR-ROUND COLOR AND INTEREST
5. USES LANDSCAPE TREATMENTS TO ENHANCE THE SCREENING OF OUTDOOR STORAGE AND MECHANICAL EQUIPMENT AREAS.

[illegible]

PER ZONING CODE SECTION 17-20.210	
<u>TOTAL LOT AREA:</u>	198,960 S.F. (4.53 ACRES)
<u>REQUIRED LANDSCAPE AREA:</u>	198,960 S.F. = 4.0% = 198,960 S.F. (0.46 ACRES)
<u>PROPOSED LANDSCAPE AREA:</u>	77,440 S.F. (1.78 ACRES) (24%)

LOCATION:	PARKING LOT TOTAL AREA	INTERIOR LANDSCAPE PROVIDED:
DANFORTH CENTER:	7,224 sf	1,591 sf (22%)
LEASING & REC. AREA:	2,420 sf	482 sf (20%)
TANDEM PARKING at DOG PARK:	3,014 sf	633 sf (21%)
TANDEM PARKING at BIOPRETENTION BASIN:	1,028 sf	0 sf (0%)
TANDEM PARKING at GROUP BBO AREA:	3,322 sf	136 sf (4%)
PARKING LOT EAST of BUILDING 1:	1,600 sf	498 sf (31%)
TOTAL PARKING LOT LANDSCAPING:	19,608 sf	3,711 sf (19%)

PURPOSE: TO PROVIDE THE PROPERTY MANAGEMENT STAFF A MECHANICAL DEVICE TO DISTRIBUTE WATER AND ENSURE PLANT SURVIVAL IN THE MOST EFFICIENT MANNER AND WITHIN A TIME FRAME THAT LEAST INTERFERES WITH THE ACTIVITIES OF THE FLEET/IRIGATION. COMPATIBLE WITH THE AREA CONCEPT, THE SYSTEM WILL NOT STAIN THE SOIL. THE SYSTEM WILL BE CONTROLLED BY A BEING WATERED AND NOT BY A TIME SCHEDULE. THE SYSTEM WILL BE CONTROLLED BY A SMART CONTROLLER. VALVES PROGRAMMED FROM AUTOMATIC CONTROLLERS WILL MAXIMIZE EFFICIENT WATER APPLICATION.

DETECT ANY BROKEN DOUBLE CHECK VALVE. LEAKING TO OTHER SYSTEMS, ADVANCING TO THE NEXT WORKABLE STATION. IN THE EVENT OF PRESSURE SUPPLY LINE BREAKAGE, IT WILL COMPLETELY STOP THE OPERATION OF THE SYSTEM. ALL MATERIAL WILL BE NON-FERROUS, WITH THE EXCEPTION OF THE BRASS PIPING INTO AND OUT OF THE BACKFLOW UNITS. ALL WORK WILL BE IN THE BEST ACCEPTABLE MANNER IN ACCORDANCE WITH APPLICABLE CODES AND STANDARDS PREVAILING IN THE INDUSTRY.

LANDSCAPE PLANS WILL ADHERE TO THE CITY OF SALINAS WATER EFFICIENT LANDSCAPE ORDINANCE
WILCOX'S DATA BASED ON CITY OF SALINAS, REGION 1

LINE-OF-SIGHT NOTE:
 PLUM BBS TO BE MAINTAINED AT MAXIMUM 24" HIGH WITHIN LINE OF SIGHT AT STREET INTERSECTIONS.

ALL PROPOSED SHRUBS will be COMPLIANT with CITY OF SALINAS LANDSCAPE STANDARDS and GUIDELINES. **ALL PROPOSED SHRUBS will be COMPLIANT with CITY OF SALINAS LANDSCAPE STANDARDS and GUIDELINES**

BOTANICAL NAME	COMMON NAME	WT.	CL. MATR.
ASPHAGNUM DESFILORUS MYERS	MYERS ASPHAGNUS	5 GAL	Med.
BIUMS MORPHOLIA GREEN BEAUTY	GREEN BEAUTY BOXWOOD	5 GAL	Med.
DANIELA REVOLUTA LITTLE RUE	LITTLE RUE DANIELA	1 GAL	Med.
FESTUCA GLAUCA ELIAN BLUE	BLUE FESCUE	1 GAL	Med.
HENOCALLIS X STARBURST	EVERGREEN DANIEL	5 GAL	Med.
LAVANOLA DENTATA	FRENCH LAVENDER	5 GAL	Low
MAQUINA REPENS	CREeping BARRBERY	1 GAL	Low
PITOSPORA TOBIJA WHEELERS DWARF	DWARF MAICK ORANGE	5 GAL	Low
ROSA X RED CARPET	CARPET ROSE	5 GAL	Med.
ROSMARINUS OFFICINALIS PROSTRATUS	DWARF ROSEMARY	5 GAL	Low
THACHOLEPANDIA JASMINOIDES	STAR JASMINE	1 GAL	Med.

[illegible]

BOTANICAL NAME	COMMON NAME	SPR	SLANT	MO
ABUTILON UNDO COMPACT*	DWARF STAMBERG TREE	5 GAL	Low	Mod.
ADONIS AETHEAS	FEATHER REED GRASS	5 GAL	Low	Mod.
CALLAEAGRIS X A. KARL FORSTER	DWARF BUTTERFLY	5 GAL	Low	Mod.
CALISTEGIA CRISTUS BETTER JOY*	BUSH ANEMONE	15 GAL	Low	Mod.
CARPENTARIA CALIFORNICA	SANTA BARBARA Ceanothus	15 GAL	Low	Mod.
CEANOTHUS IMPRESSUS PLUGET BLUE	COTONMASTER	5 GAL	Low	Mod.
COTONMASTER SP.	COTONMASTER	5 GAL	Low	Mod.
DIETES 'DANCING DROP'	FOXTAIL LILY	5 GAL	Low	Mod.
DODONAEA 'NIGELLA PURPUREA'	PURPLE HOPSEED BUSH	15 GAL	Low	Mod.
DRACOPIS X 'NIGELI'	GREVILLEA	5 GAL	Low	Mod.
OLEA EUROPAEA 'LITTLE OLIVE'	LITTLE OLIVE OLIVE	5 GAL	Low	Mod.
OLEA EUROPAEA 'LITTLE OLIVE'	LENAHORE BERRY	15 GAL	Low	Mod.
RHUS INTEGRIFOLIA	RED-TIPPED PHOTINIA	5 GAL	Low	Mod.
PHOTINIA FRASER	MOCK ORANGE	5 GAL	Low	Mod.
PITTOSPORUM TORIBA	VARIEGATED MOCK ORANGE	5 GAL	Low	Mod.
PITTOSPORUM TORIBA 'MAREGATA'	ITALIAN BUCKTHORN	5 GAL	Low	Mod.
PRUNUS X AETHEAS	ITALIAN BUCKTHORN	5 GAL	Low	Mod.

ALL PROPOSED PLANTS will be COMPLIANT with CITY OF SALINAS LANDSCAPE STANDARDS and GUIDELINES

BOTANICAL NAME	COMMON NAME	SIZE	CALMNESS	LOW
ACHILLEA MILLEFOLIUM	YARROW	1 GAL	*	Low
BROMUS CARIINATUS	CALIFORNIA BROME	1 GAL	*	Low
BROMUS CARIINATUS	CALIFORNIA BROME	1 GAL	*	Low
CAREX CONSPICUA	SLOUGH SEDGE	1 GAL	*	Low
CISTACEA MINUTA	INDIAN PANTRUBUSH	1 GAL	*	Low
DESMODIUM CAESPITOSA	TUFTED HARRISSES	1 GAL	*	Low
LEWISIA CONDENSATIS	CANYON PRINCE	1 GAL	*	Low
MULHBERGIA RIENS	DEER GRASS	1 GAL	*	Low
JUNCUS PATENS	SPREADING RUSH	1 GAL	*	Low

ALL PROPOSED PLANTS will be COMPLIANT with CITY OF SALINAS LANDSCAPE STANDARDS and GUIDELINES

SYMBOL	BOTANICAL COMMON NAME	SIZE	WUCOLS	QTY
TREES	ABUTILON X 'HARINA'	36"BOX	LOW	10
	HARINA STRAWBERRY TREE STANDARD	36"BOX	LOW	10
	CECIS CANADENSIS 'FOREST PANSY'	24"BOX	MODERATE	19
	FOREST PANSY EASTERN REDBUD	24"BOX	MODERATE	19
	CECIS OCCIDENTALIS WESTERN REDBUD	24"BOX	VERY LOW	24
	GRINGO BLOOM AUTUMN GOLD 2'	24"BOX	MODERATE	6
	AUTUMN GOLD PANDANUS TREE	24"BOX	LOW	18
	HETEROPHELOS ARBUTIFOLIA TOTO	24"BOX	LOW	18
	OLEA EUROPEA 'SWAN HILL'	48"BOX	MODERATE	6
	SWAN HILL FRUITLESS OLIVE	48"BOX	MODERATE	6
SHRUBS	MYRTICA CHINESE 'KEITH DAVEY'	36"BOX	LOW	8
	KEITH DAVEY CHINESE MYRTACHE	36"BOX	LOW	8
	PLATANUS RACEMOSA CALIFORNIA SYCAMORE	24"BOX	LOW	5
	QUERCUS AGRIFOLIA COAST LIFE OAK	24"BOX	LOW	7
	QUERCUS SHUMARDII SHUMARD OAK	24"BOX	MODERATE	18

SCREENING	LAURUS NOBILIS	15 GAL	LOW	41
○	RAY LAUREL - COLUMBAR			
STREET TREE				
	LIQUIDAMBAR STRACIFELIA		MODERATE	7
	HOT LIPS OLEA			
	ROUND LEAVED SWEET GUM			
	STREET TREE IN S PARKWAY			
				TOTAL QTY: 189

SHRUBS	SEE SHEET L3 FOR PROPOSED SHRUB LIST	4' O.C. SPACING	APPROX. 5,598
--------	--------------------------------------	-----------------	---------------

[illegible]

ALL ABOVE-GROUND UTILITY EQUIPMENT WILL BE SCREENED FROM PUBLIC VIEW WITH A MINIMUM 3" WIDE PLANTING AREA. PROPOSED SCREEN SHRUB WILL BE 15 GALLON SIZE SPACED TO SCREEN 75% OF UTILITY AT THE TIME OF PLANTING.

BOTANICAL NAME	COMMON NAME	SIZE	CALCULATING	WATER
CORPORA VIRIDI	TRAILING CORPORA	1 GAL		Low
MULHENERGIA REIGNS	DEER GRASS	1 GAL	*	Low
MYOPORIUM PARSIFOLIUM	DWARF MYOPORIUM	1 GAL		Low
ROSEMARYNIUS OFFICINALIS	DWARF ROSEMARY	1 GAL		Low

**MILESTONE HOUSING GROUP
MONTEREY COUNTY HOUSING AUTHORITY
DEVELOPMENT CORPORATION**

WALL AND FENCE LEGEND

SITE RETAINING WALLS, SEE DRAWINGS BY CIVIL ENGINEER, TAN SPLIT FACE FINISH, ONE SIDE.

EXISTING 6' HT. WOOD FENCE, PROTECT IN PLACE, PAINT PROJECT SIDE, COLOR TO MATCH EXISTING

EXISTING CHAINLINK FENCE, PROTECT IN PLACE

NEW 6' HT. CHAINLINK FENCE AT 15' SETBACK FROM TOP OF BANK


NEW 6' HT. CHAINLINK FENCE AT 10' SETBACK FROM TOP OF BANK


NEW 3' HT. CHAINLINK FENCE AT BIO-RETENTION BASIN WITH GATE


NEW 6' HT. FENCE ON LOW RETAINING WALL TO MATCH EXISTING FENCE COLOR


EVA GATE


NOTE: EXISTING ACCESS GATE WILL BE PROTECTED AND MAINTAINED. NEW GATE SHALL BE CONSTRUCTED TO MATCH EXISTING GATE. GATE SHALL BE 10' WIDE AND 6' HIGH. GATE SHALL BE 10' WIDE AND 6' HIGH. GATE SHALL BE 10' WIDE AND 6' HIGH.











City of Salinas

COMMUNITY DEVELOPMENT DEPARTMENT


65 W. Alisal Street • Salinas, California 93901
(831) 758-7251 • (831) 758-7938 (Fax) • www.ci.salinas.ca.us

PLANNING APPLICATION REVIEW - BUILDING

Date: 9/25/2025
Application: SPR2025-014
Address: 200 CASENTINI ST
Scope: 88 affordable multi-family units
Contact: Contact
Planner: Son Pham

1. Soils report for proposed work will be required at building permit submittal.
NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.
2. The occupancy classification, construction types, building area analysis, fire sprinklered for all proposed structures for Specific Building comments will be generated upon building permit submittal. Building permit shall comply with California Code of Regulations, Title 24
NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.
3. Please show accessible path of travel from the main entry connecting the structures to the public way, trash enclosure, and accessible parking.
NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.
4. Multifamily dwellings constructed for first occupancy after March 13, 1991 shall comply with the accessibility requirements of the California Building Code Chapter 11A. Verify accessible residential units are provided.
NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.

Exhibit C



City of Salinas

COMMUNITY DEVELOPMENT DEPARTMENT

65 W. Alisal Street • Salinas, California 93901

(831) 758-7251 • (831) 758-7938 (Fax) • www.ci.salinas.ca.us

5. Verify the private balconies and adjacent doors and windows can comply with fire protection features as designed. See section 705 for exterior balconies and opening protectives.

NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.

6. Verify all fire rated construction, opening areas comply with the requirements of CBC chapter 7.

NO RESPONSE REQUIRED. REQUIREMENTS TO BE VERIFIED AT BUILDING PERMIT SUBMITTAL.

7. At least ninety days prior to building permit application, please set up a meeting with the Chief Building Official to discuss the process and expectations for proposed development.

- Plans
- Approximate timelines for applications and construction
- Fees
- Turn-around-times
- Special inspections,
- Deferred/Separate submittals (trusses, sprinklers, P.V. systems, etc)

NO RESPONSE REQUIRED UNTIL APPLICANT IS CLOSE TO PERMIT SUBMITTAL

8. Specific Building comments will be generated upon building permit submittal. Building permit shall comply with California Code of Regulations, Title 24.

NO RESPONSE REQUIRED

(End of Comments)

Raul Ortega

City of Salinas Permit Services

Community Development Department



City of Salinas

SALINAS FIRE DEPARTMENT

Fire Prevention Division – Office of the Fire Marshal

200 Lincoln Avenue • Salinas, California 93901

(831) 758-7466 • fireprevention@ci.salinas.ca.us

Plan Review Notes

Date:	March 10, 2026
Project Number	PUD2025-003, SPR2025-014 & CUP2025-025
Owner Name	INTERIM, INC. Monterey County Housing Authority
Applicant Name	Milestone Housing Group
Address	200 Casentini Street
Project Description	AMENDMENT TO A PLANNED UNIT DEVELOPMENT PERMIT (PUD 92-006) - PUD 2025-003; A REQUEST TO CONSTRUCT 88 AFFORDABLE MULTI-FAMILY HOUSING UNITS (SPR 2025-014) WITH A DAY CARE CENTER (CUP 2025-025) LOCATED AT 200 CASENTINI STREET IN THE RESIDENTIAL HIGH DENSITY (R-H-2.1) ZONING DISTRICT
Plan Review Sequence	1 st Review - SPR2025-014 & CUP2025-025 2 nd Review - PUD2025-003 3 rd Review - PUD2025-003, SPR2025-014 & CUP2025-025 4 th Review - PUD2025-003, SPR2025-014 & CUP2025-025
<i>Plans for the above-referenced project have been reviewed. Revisions are required.</i>	
1. <u>Fire Safety Requirements – General</u> – The fire safety requirements recorded with the original planned unit development PUD92-006 are hereby superseded by the fire safety requirements set forth in PUD2025-003. RESPONSE REQUIRED: None	
2. <u>Fire Sprinkler Standard</u> The fire sprinkler standards that will apply to this project are as follows: a. Amenity/Leasing Office (Group B and Group A occupancies) – NFPA 13 – This fire sprinkler system is optional under the Salinas Municipal Code and is being proposed as an option of the applicant. b. Apartment Buildings (Group R-2 occupancy) – NFPA 13R or NFPA 13, pursuant to the determination by the Building Official. The fire sprinkler standard will be a minimum of NFPA 13R, but may be upgraded to NFPA 13 based on building code requirements determined during plan review due to fire separation distance, allowable building area, type of construction, etc. The architect shall clearly	

Exhibit D

indicate on the plans the fire sprinkler standard that is intended to be considered during building permit plan review.

- c. Child Care Center – NFPA 13 – If this childcare center is classified as a Group E occupancy, then fire sprinkler system is proposed as an option of the applicant. If the facility is classified as a Group I-4 occupancy, it will be a required fire sprinkler system.

RESPONSE REQUIRED: At the time of building permit submittal, Include the appropriate code analysis.

3. **Fire Flow** – Add the following note to the plans:

Fire flow shall be provided at a minimum rate of 1,500 gpm with a residual pressure of 20 psi for a duration of 2 hours.

This fire flow rate is based on the largest building with a fire area of 26,950 square feet and Type V-B construction as listed in Table B105.2 of the California Fire Code, with reduction granted per Footnotes a. and b.

RESPONSE REQUIRED: At the time of building permit submittal, Add this note on the plans, and ensure it is on the plans presented with the fire service application to California Water Service.

4. **Fire Hydrant Relocation – Sheet C3.0** – Relocate the existing fire hydrant located on the west side of the proposed apartment complex driveway to the east side. This relocation will increase access to the hydrant for both the apartment complex and the childcare center. Refer to the markup image below.

RESPONSE REQUIRED: None. Utility site plans have been revised to reflect this installation during construction.

5. **Fire Service Connection Location – Sheet C3.0 - Amenity/Leasing & Apartment Bldgs.** – The fire service connection to California Water Service and the Fire Backflow Preventer can be combined for the amenity/leasing building and the apartment buildings, but the fire department connections (“FDCs”) and post indicating valves (“PIVs”) shall be installed separately for each sprinklered building.

RESPONSE REQUIRED: At the time of building permit submittal, Revise this note on the plans.

6. **Fire Service Connection Location – Sheet C3.0 – Child Care Center** – The fire service connection to California Water Service and the Fire Backflow Preventer shall be separate for the childcare center. The Fire Backflow Preventer shall include the following features:
 - a. tamper switches connected to the childcare center fire alarm system
 - b. fire department connection with two 2-1/2” inlets and Knox brand locking FDC caps

RESPONSE REQUIRED: At the time of building permit submittal, reflect these fire protection devices on the utility plans.

7. Maximum Occupant Load – Leasing & Amenity Bldg. – Club Room – Sheet A3.4 –

The Club Room is proposed to have an area of 478 square feet. As an assembly use, the space has a maximum occupant load of 68 based on concentrated use without fixed seating or tables (478 sq. ft./7 occupant load factor), and therefore, two (2) exits would be required from the Club Room space.

RESPONSE REQUIRED: At the time of building permit submittal, Revise the plans to reflect the exiting and path of travel pursuant to California Building Code Chapter 10, Table 1006.2.1, Table 1004.5., Section 1009.

8. Fire Lanes – Add details to the plans for fire lane designations including painted red-curbs marked with “NO PARKING – FIRE LANE” per California Fire Code Section 503.3.

RESPONSE REQUIRED: At the time of building permit submittal, Add fire lane details to the plans.

9. Knox Box – Add details to the plans as follows pursuant to California Fire Code Section 506:

a. Site locations

- i. Leasing & Amenity Building exterior wall next to its main entrance
- ii. Childcare Center exterior wall next to its main entrance

b. Building locations – Knox boxes shall be mounted between four and six feet above ground (floor) level, readily visible and not more than 12 feet from the main entry of the premises.

c. Required Keys – The following keys shall be provided: (1) grand master key; (1) fire alarm cabinet key. All utility, mechanical and amenity/leasing building keys shall conform to a master key system.

RESPONSE REQUIRED: At the time of building permit submittal, Add Knox box details and specification notes to the plans.

10. Portable Fire Extinguishers - Per California Fire Code Section 906, portable fire extinguisher(s) with a minimum rating of 2A:10B:C shall be installed and maintained on an approved bracket or cabinet at the following locations:

- a. Apartment buildings - Centrally located on the building exterior on each level within a maximum travel distance of 75 feet from each Group R-2 dwelling unit, **or** one (1) portable fire extinguisher mounted and maintained on an approved bracket or cabinet inside each of the Group R-2 dwelling units.
- b. Leasing & Amenity Building – One (1) portable fire extinguisher in the lobby and one (1) in the Club Room.
- c. Child Care Center – The fire extinguisher locations can be determined at the time of building permit application.

RESPONSE REQUIRED: At the time of building permit submittal, Revise the plans to reflect these fire extinguisher locations and specifications.

11. Address Posting

Add a note to the plans as follows:

- (a) *All residential including multifamily residential addresses must be clearly identified with a number/letter a minimum of three and one-half inches high and one-half inch stroke and located on or adjacent to the entrance. If provided, the address(es) shall be placed on the freestanding or monument sign corresponding to the adjacent building(s).*
- (b) *Clustered units/apartments/condominiums shall have a single number/letter for the cluster posted where it is clearly identified from the street or road. Individual units in the cluster will be numbered alphabetically or numerically with letters a minimum of three and one-half inches high and located on or adjacent to the entrance of the unit.*
- (c) *A directory board is required at the entrance of the apartment complex indicating the direction and building number or letter. Where a building is set back from the street or road, the address number or letter shall be determined for both the street approach and on the building, in accordance to the following standards:*
 - (1) *Zero to thirty-foot distance: four inches minimum height and one-half inch minimum stroke width.*
 - (2) *Thirty-one to fifty-foot distance: six inches minimum height and three-fourths inch minimum stroke width.*

RESPONSE REQUIRED: At the time of building permit submittal, Print this note and include address specifications on the plans.

12. Building Identification - Add the following details to the plans:

- a. All buildings (except the trash enclosures) shall be clearly identified by a sign with numbers or letters with a minimum height of 6 inches on a contrasting background.
- b. All buildings shall have building identification numbers or letters installed on the sides facing the fire access road and on the back side.

RESPONSE REQUIRED: At the time of building permit submittal, Print this note and include building identification sign specifications on the plans.

13. Emergency Access Gate – Add the following note to the plan:


An emergency access gate is required for fire department use at the northwest end of the fire access road. The gate shall be secured with a standard padlock capable of being removed by fire personnel with a bolt cutter. Signage shall be posted and maintained on both sides of the gate that reads "EMERGENCY ACCESS – DO NOT BLOCK".

RESPONSE REQUIRED: At the time of building permit submittal, Print this note on the plans.

14. Fire Apparatus Access Road – Revise the driveway detail to reflect the fire apparatus access road weight-rating requirements of Section 503.2.3 of the California Fire Code as amended in the City of Salinas Municipal Code.

RESPONSE REQUIRED: At the time of building permit submittal, revise this detail and specification on the roadway improvement plans.

Plans reviewed by: DOROTHY PRIOLO, Deputy Fire Marshal



City of Salinas

DEVELOPMENT ENGINEERING (PW) • 65 West Alisal Street • Salinas, California

Phone: (831) 758-7251 • www.cityofsalinas.org

ENGINEER'S REPORT

PURPOSE: CUP2025-025, SPR2025-014 & PUD2025-003 **DATE:** 3/18/2026
LOCATION: 200 Casentini St **PLANNER:** Son Pham
APPLICANT: Milestone Housing Group **REVIEWER:** Fernando Rizo, QSD
ENGINEER: BKF Engineers Assistant Engineer

DEVELOPMENT PROPOSAL: Amendment to PUD92-006 – Multi-family housing project

RECOMMENDATION: Approved with Conditions

SWDS THRESHOLD: Performance Requirement 1, 2, 3 & 4.

NPDES CATEGORY: High Priority

DEVELOPMENT REVIEW: *Development Review Submittal prepared by KTG Group, Inc. and BKF Engineers dated October 20, 2025.*

DEVELOPMENT IMPACT FEES:

Development Impact Fees – Development impact fees are estimated at \$1,730,170.75. Fees are assessed and due prior to issuance of a building permit. Fees are based on the 2010 Traffic Improvement Program and Institute of Transportation Engineers Trip Generation.

CONDITIONS OF APPROVAL:

1. Riparian Setback – The project appears to encroach into the 100'-setback from the top of the Reclamation Ditch, provide setback reference. Clearly delineate the 100-setback from the top of ditch. If applicant wishes to explore encroaching into the 100'-setback a biotic study shall be prepared under the direction of the City of Salinas Planning Department. The proposed chain-link fence shown is acceptable to City staff based on existing topography conditions.
2. Utility Plan – Provide more information pertaining to existing storm drain easement and the impacts of proposed improvements and building foundation. Provide depth of existing storm drain line closest to proposed buildings.
3. Grading and Drainage Plan – Provide final grading and drainage plan showing all proposed finished elevations and grades.
4. Utility Plan – Provide final utility plan showing all proposed grate elevation, piping size, material type and slope.
5. Site Plan – Access shall be maintained to existing City of Salinas Drainage Easement. Existing slope and sidewalk easements may be abandoned.
6. Site Plan - Proposed trash enclosure shall conform with City of Salinas 57A. Provide 2' minimum landscape strip, 2" weep holes, and concrete pad drainage patterns flowing towards required weep holes and landscaping strip.
7. Offsite Improvements – An ADA compliant sidewalk is required at all driveways. Indicate if the project provides a 4-foot-wide minimum ADA-compliant sidewalk. If not, applicant shall obtain an encroachment permit to reconstruct the driveway to provide an ADA compliant sidewalk.
8. Offsite Improvements - Identify any sidewalk damage that may cause someone to trip and fall on

Exhibit E

the sidewalk along your frontage. In accordance with City Resolution No. 4926 and State Code 5610, maintenance of the sidewalk is the responsibility of the property owner.

9. Offsite Improvements – Per City Standards, street trees are required at a maximum of 60-ft spacing based on street frontage. For this property a minimum of six (6) trees are required. If the existing improvements or the site cannot accommodate six street trees, the applicant shall pay the street tree impact fee in lieu of the street tree installation.
10. Offsite Improvements – Street lighting will be required along frontage. Provide photometric plan showing conformance.
11. Offsite Improvements – Any construction, reconstruction, or closure of the right of way shall require an encroachment permit.
12. SWDS Compliance – Prior to issuance of a building permit, applicant shall provide a final stormwater control plan consistent with Appendix B of SWDS.
13. SWDS Compliance – A Stormwater Quality (SWQ) Permit will be required prior to any land disturbance.
14. SWDS Compliance – Landscaping plans shall be submitted for proposed bio-retention facilities, and these shall comply with City of Salinas 2021 Stormwater Design Standards.
15. Geotechnical Report – Provide a site-specific geotechnical report which includes infiltration testing at the proposed infiltration depths.
16. Addressing – Prior to building permit issuance, any change in addressing shall be processed via a addressing change application.
17. NPDES/Site Disturbance – Prior to issuance of a building/grading permit, applicant shall provide a SWPPP for review. Provide complete information including QSP information, required signatures and construction schedule. Provide completed erosion and sediment control checklist.
18. NPDES Compliance – Applicant shall provide construction BMPs for site improvements.

Notice: The Conditions of Approval for this Site Plan Review include certain fees and development requirements. Pursuant to Government Code Section 66020 (d)(1), this hereby constitutes written notice stating the amount of said fees and describing the development requirements. The applicant is hereby notified that the 90-day appeal period in which he/she/they may protest these fees and development requirements, pursuant to Government Code Section 66020 (a), begins on the date the office land use permit is approved. If applicant files a written protest within this 90-day period complying with all requirements of Section 66020, he/she/they will be legally barred from challenging such fees and/or requirements at a later date.

DEVELOPMENT FEES (By Unit Size)

RESIDENTIAL UNITS (2025-2026)

Address: 200 Casentini St		Permit #: ESTIMATE ONLY					
No. of Units Demolished: 0	No. of Proposed Units: 88						
No. of Proposed Bedrooms: 192	Type of Unit Proposed: Multi Family Residence						
No. of Bedrooms Demolished: 0	Type of Unit Demolished: Multi Family Residence						
1. STREET TREE FEE		2304.00.0000-56.5110					
Street Frontage (LF)	multiplier (per 60' frontage): \$ -	Not assessed if provided by applicant.					
TOTAL STREET TREE FEE DUE: \$ -							
2. PUBLIC UTILITY IMPACT FEE							
Building Square Footage (Credit):		0					
Building Square Footage:		121,240					
Fee per Square Foot of Building Area:		\$ 1.31					
TOTAL SANITARY SEWER FEE DUE:		\$ 158,824.40 2301.00.0000-56.5120					
Fee Per Bedroom:		\$ 707.00					
TOTAL STORM DRAIN FEE DUE (Do Not Assess For Mixed Use):		\$ 135,744.00 2301.00.0000-56.5130					
3. TRAFFIC IMPACT FEE							
7	Trip Rate Per Proposed Unit(s)	Total Proposed Trips:	616				
0	Trip Credits	Net Trips:	616				
		Fee Per Trip:	\$ 470.00				
TOTAL TRAFFIC IMPACT FEE DUE:		\$ 289,520.00 2306.00.0000-56.5150					
4. REGIONAL DEVELOPMENT IMPACT FEE							
Fee assessed by the Transportation Agency for Monterey County		\$ 82,032.54	Per attached TAMC worksheet. 8809.81.8157-57.8640				
5. PUBLIC FACILITIES IMPACT FEES							
UNIT FEE SCHEDULE							
Bedrooms	Unit Size	No. Units	Fire	Police	Library	Recreation	Parks
1	743	24	\$ 5,544.00	\$ 30,552.00	\$ 21,744.00	\$ 12,120.00	\$ 106,272.00
1	950	16	\$ 4,496.00	\$ 24,864.00	\$ 17,696.00	\$ 9,856.00	\$ 86,464.00
2	1072	4	\$ 1,380.00	\$ 7,656.00	\$ 5,444.00	\$ 3,028.00	\$ 26,612.00
3	1141	40	\$ 13,800.00	\$ 76,560.00	\$ 54,440.00	\$ 30,280.00	\$ 266,120.00
3	1162	4	\$ 1,380.00	\$ 7,656.00	\$ 5,444.00	\$ 3,028.00	\$ 26,612.00
			\$ -	\$ -	\$ -	\$ -	\$ -
Subtotal:			\$ 26,600.00	\$ 147,288.00	\$ 104,768.00	\$ 58,312.00	\$ 512,080.00
Credits by Unit/Bedroom:							
PUBLIC FACILITIES IMPACT FEES DUE:			\$ 26,600.00	\$ 147,288.00	\$ 104,768.00	\$ 58,312.00	\$ 512,080.00
TOTAL DEVELOPMENT FEES DUE:					\$ 1,515,168.94		

Effective: July 1, 2025

Valid through: June 30, 2026

Regional Development Impact Fees

Fee Calculation Worksheet
Last updated July 1, 2024

Project Name:

Date:

Select the Benefit Zone:	GREATER SALINAS
Select the Agency:	City of Salinas

Select the Land Use Type:	Fee Schedule	Enter the # of Units	Fees
1 Apartment (Low Income)	\$1,713.66	88	\$150,802.22
2	\$0.00		\$0.00
3	\$0.00		\$0.00
4	\$0.00		\$0.00
5	\$0.00		\$0.00
Calculate by Fee per Trip (Only use for appeals)		\$442	\$0.00
Subtotal:			\$150,802.22
Apply discount: 45.60%			\$68,769.68
Apply credits:			\$0.00
Total Regional Fee:			\$82,032.54

DEVELOPMENT FEES

COMMERCIAL BUILDINGS (2025-2026)

(Including Hotels/Motels/Schools)

Address: 200 Casentini St				Permit #: ESTIMATE ONLY	
Date: 08/21/25				Bldg. Area: 2,400 sf	
1. STREET TREE FEE:					2304.00.0000-56.5110
0	Street Frontage (LF)	multiplier (per 60' frontage)	\$426:	\$ -	Not assessed if provided by applicant
TOTAL STREET TREE FEE DUE:				\$ -	
2. SANITARY SEWER FEE:					2301.00.0000-56.5120
Building Square Footage:			2400		
\$1.14/sf (Commercial):			\$ 2,736.00		
\$0.57/sf (Industrial):			\$ -		
TOTAL SANITARY SEWER FEE DUE:			\$ 2,736.00		
3. STORM DRAIN FEE:					2301.00.0000-56.5130
2,400	sf property	43,560 sf/acre:	0.055		
		@ \$8,978/acre:	\$ 494.66		
		(School Rate) @ \$7,161/acre:			
TOTAL STORM DRAIN FEE DUE:			\$ 494.66		
4. TRAFFIC IMPACT FEE:					2306.00.0000-56.5150
Building Square Footage:			2,400		
Use:	495	Divided by 1,000 :	2.400	0.000	0.000
Category:	Recreation Community Center	Trip Rate (TFO):	29		
Trips:			69	0	0
Total Trips:			69	Estimate per 2010 Traffic Improvement Program	
@ \$470/trip (\$680/trip in FGA):			\$ 32,508.96		
TOTAL TRAFFIC IMPACT FEE DUE:			\$ 32,508.96		
5. REGIONAL DEVELOPMENT IMPACT FEE					8809.81.8157-57.8640
Fee assessed by the Transportation Agency for Monterey County			\$ 16,634.60	Per TAMC fee schedule	
6. PUBLIC FACILITIES IMPACT FEE					
FIRE IMPACT FEE \$645/ksf (Commercial) =			\$ 1,548.00		
FIRE IMPACT FEE \$147/ksf (Industrial) =			\$ -		
POLICE IMPACT FEE \$858/ksf (Commercial) =			\$ 2,059.20		
POLICE IMPACT FEE \$573/ksf (Industrial) =			\$ -		
TOTAL PUBLIC FACILITIES IMPACT FEE			\$ 3,607.20		
TOTAL DEVELOPMENT FEES DUE:			\$ 55,981.41		

Effective: July 1, 2025

Valid through: June 30, 2026

Regional Development Impact Fees

Fee Calculation Worksheet

Last updated July 1, 2024

Project Name:

Date:

Select the Benefit Zone:

GREATER SALINAS

Select the Agency:

City of Salinas

Select the Land Use Type:	
1	
2	
3	
4	
5	

Fee Schedule

\$0.00
\$0.00
\$0.00
\$0.00
\$0.00

Enter the # of Units

Fees

\$0.00
\$0.00
\$0.00
\$0.00
\$0.00

Calculate by Fee per Trip (Only use for appeals):

\$442 69 \$30,579.75

Subtotal:

\$30,579.75

Apply discount:

45.60%

\$13,945.15

Apply credits:

\$0.00

Total Regional Fee:

\$16,634.60

Accessory Dwelling Units (ADU) - Senate Bill 13 (Wieckowski, 2019)

ADUs under 750 square feet are exempt from impact fees.

ADUs over 750 square feet are assessed impacts fees that are proportional to the size of the primary residence.

1. In the worksheet above, for "Select the Land Use Type", choose "Single-Family"
2. Next, calculate the proportion of the ADU to the main residence and enter that figure in "Enter the # of Units"

Primary Residence - Square Feet:

ADU - Square Feet:

Proportion:

DEVELOPMENT FEES

COMMERCIAL BUILDINGS (2025-2026)

(Including Hotels/Motels/Schools)

Address: 200 Casentini St		Permit #: ESTIMATE ONLY	
Date: 08/21/25		Bldg. Area: 4,335 sf	
1. STREET TREE FEE:		2304.00.0000-56.5110	
0	Street Frontage (LF) multiplier (per 60' frontage) \$426:	\$ -	Not assessed if provided by applicant
		\$ -	
TOTAL STREET TREE FEE DUE:		2301.00.0000-56.5120	
2. SANITARY SEWER FEE:			
Building Square Footage:		4335	
\$1.14/sf (Commercial):		\$ 4,941.90	
\$0.57/sf (Industrial):		\$ -	
		\$ 4,941.90	
TOTAL SANITARY SEWER FEE DUE:		2301.00.0000-56.5130	
3. STORM DRAIN FEE:			
4,335	sf property	43,560 sf/acre:	0.100
		@ \$8,978/acre:	\$ 893.47
(School Rate) @ \$7,161/acre:			
		\$ 893.47	
TOTAL STORM DRAIN FEE DUE:		2306.00.0000-56.5150	
4. TRAFFIC IMPACT FEE:			
Building Square Footage:		4,335	
Use:	565	Divided by 1,000 :	4.335
Category:	Day Care Center	Trip Rate (TFO):	48
		Trips:	206
		Total Trips:	206
		@ \$470/trip (\$680/trip in FGA):	\$ 97,023.37
		\$ 97,023.37	
TOTAL TRAFFIC IMPACT FEE DUE:		8809.81.8157-57.8640	
5. REGIONAL DEVELOPMENT IMPACT FEE			
Fee assessed by the Transportation Agency for Monterey County		\$ 49,646.15	Per TAMC fee schedule
6. PUBLIC FACILITIES IMPACT FEE			
FIRE IMPACT FEE \$645/ksf (Commercial) =		\$ 2,796.08	
FIRE IMPACT FEE \$147/ksf (Industrial) =		\$ -	
POLICE IMPACT FEE \$858/ksf (Commercial) =		\$ 3,719.43	
POLICE IMPACT FEE \$573/ksf (Industrial) =		\$ -	
		\$ 6,515.51	
TOTAL PUBLIC FACILITIES IMPACT FEE			
TOTAL DEVELOPMENT FEES DUE:		\$ 159,020.40	

Effective: July 1, 2025

Valid through: June 30, 2026

Regional Development Impact Fees

Fee Calculation Worksheet

Last updated July 1, 2024

Project Name:

Date:

Select the Benefit Zone:	GREATER SALINAS
Select the Agency:	City of Salinas

Select the Land Use Type:	Fee Schedule	Enter the # of Units	Fees
1	\$0.00		\$0.00
2	\$0.00		\$0.00
3	\$0.00		\$0.00
4	\$0.00		\$0.00
5	\$0.00		\$0.00

Calculate by Fee per Trip (Only use for appeals): \$442 206 \$91,265.61

Subtotal:		\$91,265.61
Apply discount:	45.60%	\$41,619.46
Apply credits:		\$0.00
Total Regional Fee:		\$49,646.15

Accessory Dwelling Units (ADU) - Senate Bill 13 (Wieckowski, 2019)

ADUs under 750 square feet are exempt from impact fees.


ADUs over 750 square feet are assessed impacts fees that are proportional to the size of the primary residence.

1. In the worksheet above, for "Select the Land Use Type", choose "Single-Family"
2. Next, calculate the proportion of the ADU to the main residence and enter that figure in "Enter the # of Units"

Primary Residence - Square Feet:

ADU - Square Feet:

Proportion:



City of Salinas

COMMUNITY DEVELOPMENT DEPARTMENT

65 W. Alisal Street, 2nd Floor • Salinas, California 93901
(831) 758-7387 • (831) 775-4258 (Fax) • www.ci.salinas.ca.us

DATE: August 20, 2025
TO: Son Pham-Gallardo, Senior Planner
FROM: Stephen Acker, Sr. Community Development Analyst
RE: Housing Division Comments – 1st Review – PUD 2025-003;
Application for Site Plan Review of proposed 100% affordable large family multi-family housing community with approximately 88 dwelling units on a 4.9 acre parcel.

The above referenced project is subject to the City of Salinas' Inclusionary Housing Ordinance. Per Section 17-16 of the Inclusionary Housing Ordinance, the owner/developer needs to address the comment below:

1. A Planned Unit Development (PUD) was submitted to the City on July 30, 2025, and it did not include an Affordable Housing Plan. The application provided indicates the proposed development of approximately 88 residential units. The Developer must state the number of housing units set aside for affordable housing under the City's Inclusionary Housing Guidelines and shall include it in the Affordable Housing Plan. The options can be found under the City's Inclusionary Housing Guidelines. The owner/developer needs to complete the provided Affordable Housing Plan template provided upon resubmittal. If the owner/developer is contemplating utilizing the Density Bonus Law to maximize the number of units produced in the Site Plan, this information needs to be included into the Affordable Housing Plan. If tapping into the Density Bonus Law, the owner/developer needs to also specify the Density Bonus percentage requested as well as any incentives, concessions, waivers, and reductions in the development standards being requested. All information needs to be detailed and integrated into the Affordable Housing Plan. Upon resubmittal, please provide a draft of the Affordable Housing Plan in PDF and Microsoft Word format to the City.

Response:

Exhibit F

Copies of the following are attached to assist in the completion of an Affordable Housing Plan submission:

- City of Salinas Inclusionary Ordinance
- City of Salinas Inclusionary Housing Guidelines
- Affordable Housing Plan Template

Prior to the approval of the Site Plan for the proposed subdivision or the issuance of a Building Permit, the project's Developer/Owner and City shall execute any of the following documents applicable to the project:

- Inclusionary Rental Regulatory Agreement and Occupancy Agreement and Declaration of Restrictive Covenants
- Density Bonus Rental Regulatory Agreement and Declaration of Restrictive Covenants (only if applicable)
- Marketing Plan for Inclusionary Housing Units
- Management Plan for Inclusionary Housing Units
- Management Plan for Density Bonus Housing Units (only if applicable)

Should the Owner require additional assistance or have any questions regarding the above comment, please contact Stephen Acker, Senior Community Development Analyst at 831-758-7375 or via e-mail at stephenac@ci.salinass.ca.us.



City of Salinas
COMMUNITY DEVELOPMENT DEPARTMENT

65 W. Alisal Street, 2nd Floor • Salinas, California 93901
(831) 758-7387 • (831) 775-4258 (Fax) • www.ci.salinas.ca.us

Affordable Housing Plan

Casentini Street Family Apartments
200 Casentini Street, Salinas, CA

Date: April 29, 2026

Project Description: Proposed development of a 100% affordable large family multi-family housing community with approximately 88 dwelling units on a 4.9-acre parcel. Residential program will include a tot-lot, sports court, dog run area, and a separate amenity/leasing building at the project frontage along Casentini Street. Project includes 89 garage parking stalls and 63 open parking stalls for a total of 152 residential parking spaces. In addition, the proposed project will include a roughly 4,335 square foot day care center with separate entry, parking, and play areas for children from newborn to five (5) years of age. A total of 16 parking spaces will be provided for staff and parent loading area.

Entitlement App. Date:	July 30, 2025
Project Address(es):	200 Casentini Street, Salinas, CA 93907
Project APN(s):	003-161-030-000
Owner(s):	The Housing Authority of the County of Monterey, a California Public Corporation
Developer(s):	Milestone Housing Group
Project Link To:	Amendment to a Planned Unit Development Permit (92-006) – PUD 2025-003; Site Plan Review (SPR 2025-014); Conditional Use Permit (CUP 2025-025).
Affordability Restriction:	55 Year Affordability (Density Bonus)
Inclusionary Option:	N/A. Per Section 17-8(f) of the Inclusionary Ordinance, this project is exempt from the Inclusionary housing requirements as it is 100% affordable.
Inclusionary Restricted Units:	0
Inclusionary Restricted Unit Mix:	0 Very Low Income 0 Low Income 0 Moderate

Density Bonus Request: Yes

Density Bonus Restricted
Units: 87

Density Bonus Restricted Unit Mix:	10	Extremely Low Income
	53	Very Low Income
	24	Low Income
	0	Moderate

Density Bonus
Waivers Requested:

1. The project applicant is requesting a waiver of Article V; Division 2; Section 37-50.360; Table 37-50.100 regarding required number of parking spaces per unit type. The project proposes a total of 88 units with 24 One-Bedroom Units, 24 Two-Bedroom Units, and 40 Three Bedroom Units. Per Table 37-50.100 of the City of Salinas Zoning Code Section 37-50.360, based on our unit mix, our required number of parking spaces is 163 spaces. Per the table below, also found in our Project Matrix on Sheet A1.0 of our Site Plan Review Application plan set, we are providing a total of 152 parking spaces. This reflects an eleven (11) stall deficit in the total required number of parking spaces.
2. The Project Applicant is requesting a waiver of Article XVIII – Regulating the Parking of Over-Size Vehicles under Section 20-18.020 prohibiting the ability to park vehicles exceeding 20 feet in length. Per Sheet A1.0: Site Plan, of our Site Plan Review Application plan set, our project data section reflects a total of 152 proposed parking stalls for our residential community. The table below shows the total number of parking stalls, the breakdown of parking stalls provided per unit type, and the breakdown of tandem parking stalls as part of the 152 total parking spaces provided. As such, of the 152 total parking spaces provided, there is a total of sixty-four (64) tandem parking spaces. This is separated as 40 tandem stalls in our parking garages within the residential buildings and another 24 tandem stalls in our surface parking areas.
3. Our proposed large family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 of the Zoning code under Table 37-30.80 requires that 10% of all dwelling units in our project include 4 or more bedrooms. As reflected above in our unit and AMI breakdown, our project includes a total of 87 apartment units. With the manager unit, we have a total of 88 units. This would require that we would include nine (9) 4-bedroom units. This requirement would require an adjustment to the building and unit design to reduce the number of 1bedroom, 2 bedroom, and 3-bedroom units to incorporate the 4-bedroom units. This adjustment to include 10% of the total unit count would result in a loss of 15 units (including the manager’s unit) of much-needed affordable residential units
4. Waiver of usable open space per dwelling unit. Our proposed large

family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 under Table 37-30.80 of the Zoning code Development Regulations requires that we provide a minimum of 500 square feet of usable open space per dwelling unit. Our project proposes 88 residential units which equate to a minimum of 44,000 Square Feet of required usable open space. Per Sheet A1.2 Common Open Space of our Site Plan Review Application Plan Set, our project is currently providing 27,305.93 square feet of usable open space.

Please see attached exhibit titled Density Bonus Application

**Other Affordable
Alternative:**

N/A

Project Units:

The table below shows the unit distribution on the project.

UNIT TYPE	NUMBER OF UNITS	BEDROOMS	NUMBER OF BATHROOMS	UNIT SQUARE FOOTAGE	% OF TOTAL UNITS
Extremely Low	3	1	1	641	3.41%
	3	2	1	838	3.41%
	4	3	2	1008	4.55%
Very Low Income	16	1	1	641	18.18%
	13	2	1	838	14.77%
	3	2	2	899	3.41%
	21	3	2	1008	23.68%
Low Income	5	1	1	641	5.68%
	4	2	2	915	4.55%
	11	3	2	1008	12.50%
	4	3	2	983	4.55%
Median Income					
Moderate Income					
Workforce Income					
Non-Restricted Units	1	2	2	899	1.14%
TOTAL					100.00%

Unit Placement:

Units offered to Inclusionary Housing participants shall represent an equitable distribution of unit types and bedroom mix in the overall development.

Follow-up Items:


Items to be completed prior to issuance of the Building Permit:

- Amended Affordable Housing Plan (only if project unit count or composition changes)
- Affordable Housing Agreement (Recorded Covenant)

Items to be completed prior to issuance of the final Certificate of Occupancy (CofO):

- Marketing Plan
- Management Plan
- Unit Income and Rent Limits (per the Density Bonus Program)

Signatures:

DocuSigned by:

C2BE408EC01A49D

Marcus Griffin
Authorized Owner/Project Representative

4/29/2026 | 4:54 PM PDT

Date

Signed by:

4D21317221AE402

Orlando Reyes-Rodas, Assistant Director
Community Development Department

4/29/2026 | 5:44 PM PDT

Date

Attachment A
Density Bonus Unit Placement Table

[Density Bonus units have to be evenly distributed among the different unit types in the project. If project is going to be developed in phases, please describe how this phased approach will impact the distribution and placement of units]

Location	Income	SRO	Studio	1 Bedroom	2 Bedroom	3 Bedroom	4 Bedroom	Total
Phase I	Extremely			3	3	4		10
	Very Low			16	16	21		53
	Low			5	4	15		24
Phase I	Median							
	Moderate							
	Workforce							
Phase III	Median							
	Moderate							
	Workforce							
Phase IV	Median							
	Moderate							
	Workforce							
Phase V	Median							
	Moderate							
	Workforce							
Phase VI	Median							
	Moderate							
	Workforce							
Phase VII	Median							
	Moderate							
	Workforce							

Attachment B
Density Bonus Unit Placement Map

[Insert Site Plan / Floorplan diagram indicating where the Density Bonus units will be located]

Exhibit A – AMI Plan on following pages.



VICINITY MAP

COVER SHEET
AFFORDABLE HOUSING PLAN

MILESTONE HOUSING GROUP
CASENTINI STREET FAMILY APARTMENTS
SALINAS, CA


Site Summary		4.59 AC	(199,960 SF)
Lot Site Area		4.59 AC	
Dwelling Units		95 DU/AC	
Density		19.5 DU/AC	
Apartment Buildings 1-5		121,240 SF	
Daycare Building 7		2,400 SF	
Daycare Building 7		4,335 SF	
F.A.R.		0.64	

Plan Summary		Quantity	% Total Net S.F.	Avg. Net S.F.
Plan 1-1	1	641	27.3%	
Plan 2-1	2	838	18.2%	
Plan 2-2	2	899	4.5%	
Plan 2-3	2	915	4.5%	
Plan 3-1	3	1008	40.9%	
Plan 3-2	3	883	4.5%	
Total		68	100%	76,268
Type		No. Units	Mix	
1Bd		24	27.3%	
2Bd		24	27.3%	
3Bd		40	45.5%	
Total		88	100%	

Parking Summary		Unit Count (DU)	Ratio	No. Spaces Required	No. Single Spaces Provided	No. Tandem Spaces Provided
Bldg. 1-5	Multi-Family	24 DU	1.0*	24	24	0
1 Bedroom		24 DU	1.5*	36	0	48 (24 Open Pairs)
2 Bedroom		40 DU	1.5*	60	0	80 (40 Garage Pairs)
3 Bedroom					24	128
Total				120	152 (1.7 sp/du)	
Bldg. 6	Amenity/Leasing	2,400 SF	N/A	0	0	0
Bldg. 7	Daycare	40 Children	1 Sp. / 8 Children	7	16	0
Grand Total				127	168	

Notes
*State Density Bonus Parking Ratio
**Tandem pairs are assigned to the largest units first. For example, 40 tandem garage pairs go to the 40 three-bedroom units, and are always assigned to specific units, never shared.


Multi-Family Affordable Accessible Parking Calculations		Total
% Required***	1 Bedroom 2 Bedroom 3 Bedroom	6
5% Required	2 2 2	6 (1 Van)
Total Required (1.5 - Van Inclusive of Total)		
% Required***	Remaining Parking Spaces	2
2% Required		
Total Required (Van Inclusive of Total)		2 (1 Van)
Multi-Family Total Provided (Van Inclusive of Total)		8 (2 Van)
Daycare Accessible Parking Calculations		Total
Total Required***		1 (1 Van)
Daycare Total Provided (Van Inclusive of Total)		2 (1 Van)
Notes		
***Required Accessible Parking for Mobility Units per 11B-208.2.3.1 & 11B-208.2.3.2		
***Required Accessible Parking for Daycare per Table 11B-208.2		



Legend

C Compact parking
T Transformer
X Building Type
X Building Number

Direction of Vehicle Travel



Typical Parking Spaces | Scale 1/8"=1'-0"

Bicycle parking provided: 12

CASENTINI STREET FAMILY APARTMENTS
UNIT MATRIX WITH AMI

BEDROOM TYPE	AMI LEVEL	No. of Units
1-BEDROOM	30.00%	3
1-BEDROOM	40.00%	4
1-BEDROOM	50.00%	12
1-BEDROOM	60.00%	5
TOTAL	47.92%	24

BEDROOM TYPE	AMI LEVEL	No. of Units
2-BEDROOM	30.00%	3
2-BEDROOM	40.00%	4
2-BEDROOM	50.00%	12
2-BEDROOM	60.00%	4
TOTAL	47.39%	23

BEDROOM TYPE	AMI LEVEL	No. of Units
3-BEDROOM	30.00%	4
3-BEDROOM	40.00%	6
3-BEDROOM	50.00%	15
3-BEDROOM	60.00%	15
TOTAL	50.25%	40

TOTAL	AMI
10	30%
14	40%
39	50%
24	60%
87	49%


BLDG 1	AMI
LEVEL 1	
PLAN 3-2	30.00%
PLAN 3-2	40.00%
LEVEL 2	
PLAN 2-3	30.00%
PLAN 2-3	40.00%
PLAN 3-2	50.00%
PLAN 3-2	60.00%
LEVEL 3	
PLAN 2-3	50.00%
PLAN 2-3	60.00%

BLDG 2	AMI
LEVEL 1	
PLAN 1-1	30.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-1	50.00%
PLAN 2-1	30.00%
PLAN 2-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%


BLDG 3	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	30.00%
PLAN 1-1	50.00%
PLAN 2-1	50.00%
PLAN 2-1	40.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%

BLDG 4	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-1	50.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-1	40.00%
PLAN 2-1	30.00%
PLAN 2-1	40.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%

BLDG 5	AMI
LEVEL 1	
PLAN 1-1	30.00%
PLAN 1-1	40.00%
PLAN 2-2	MINGR
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	60.00%
PLAN 1-1	50.00%
PLAN 2-1	50.00%
PLAN 2-1	50.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%



BLDG 1	AMI
LEVEL 1	
PLAN 3-2	30.00%
PLAN 3-2	40.00%
LEVEL 2	
PLAN 2-3	30.00%
PLAN 2-3	40.00%
PLAN 3-2	50.00%
PLAN 3-2	60.00%
LEVEL 3	
PLAN 2-3	50.00%
PLAN 2-3	60.00%




Building 'A' - Area	
Level 1	± 5,620 G.S.F.
Level 2	± 5,205 G.S.F.
Level 3	± 2,615 G.S.F.
Total	± 13,440 G.S.F.

BUILDING 1



BLDG 1	AMI
LEVEL 1	
PLAN 1-2	30.00%
PLAN 3-2	40.00%
LEVEL 2	
PLAN 2-3	30.00%
PLAN 2-3	40.00%
PLAN 3-2	50.00%
PLAN 3-2	60.00%
LEVEL 3	
PLAN 2-3	50.00%
PLAN 2-3	60.00%

BUILDING 1




BUDG 2	AMI
LEVEL 2	
PLAN 1-1	30.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-1	50.00%
PLAN 2-1	30.00%
PLAN 2-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%

Building 'B' - Area	
Level 1	± 9,778 G.S.F.
Level 2	± 8,586 G.S.F.
Level 3	± 8,586 G.S.F.
Total	± 26,950 G.S.F.

BUILDING 2


Mech. Equipment -
Screened by Roof



Roof

BLDG 2	AMI
LEVEL 1	
PLAN 1-1	30.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-1	50.00%
PLAN 2-1	30.00%
PLAN 2-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%

Level 3



BUILDING 2


0 4 8 12
1" = 4'-0"

SCHEMATIC DESIGN
FEBRUARY 19, 2025

Floor Plans
BLDG 2


A3.3

140'-1"



BLDG 3	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	30.00%
PLAN 1-1	50.00%
PLAN 2-1	50.00%
PLAN 2-1	40.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%


Building 'B' - Area	
Level 1	± 9,778 G.S.F.
Level 2	± 8,586 G.S.F.
Level 3	± 8,586 G.S.F.
Total	± 26,950 G.S.F.




BUILDING 3

BUILD 3	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-1	40.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	30.00%
PLAN 1-1	50.00%
PLAN 2-1	50.00%
PLAN 2-1	40.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%

Level 3



BUILDING 3



Bldg 4	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-2	50.00%
PLAN 2-1	50.00%
PLAN 2-2	50.00%
PLAN 3-1	50.00%
PLAN 3-2	50.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-2	40.00%
PLAN 2-1	30.00%
PLAN 2-2	40.00%
PLAN 3-1	30.00%
PLAN 3-2	40.00%
PLAN 3-3	60.00%
PLAN 3-4	50.00%
PLAN 3-5	50.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-2	60.00%
PLAN 2-1	50.00%
PLAN 2-2	60.00%
PLAN 3-1	60.00%
PLAN 3-2	60.00%
PLAN 3-3	50.00%
PLAN 3-4	50.00%

Building 'B' - Area	
Level 1	± 9,778 G.S.F.
Level 2	± 8,586 G.S.F.
Level 3	± 8,586 G.S.F.
Total	± 26,950 G.S.F.

BUILDING 4

A3.2

Floor Plans
Bldg. 4

SCHEMATIC DESIGN
FEBRUARY 19, 2025


Scale: 1/8" = 1'-0"

CASANTINI STREET FAMILY APARTMENTS
SALINAS, CA


MILESTONE HOUSING GROUP

888.456.5849 | ktgy.com
No. 20240276

ktgy




Roof




Level 3

BUILDING 4

BLDG 4	AMI
LEVEL 1	
PLAN 1-1	50.00%
PLAN 1-1	50.00%
PLAN 2-2	50.00%
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	50.00%
PLAN 1-1	40.00%
PLAN 2-1	30.00%
PLAN 2-1	40.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
PLAN 3-1	50.00%




BLDG 5	AMII
LEVEL 1	
PLAN 1-1	30.00%
PLAN 1-1	40.00%
PLAN 2-2	MNGR
PLAN 3-1	60.00%
LEVEL 2	
PLAN 1-1	60.00%
PLAN 1-1	50.00%
PLAN 2-1	50.00%
PLAN 2-1	50.00%
PLAN 3-1	30.00%
PLAN 3-1	40.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%
LEVEL 3	
PLAN 1-1	50.00%
PLAN 1-1	60.00%
PLAN 2-1	50.00%
PLAN 2-1	50.00%
PLAN 3-1	60.00%
PLAN 3-1	60.00%
PLAN 3-1	50.00%




Level 3


BUILDING 5




UNIT TYPE P2-1
2 BEDROOM / 1 BATHROOM
±838 NET SF
±950 GROSS SF



UNIT TYPE P1-1
1 BEDROOM / 1 BATHROOM
±641 NET SF
±743 GROSS SF




UNIT TYPE P3-1
3 BEDROOM / 2 BATHROOM
±1,008 NET SF
±1,141 GROSS SF




UNIT TYPE P2-2
2 BEDROOM / 2 BATHROOM
±899 NET SF
±1028 GROSS SF

51'-8 1/2"



UNIT TYPE P2-3
2 BEDROOM / 2 BATHROOM
#915 NET SF
#1015 GROSS SF

56'-8 1/2"



UNIT TYPE P3-2
3 BEDROOM / 2 BATHROOM
#1077 NET SF
#1192 GROSS SF

DENSITY BONUS APPLICATION CONCESSION AND WAIVER REQUEST CASENTINI STREET FAMILY APARTMENTS

Milestone Housing Group in partnership with the Monterey County Housing Authority proposes to develop a currently vacant parcel along Casentini Street as an affordable large family apartment community on a 4.9-acre site comprised of one parcel (APN: 003-161-030) with an address of 200 Casentini Street, Salinas, CA. The Monterey County Housing Authority is the current owner of the project property.

The project sponsor proposes to regrade the vacant property and construct a new 100% affordable multi-family residential apartment community and a new day care center. The residential community portion of the project will consist of five (5) new, 3-story apartment buildings and will include eighty-eight (88) apartment units with a mix of 1-bedroom, 2-bedroom, and 3-bedroom apartments. The residential community will also include a leasing/amenity building, a tot lot, and sport court, a dog park area, walking paths, and a mix of covered and surface parking spaces totaling 152 parking spaces.

There is a total of eighty-eight (88) residential apartment units, which includes 87 low income or subsidized housing units and one (1) Manager's Unit. The unit mix is broken down in the Table below and reflects twenty-four (24) one-bedroom units (27.3%), twenty-four (24) two-bedroom units (27.3%), and forty (40) three-bedroom units (45.4%). This unit mix allows for this project to be considered as a large family project. The project also includes a leasing/amenity building with indoor fitness, business/computer room, and a community room. Exterior amenities include a sport court with a basketball hoop for all residents of the project and a tot lot for children up to nine (9) years of age.

The Day Care Center, measuring roughly 4,335 square feet, will provide services to children from newborn age up to 5 years of age. The building will be divided into two classrooms with one room for children 0-24 months and the second classroom for children 24 months to 60 months. Each classroom will have their own secure outdoor play area. The building will include bathrooms, offices for staff, a breakroom, and a kitchen for meal preparation. The Daycare Center will have their own access into the property off Casentini Street and will include 16 parking spaces.

The project will be 100% affordable for households with income at or below 60% of Area Median Income (AMI). The Average AMI level for the project is roughly 49%. The breakdown of AMI levels, unit mix, and number of subsidized units are found in the Table below:

**CASENTINI STREET FAMILY APARTMENTS
UNIT MIX AMI BREAK DOWN**

BEDROOM TYPE	AMI LEVEL	NUMBER OF UNITS
1-BEDROOM	30.00%	3
1-BEDROOM	40.00%	4
1-BEDROOM	50.00%	12
1-BEDROOM	60.00%	5
2-BEDROOM	30.00%	3
2-BEDROOM	40.00%	4
2-BEDROOM	50.00%	12
2-BEDROOM	60.00%	4
3-BEDROOM	30.00%	4
3-BEDROOM	40.00%	6
3-BEDROOM	50.00%	15
3-BEDROOM	60.00%	15
TOTAL UNIT COUNT (SUBSIDIZED)		87
TOTAL UNIT COUNT AT 30% AMI		10
TOTAL UNIT COUNT AT 40% AMI		14
TOTAL UNIT COUNT AT 50% AMI		39
TOTAL UNIT COUNT AT 60% AMI		24
AVERAGE AMI LEVEL		49%

The project seeks on-going rental subsidies in the form of Project-Based Section 8 Vouchers from the Housing Authority of the County of Monterey in addition to tax exempt bond financing and low-income housing tax credits.

To develop the Casentini Street Family Apartments and provide necessary affordable housing to the community, the project requires incentives/concessions and/or waivers as allowed through the State Density Bonus Law. Currently, per our analysis of the City of Salinas Zoning Code, waivers required to allow for the development of the project include removing the restriction on tandem parking spaces, a waiver for not providing 4-bedroom units in our project design, and a waiver requesting a reduction in required open space. Below is a written explanation of the why this 100% affordable large family apartment community could not be developed without these requested waivers.

Waiver Request #1: Article V. Division 2. Parking, Loading, and Outdoor Lighting; Section 37-50.360. Off Street Parking and Loading Spaces Regulations Table 37-50.100:

The project applicant is requesting a waiver of Article V; Division 2; Section 37-50.360; Table 37-50.100 regarding required number of parking spaces per unit type. The project proposes a total of 88 units with 24 One-Bedroom Units, 24 Two-Bedroom Units, and 40 Three Bedroom Units. Per Table 37-50.100 of the City of Salinas Zoning Code Section 37-50.360, based on our unit mix, our required number of parking spaces is 164 spaces. Per the table below, also found in our Project Matrix on Sheet A1.0 of our Site Plan Review Application plan set, we are providing a total of 152 parking spaces. This reflects an eleven (11) stall deficit in the total required number of parking spaces.

Per the State Government Code under Title 7; Division 1; Chapter 4.3 Density Bonus and Other Incentives under Section 65915(p)(1) Law, we are allowed to use a parking ratio of 1 parking stall per every 1-Bedroom Unit, and 1.5 parking stalls per every 2 and 3-Bedroom unit without a requirement to apply for an additional waiver. As reflected in the table below, using the State Density Bonus Law related to parking ratios per bedroom type, our required parking would total 121 stalls. We are providing 152 parking spaces, which exceeds the parking requirements using State Density Bonus Law.

In the light of the above, we respectfully request that the State Density Bonus Law parking ratios be applied as part of our application. In addition, as part of our Waiver Request, if we are required to add eleven (11) parking stalls to meet the City parking requirements, we would be required to remove an entire building section, which would equate to losing four (4) stacks of units or a total of twelve (12) much-needed affordable housing units.

Bedroom Type	Number of Units	Parking Required per Unit Type	Parking Required Total	Parking Required Per State Density Bonus Law	Total Parking Required Per State Density Bonus Law	Parking Provided Per Unit Type	Total Parking Provided
1-BEDROOM	3	1.5	4.5	1	3	1	3
1-BEDROOM	4	1.5	6	1	4	1	4
1-BEDROOM	12	1.5	18	1	12	1	12
1-BEDROOM	5	1.5	7.5	1	5	1	5
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
2-BEDROOM	9	2	18	1.5	13.5	2	18
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	6	2	12	1.5	9	2	12
3-BEDROOM	15	2	30	1.5	22.5	2	30
3-BEDROOM	11	2	22	1.5	16.5	2	22
3-BEDROOM	4	2	8	1.5	6	2	8
MANAGER UNIT - 2-BEDROOM	1	2	2	2	2	2	2
TOTAL	88	1.86	164	1.37	121	1.73	152

Waiver Request #2: Section 20-18.020 – Prohibition of Oversized Vehicle Parking (Tandem Parking Stalls):

The Project Applicant is requesting a waiver of Article XVIII – Regulating the Parking of Over-Size Vehicles under Section 20-18.020 prohibiting the ability to park vehicles exceeding 20 feet in length. Per Sheet A1.0: Site Plan, of our Site Plan Review Application plan set, our project data section reflects a total of 152 proposed parking stalls for our residential community. The table below reflects the total number of parking stalls, the breakdown of parking stalls provided per unit type, and the breakdown of tandem parking stalls as part of the 152 total parking spaces provided. As such, of the 152 total parking spaces provided, there is a total of sixty-four (64) tandem parking spaces. This is separated as 40 tandem stalls in our parking garages within the residential buildings and another 24 tandem stalls in our surface parking areas.

In review of our project plan and building layout, losing 64 parking spaces would have a significant impact on the number of affordable units provided in the project. Based on calculating the current number of parking spaces provided and removing the 64 tandem spaces, it leaves the project with a total of 91 parking spaces. Based on the parking ratio of what is provided at 1.73 stalls per unit, we would lose roughly 35 much-needed affordable residential units.

CASENTINI STREET FAMILY APARTMENTS PARKING BREAKDOWN		
PARKING TYPE	TANDEM SPACES	TOTAL SPACES
TANDEM GARAGE	40	80
TANDEM OPEN STALL	24	48
SINGLE GARAGE	0	9
OPEN SPACE - SINGLE	0	15
TOTAL UNIT COUNT (SUBSIDIZED)	64	152

Bedroom Type	Number of Units	Parking Required per Unit Type	Parking Required Total	Parking Required Per State Density Bonus Law	Total Parking Required Per State Density Bonus Law	Parking Provided Per Unit Type	Total Parking Provided
1-BEDROOM	3	1.5	4.5	1	3	1	3
1-BEDROOM	4	1.5	6	1	4	1	4
1-BEDROOM	12	1.5	18	1	12	1	12
1-BEDROOM	5	1.5	7.5	1	5	1	5
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
2-BEDROOM	9	2	18	1.5	13.5	2	18
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	6	2	12	1.5	9	2	12
3-BEDROOM	15	2	30	1.5	22.5	2	30
3-BEDROOM	11	2	22	1.5	16.5	2	22
3-BEDROOM	4	2	8	1.5	6	2	8
MANAGER UNIT - 2 BEDROOM	1	2	2	2	2	2	2
TOTAL	88	1.86	164	1.37	121	1.73	152

Waiver Request #3: Section 37-30.170; Table 37-30.80 – Bedrooms per Dwelling Unit (Percent of total dwelling units):

Our proposed large family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 of the Zoning code under Table 37-30.80 requires that 10% of all dwelling units in our project include 4 or more bedrooms. As reflected above in our unit and AMI breakdown, our project includes a total of 87 apartment units. With the manager unit, we have a total of 88 units. This would require that we would include nine (9) 4-bedroom units. This requirement would require an adjustment to the building and unit design to reduce the number of 1 bedroom, 2 bedroom, and 3-bedroom units to incorporate the 4-bedroom units. This adjustment to include 10% of the total unit count would result in a loss of 15 units (including the manager's unit) of much-needed affordable residential units

Waiver Request #4: Section 37-30.170; Table 37-30.80 – Usable Open Space Area per Dwelling Unit - Minimum:

Our proposed large family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 under Table 37-30.80 of the Zoning code Development Regulations requires that we provide a minimum of 500 square feet of usable open space per dwelling unit. Our project proposes 88 residential units which equate to a minimum of 44,000 Square Feet of required usable open space. Per Sheet A1.2 Common Open Space of our Site Plan Review Application Plan Set, our project is currently providing 27,305.93 square feet of usable open space.

Our Open Space exhibit reflects six (6) Open Space areas where our calculation derives from. Although there is a substantial amount of excess land on our 4.9-acre parcel, a large area of the site has slopes greater than a 10% slope and cannot be considered for usable open space. The Usable Open Space being provided, 27,306, equates to roughly 310 square feet per unit or a deficiency of roughly 190 square feet per unit. In order for our project to increase our usable open space, we need to reduce our residential building area by 16,694 square feet. Our current residential building area is roughly 121,240 square feet or roughly 1,378 square feet per unit (gross). Reducing the building area by roughly 17,000 square feet, our unit count would reduce from 88 units down to 75 units. Without our requested waiver for this development regulation, the project would lose roughly 13 much-need affordable residential units.

If City Staff would like additional information related to this Waiver Request and analysis stated above, please contact Aaron Barger at abarger@milestonehousing.com or at 408-640-1100 to discuss further.



Harris & Associates

November 24, 2025

Aaron Barger
Milestone Housing Group
51 University Avenue, Suite D
Los Gatos, California 95030

Subject: Aquatic Resources Constraints Letter Report for the Casentini Street Family Apartments Project

Dear Mr. Barger,

On October 29, 2025, Harris & Associates (Harris) conducted a biological and aquatic resources field reconnaissance survey of the Casentini Street Family Apartments Project (project) site and a 100-foot buffer (approximately 10.21 acres in total), together referred to as the survey area. The purpose of this letter report is to provide the results of an aquatic resources delineation for the City of Salinas (City) to evaluate the appropriate setbacks areas from any potential off-site aquatic resources. This letter report includes an assessment of the need for 100-foot setbacks from any existing aquatic resources, or lack thereof, pursuant to Salinas City Code, Chapter 37, Article V, Division 1, Section 37-50.180(h), Ecological and Biological Resources (City of Salinas 2025). Under the Salinas City Code, activities may be considered within the setback area if the City determines the encroachment to be minor.

Project Location and Description

The project site is in the City of Salinas in Monterey County (County), California, within Assessor's Parcel Number 003-161-030-000 (Attachment 1, Figures; Figure 1, Regional Location, and Figure 2, Project Location). The project site is a vacant lot bordered by Casentini Street to the south and high-density residential development to the west, north, and east. The survey area is within the City's existing boundary and is surrounded by development, as depicted on Figure LU-1 of the City's General Plan Land Use Element, and is in a Residential High Density (R-H-2.1) Zoning District (City of Salinas 2002).

The project involves constructing a 100 percent affordable large-family and multi-family housing community with approximately 88 dwelling units and a child daycare center on a 4.9-acre undeveloped parcel. The project will consist of two housing buildings, a daycare building, an amenity building, landscaping, two entrances/exits onto Casentini Street, and parking.

Environmental Setting

Land Use

The project site is on a gently sloping, flat parcel of undeveloped land that is currently maintained by mowing and disking. Historically, the site has remained undeveloped for residential purposes. A review of historical aerial imagery indicates that the site has been consistently mowed and disked, has remained undeveloped, and has not supported any permanent structures or residential development thus far (Google Earth 2025). It is surrounded by residential development immediately to the west, northwest, and south/southwest, with a tennis court and urban landscapes to the north. Natividad Creek borders the survey area to the east, with residential development surrounding the survey area farther out on all sides.

Topography and Soils

The survey area is generally flat, with a slight decrease in elevation moving south, where it borders Casentini Street. In the southeastern corner, where the survey area borders a concrete canal, the elevation drops sharply.

Exhibit H



Elevations within the survey area range from approximately 35 to 64 feet above mean sea level (Figure 3, USGS Topographic Map). The U.S. Department of Agriculture Natural Resources Conservation Service soil series search results for the project site included four soils (USDA 2019) (Figure 4, Soils). A description of each soil series is provided below:

- **Antioch Very Fine Sandy Loam.** Antioch series soils consist of fine-textured, moderately well-drained soils that formed on alluvial fans and floodplains in California at elevations ranging from near sea level to 1,100 feet above mean sea level. They are typically light brownish-gray and brown and found on slopes. This soil is found in the southwestern portion of the survey area.
- **Clear Lake Clay, Sandy Substratum, Drained.** Clear Lake series soils consist of very deep, poorly drained soils that formed in fine-textured alluvium derived from mixed rock sources on slopes ranging from zero to 5 percent. This soil occurs in the eastern portion of the survey area.
- **Cropley Silty Clay.** Cropley series soils consist of very deep, moderately well- and well-drained soils that formed in alluvium from mixed rock sources on slopes ranging from zero to 15 percent. This soil occurs on the western portion of the survey area.
- **Diablo Clay.** Diablo series soils consist of fine, smectitic, Aridic Haploxererts, usually found on slopes higher than 9 percent. This series is throughout Central California on steep slopes at elevations ranging from near sea level to 3,000 feet above mean sea level (USDA 2019). This soil occurs in the central portion of the survey area.

Hydrology

The survey area is in the greater Monterey Bay Watershed (Hydrologic unit 18060015) and the Alisal Slough-Tembladero Slough Subwatershed (Hydrologic Unit 180600150103). The Monterey Bay Watershed is located primarily in Monterey and Santa Cruz Counties and encompasses drainages that flow directly into the Monterey Bay and the Pacific Ocean. The Alisal Slough-Tembladero Slough Subwatershed drains approximately 144 square kilometers of area west to the Pacific Ocean via the Tembladero Slough (USEPA 2025).

The National Wetlands Inventory (NWI) Wetlands Mapper and National Hydrography Dataset results identified one aquatic feature that is within the survey area, outside the project footprint, but within the survey area (Figure 5, Hydrology). Natividad Creek is identified as an intermittent, excavated, seasonally flooded riverine feature by the NWI (USFWS 2025). Natividad Creek flows from north to south through the 100-foot survey buffer east of the project footprint. This section of the creek is highly modified, having been channelized into an open, cement-lined ditch for stormwater and flood control.

During the October 2025 site visit, three aquatic features were observed in and near the survey area: Natividad Creek and two short, unnamed unvegetated channels that flow directly into Natividad Creek. None of the three aquatic features occur within the project site boundary. Two off-site cement-lined v-ditches occur east of the project site and drain rainwater from uplands west to Natividad Creek. Natividad Creek runs just east of the project site boundary, flowing south through a concrete channel before joining an earthen canal that flows west by way of numerous irrigation and flood control ditches and eventually empties into the Pacific Ocean, which is defined as traditional navigable water (TNW) by the U.S. Army Corps of Engineers (USACE).

Further discussion on potentially jurisdictional aquatic resources is provided in the Aquatic Resources Delineation section in the Results section.

Climate

The survey area is in Monterey County. On a regional level, the County has a Mediterranean climate, which is characterized by wet winters and dry summers. This is largely because of a Semi-Permanent High-Pressure Zone that sits over the Pacific Ocean during much of the year and forms a fog belt (marine layer). The project site is generally within the Peninsular Ranges of Central California. The generalized climate in the region is dry, subhumid mesothermal, which pushes the growing season to the wet months of the year (late winter to early spring). The rainy season in the County typically lasts from November through March. Vegetation often goes dormant during the late summer months until the first rain in the fall.



According to historical data from the weather station at the Salinas Municipal Airport, approximately 2.6 miles southeast of the survey area, the average maximum annual temperature for the area surrounding the survey area is 68.4 degrees Fahrenheit (°F), and the average minimum temperature is 47.3°F. Average annual precipitation in the area is 14.54 inches (WRCC 2025).

Methods

This biological and aquatic resources analysis includes the results of a database review and biological resources survey, which document the existing biological conditions of the survey area. The results of the database review provide information on permitting requirements and potential constraints to project construction due to the presence (or lack thereof) of sensitive biological and aquatic resources.

Database Review

Prior to conducting fieldwork, a Harris biologist referenced the following materials:

- Topographic maps
- Aerial imagery (Google Earth from 1994 to 2025)
- U.S. Fish and Wildlife Service NWI Online Wetland Mapper (USFWS 2025)
- U.S. Department of Agriculture Natural Resources Conservation Service (NRCS) Web Soil Survey (USDA 2019)

Aquatic Resources Delineation

A Harris biologist conducted an aquatic resources delineation on October 29, 2025, using the routine on-site determination method described in the USACE Wetlands Delineation Manual (USACE 1987), the Regional Supplement to the Corps of Engineers Wetlands Delineation Manual: Arid West Region (USACE 2008), and the National Ordinary High Water Mark Field Delineation Manual for Rivers and Streams: Final Version (USACE 2025a). Plant species names and wetland indicator statuses follow the most recent iteration of the National Wetland Plant List (Attachment 2, Observed Plant Species List; USACE 2025b). The Harris biologist conducted the aquatic resources delineation fieldwork to identify aquatic resources within the survey area, including ordinary high water mark indicators and data applicable to a concrete-lined ditch, as well as prepared a USACE three-parameter wetland determination datasheet for the Arid West Region (wetland determination datasheet) at a representative point in the southeastern portion of the survey area, which sits at a lower grade than the surrounding land (Attachment 3, Datasheets).

Survey Limitations

Plants were identified by direct observation. However, the site visit was conducted at the end of the growing season, when some plant species were not evident or identifiable. Further, the site is regularly maintained through mowing, further reducing the potential for identification. Therefore, the list of observed plant species is not necessarily comprehensive.

Results

Vegetation Communities and Land Cover Types

Four vegetation communities and land cover types were observed in the survey area: unvegetated channel, coast live oak woodland, disturbed (ruderal) habitat, and urban/developed land (Figure 6, Vegetation Communities and Land Cover Types; Table 1, Vegetation Communities and Land Cover Types in the Survey Area) (Holland 1986). One vegetation community associated with aquatic resources in the survey area—unvegetated channel—is described in the following section.



Table 1. Vegetation Communities and Land Cover Types in the Survey Area

Vegetation Community and Land Cover Type	Project Site (acres) ¹	Survey Buffer (acres) ¹	Survey Area (acres) ¹
Aquatic			
Unvegetated Channel	0	0.14	0.14
<i>Subtotal</i>	<i>0</i>	<i>0.14</i>	<i>0.14</i>
Upland			
Coast Live Oak Woodland	0.05	0.42	0.47
<i>Subtotal</i>	<i>0.05</i>	<i>0.42</i>	<i>0.47</i>
Disturbed (Ruderal) Habitat/Developed Lands			
Disturbed (Ruderal) Habitat	4.32	0	4.32
Urban/Developed Land	0	5.28	3.60
<i>Subtotal</i>	<i>4.32</i>	<i>5.28</i>	<i>7.92</i>
Total	4.37	5.84	10.21

Notes:

¹ Acreages are approximate and based on ArcGIS Collector data. Values are rounded up to one-hundredth of an acre.

Aquatic Vegetation Communities***Unvegetated Channel***

Approximately 0.14 acre of unvegetated channel occurs in the 100-foot survey buffer, all within the eastern portion of the survey area (Figure 6). Three concrete-lined channels occur in the survey buffer, outside the project site boundary: Natividad Creek and two v-ditches. These features are discussed further in the following Aquatic Resources Delineation section.

Upland Vegetation Communities***Coast Live Oak Woodland***

Remnant coast live oak (*Quercus agrifolia*) woodland occurs along the northern edge of the survey area, along with isolated coast live oak trees within the survey area. Approximately 0.05 acre of coast live oak woodland occurs on the project site, with an additional 0.42 acre within the 100-foot survey buffer. The overstory of this vegetation community is dominated by coast live oak. The understory consists primarily of non-native grassland similar to the disturbed/ruderal grassland elsewhere in the survey area, as described below.

Disturbed (Ruderal) Habitat/Developed Lands***Disturbed (Ruderal) Habitat***

Disturbed or ruderal vegetation communities are generally dominated by non-native vegetation of various densities. In the survey area, disturbed habitat consists of approximately 4.32 acres of ruderal grassland maintained by mechanical means (regular mowing). Dominant species in the ruderal grassland include wild oat (*Avena fatua*), Harding grass (*Phalaris aquatica*), and field bindweed (*Convolvulus arvensis*). An isolated arroyo willow (*Salix lasiolepis*) occurs in the eastern portion of this vegetation community.

Urban/Developed Land

Urban/developed land cover type encompasses anthropogenic development, including buildings, roadways, structures, and associated hardscaping and manicured landscaping. Within the survey area, urban/developed land includes buildings, paved roadways, parking lots, tennis courts, and manicured lawns. No urban/developed land occurs on the project site, but approximately 5.28 acres occur within the 100-foot survey buffer. Vegetation in this land cover type is typically absent or manicured and artificially irrigated plantings.



Aquatic Resources Delineation

During the October 2025 site visit, data was collected from one representative data point and three drainage ditches within the survey area. The representative data point was collected from a low area in the southeastern corner of the survey area, where the vegetation community changes slightly from the surrounding ruderal grassland. Curly dock (*Rumex crispus*) is co-dominant in this area, indicating more moisture is likely present in the soil. Investigation of plants, soils, and hydrology indicated that this area does not pond water for sufficient lengths of time to sustain hydrophytic vegetation, hydric soils, or wetland hydrology (refer to Attachment 3 and Attachment 4, Photographic Log). Thus, no wetlands were observed on site.

Three aquatic resources were identified in the survey area, east of the project site: Natividad Creek and two unnamed unvegetated channels that drain rainwater runoff into the cement-lined channel of Natividad Creek (Figure 7, Aquatic Resources, and Figure 8, Potential Jurisdictional Waters of the U.S. and State). None of the three aquatic resources occur within the project site boundary.

Natividad Creek

Natividad Creek is approximately 9 feet wide at the ordinary high water mark and 14 feet wide at the top of bank, which is just above the cement-lined portion of the drainage. Approximately 8 inches of slow-flowing water was within the concrete channel at the time of the October 2025 survey. The channel contained sporadic cattail (*Typha* spp.); however, piles of mud and dried cattails found adjacent to the creek indicate that the channel is regularly dredged for stormwater control to prevent sediment buildup and vegetation from establishing for long periods of time. Natividad Creek is identified as an intermittent, excavated, seasonally flooded riverine feature by the NWI and has a documented downstream connection to the Pacific Ocean, a traditional navigable water as defined by the USACE, via a series of constructed irrigation canals (USACE 2025a). Therefore, Natividad Creek is likely under the jurisdiction of the USACE pursuant to the Clean Water Act, Section 404. This creek is also likely a water of the state and would be considered jurisdictional pursuant to the Porter-Cologne Water Quality Control Act and California Fish and Game Code, Section 1602.

Unvegetated Ditch

Two unvegetated, cement-lined v-ditches in the eastern portion of the survey area are approximately 85 feet long and drain west into Natividad Creek. These ditches direct water from urban landscaping east of the survey area into Natividad Creek. The ditches are not identified in the NWI, and no water was flowing in either ditch during the October 2025 site visit, indicating that these channels likely do not contain water outside the rainy season. Due to the developed and ephemeral nature of these ditches and because they were excavated in uplands and only channel rainwater runoff from uplands, the unvegetated ditches are not likely under the jurisdiction of the USACE pursuant to the Clean Water Act, Section 404. They may be jurisdictional as waters of the state pursuant to the Porter-Cologne Water Quality Control Act and the California Fish and Game Code, Section 1602.

Plant Species

Attachment 2 lists the vascular plant species observed in the survey area during the site visit. A total of 15 plant species were identified in the survey area, six (40 percent) of which were native and nine (60 percent) of which were non-native. No sensitive plant species were identified in the survey area during the October 2025 site visit.

Project Impacts

No impacts to aquatic resources are anticipated because no aquatic resources are on site. The cement-lined channel of Natividad Creek is not within the project footprint, and no direct or indirect impacts are anticipated because of project development.

Constraints Analysis Conclusion

The survey area, including the project site and survey buffer, is either already developed or regularly maintained through mechanical means. The drainage east of the project site is an excavated, cement-lined canal that provides



neither high-quality aquatic habitat for wildlife nor riparian habitat for local wildlife shelter or movement. The two cement-lined v-ditches were excavated in uplands and drain uplands.

Based on the conditions of Natividad Creek adjacent to the project footprint, a 100-foot setback is not necessary. The channel is cement-lined and does not have any associated riparian habitat, thereby reducing the functions and values of the channel as a natural waterway or wildlife migration corridor. Implementation of appropriate best management practices during project development will be sufficient to prevent sedimentation or water runoff into Natividad Creek during construction. No direct or indirect impacts to aquatic resources are anticipated as a result of project development, and no further analysis or aquatic resources permitting is recommended.

Preparers

Harris & Associates

Will Lawton, Biologist, Author

Laura Burris, Principal Biologist, Senior Review

If you have any questions regarding this letter report, please contact me at (916) 835-9671 or Laura.Burris@WeAreHarris.com.

Sincerely,

Laura Burris

Principal Biologist

Attachments

- 1, Figures
- 2, Observed Plant Species List
- 3, Datasheets
- 4, Photographic Log

References

- City of Salinas. 2002. City of Salinas General Plan. September. Accessed November 2025. <https://www.salinas.gov/files/sharedassets/city/v/1/residents/documents/generalplan.pdf>.
- City of Salinas. 2025. "Section 37-50.180(h): Ecological and Biological Resources." In Salinas City Code. Accessed November 2025. https://library.municode.com/ca/salinas/codes/code_of_ordinances?nodeId=PTIITHCO_CH37ZO_ARTVSUREAPALDI_DIV1SPREAPALDI_S37-50.180PEST#:~:text=Ecological%20and%20Biological%20Resources.
- Google Earth. 2025. "Google Earth." Accessed November 2025. <https://www.google.com/earth/>.
- Holland, Robert F. 1986. Preliminary Descriptions of the Terrestrial Natural Communities of California. California Department of Fish and Game. October. Accessed November 2025. https://www.sandiegocounty.gov/content/dam/sdc/pds/ceqa/JVR/AdminRecord/IncorporatedByReference/Appendices/Appendix-J---Groundwater-Investigation-Report/Holland_1986.pdf.pdf.
- USACE (U.S. Army Corps of Engineers). 1987. Corps of Engineers Wetlands Delineation Manual. Final report. Wetlands Research Program Technical Report Y 87 1 (online edition). Prepared by Environmental Laboratory, U.S. Army Corps of Engineers, Waterways Experiment Station. Wetlands Research Program. January. Accessed November 2025. <http://www.cpe.rutgers.edu/Wetlands/1987-Army-Corps-Wetlands-Delineation-Manual.pdf>.

- USACE. 2008. Regional Supplement to the Corps of Engineers Wetlands Delineation Manual: Arid West Region (Version 2.0). Final report. ERDC/EL TR-08-28. Prepared by Environmental Laboratory, U.S. Army Engineer Research and Development Center. Wetlands Regulatory Assistance Program. September. Accessed November 2025. <https://usace.contentdm.oclc.org/utis/getfile/collection/p266001coll1/id/7627>.
- USACE. 2025a. National Ordinary High Water Mark Field Delineation Manual for Rivers and Streams. Final Version. ERDC/CRREL TR-25-1. Prepared by Gabrielle C. L. David, Ken M. Fritz, Tracie-Lynn Nadeau, Brian J. Topping, Aaron O. Allen, Patrick H. Trier, Steven L. Kichefski, L. Allan James, Ellen Wohl, and Daniel Hamill. U.S. Army Engineer Research and Development Center, Cold Regions Research and Engineering Laboratory. January. Accessed November 2025. <https://erdc-library.erdcdren.mil/items/76c61f8f-6d75-4a35-aaf3-39aa64918afb>.
- USACE. 2025b. National Wetland Plant List. Accessed November 2025. <https://nwpl.sec.usace.army.mil/>.
- USDA (U.S. Department of Agriculture). 2019. Web Soil Survey. Natural Resources Conservation Service, Soil Survey Staff. Last modified July 31. Accessed November 2025. <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>.
- USEPA (U.S. Environmental Protection Agency). 2025. WATERS GeoViewer. Last updated August 7. Accessed November 2025. <https://www.epa.gov/waterdata/waters-geoviewer>.
- USFWS (U.S. Fish and Wildlife Service). 2025. National Wetlands Inventory Wetlands Mapper. Accessed November 2025. <https://www.fws.gov/program/national-wetlands-inventory/wetlands-mapper>.
- WRCC (Western Regional Climate Center). 2025. "Salinas, California (047668)." Accessed November 2025. <https://wrcc.dri.edu/cgi-bin/cliMAIN.pl?ca7668>.

This page intentionally left blank.

Attachment 1. Figures

This page intentionally left blank.



Source: ESRI, 2023.



Harris & Associates




0 5 10
Miles

Figure 1

Regional Location

Casentini Street Family Apartments Project



Source: ESRI, 2023.

Figure 2

Project Location


Casentini Street Family Apartments Project



Harris & Associates



0 100 200
Feet



Source: USGS & 5 Minute Salinas Quadrangle, 1984.

Figure 3

USGS Topographic Map


Casentini Street Family Apartments Project



Harris & Associates



0 500 1,000
Feet




Harris & Associates



0 100 200
Feet

Figure 4
Soils


Casentini Street Family Apartments Project



Source: USGS National Hydrography Dataset, 2025; USFWS, 2025; Maxar Imagery, 2023.

Figure 5
Hydrology

Casentini Street Family Apartments Project



Source: ESRI, 2023.

Figure 6

Vegetation Communities and Land Cover Types
Casentini Street Family Apartments Project



Harris & Associates




0 75 150
Feet



- Project Site
- 100-Foot Survey Buffer
- Aquatic Resources**
- Unvegetated Channel

Source: ESRI, 2023.



Harris & Associates

Figure 8

Potential Jurisdictional Waters
of the U.S. and State for the
Casentini Street Family Apartments Project

Legend

 Project Site

 100-Foot Survey Buffer

○ Reference Points

● Aquatic Resource Point

Aquatic Resources

Natividad Creek (0.12 acres)

Cement-Lined Ditch (0.3 acres)



0 100 200
Feet

Coordinate System: NAD 1983 California State Plane Zone 6
Projection: Lambert Conformal Conic
Datum: North American 1983
Vertical Datum: No Coordinate System
1 inch = 200 Feet

Created on November 3rd, 2025
Revised on November 18th, 2025

Made in accordance with the Updated Map and Drawing Standards
for the South Pacific Division Regulatory Program, as amended on
February 10, 2016, by Jason Delors, Project Manager Enforcement and
Special Projects Unit U.S. Army Corps of Engineers South Pacific Division
Sacramento District, Regulatory Division
1325 J Street, Room 1350
Sacramento, California 95814-2922

Attachment 2. Observed Plant Species List

This page intentionally left blank.

Scientific Name	Common Name	Special Status
EUDICOTS		
Asteraceae - Sunflower family		
* <i>Helminthotheca echioides</i>	Bristly ox-tongue	
* <i>Lactuca serriola</i>	Prickly lettuce	
* <i>Sonchus sp.</i>	Sowthistle	
Brassicaceae - Mustard family		
* <i>Hirschfeldia incana</i>	Shortpod mustard	
Convolvulaceae - Morning-glory f		
* <i>Convolvulus arvensis</i>	Bindweed, orchard morning-glory	
Fabaceae - Legume family		
<i>Acmispon junceus</i>	Rush lotus	
Fagaceae - Oak family		
<i>Quercus agrifolia</i>	Coast live oak	
Juglandaceae - Walnut family		
<i>Juglans hindsii</i>	Northern California black walnut	
Malvaceae - Mallow family		
<i>Malvella leprosa</i>	Alkali mallow	
Polygonaceae - Buckwheat famil		
* <i>Rumex crispus</i>	Curly dock	
Salicaceae - Willow family		
<i>Salix lasiolepis</i>	Arroyo willow	
MONOCOTS		
Poaceae - Grass family		
* <i>Avena fatua</i>	Wild oat	
<i>Bromus carinatus</i>	California brome	
* <i>Phalaris aquatica</i>	Harding grass	
Typhaceae - Cattail family		
* <i>Typha angustifolia</i>	Narrow-leaved cattail	

Scientific Name	Common Name	Special Status
Legend		
*= Non-native or invasive species		
Special Status:		
Federal:		
FE = Endangered		
FT = Threatened		
State:		
SE = Endangered		
ST =Threatened		
CRPR – California Rare Plant Rank		
1A. Presumed extinct in California and elsewhere		
1B. Rare or Endangered in California and elsewhere		
2A. Presumed extinct in California, more common elsewhere		
2B. Rare or Endangered in California, more common elsewhere		
3. Plants for which we need more information - Review list		
4. Plants of limited distribution - Watch list		
Threat Ranks		
.1 - Seriously endangered in California		
.2 – Fairly endangered in California		
.3 – Not very endangered in California		

Attachment 3. Datasheets

This page intentionally left blank.

WETLAND DETERMINATION DATA FORM – Arid West Region

Project/Site: Casentini Street Apartments City/County: Salinas, Monterey Co. Sampling Date: 10/29/2025
 Applicant/Owner: City of Salinas State: CA Sampling Point: AF-1
 Investigator(s): Will Lawton Section, Township, Range: Township 14 South, Range 3 East
 Landform (hillslope, terrace, etc.): Hillslope Local relief (concave, convex, none): Concave Slope (%): 1
 Subregion (LRR): LLR C, Central California Coastal Valley Lat: 36.686412 Long: -121.6571143 Datum: NAD 83
 Soil Map Unit Name: Clear Lake Clay, Sandy Substratum, Drained NWI classification: None

Are climatic / hydrologic conditions on the site typical for this time of year? Yes ☒ No ☐ (If no, explain in Remarks.)
 Are Vegetation ☐, Soil ☐, or Hydrology ☐ significantly disturbed? Are "Normal Circumstances" present? Yes ☒ No ☐
 Are Vegetation ☐, Soil ☐, or Hydrology ☐ naturally problematic? (If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

Hydrophytic Vegetation Present? Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒
Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present? Yes ☐ No ☒	
Remarks: Project site is at the base of a hill that is frequently mowed, but the site itself appears to be maintained less frequently, as vegetation reached at least 3 feet high throughout. The sample point was taken at the low point below the steep hill that comprises the majority of the site, but the sample point is still located on a slight slope that leads to a concrete channel with slowly flowing approximately 20 feet away.	

VEGETATION – Use scientific names of plants.

Tree Stratum (Plot size: <u>30</u>)	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test worksheet: Number of Dominant Species That Are OBL, FACW, or FAC: <u>1</u> (A) Total Number of Dominant Species Across All Strata: <u>2</u> (B) Percent of Dominant Species That Are OBL, FACW, or FAC: <u>50</u> (A/B)
1. <u>None</u>				
2. _____				
3. _____				
4. _____				
_____ = Total Cover				
Sapling/Shrub Stratum (Plot size: <u>15</u>)				Prevalence Index worksheet: Total % Cover of: _____ Multiply by: _____ OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species <u>62</u> x 3 = <u>186</u> FACU species <u>44</u> x 4 = <u>176</u> UPL species <u>4</u> x 5 = <u>20</u> Column Totals: <u>110</u> (A) <u>382</u> (B) Prevalence Index = B/A = <u>3.47</u>
1. <u>None</u>				
2. _____				
3. _____				
4. _____				
5. _____				
_____ = Total Cover				
Herb Stratum (Plot size: <u>5</u>)				Hydrophytic Vegetation Indicators: ___ Dominance Test is >50% ___ Prevalence Index is ≤3.0 ¹ ___ Morphological Adaptations ¹ (Provide supporting data in Remarks or on a separate sheet) ___ Problematic Hydrophytic Vegetation ¹ (Explain)
1. <u>Rumex crispus</u>	<u>40</u>	<u>Yes</u>	<u>FAC</u>	
2. <u>Convolvulus arvensis</u>	<u>25</u>	<u>Yes</u>	<u>FACU</u>	
3. <u>Helminthotheca echioides</u>	<u>12</u>	<u>No</u>	<u>FAC</u>	
4. <u>Malvella leprosa</u>	<u>10</u>	<u>No</u>	<u>FACU</u>	
5. <u>Acmispon junceus</u>	<u>10</u>	<u>No</u>	<u>FAC</u>	
6. <u>Phalaris aquatica</u>	<u>5</u>	<u>No</u>	<u>FACU</u>	
7. <u>Lactuca serriola</u>	<u>4</u>	<u>No</u>	<u>FACU</u>	
8. <u>Hirschfeldia incana</u>	<u>4</u>	<u>No</u>	<u>UPL</u>	
<u>110</u> = Total Cover				
Woody Vine Stratum (Plot size: <u>15</u>)				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic. Hydrophytic Vegetation Present? Yes ☐ No ☒
1. <u>None</u>				
2. _____				
_____ = Total Cover				
% Bare Ground in Herb Stratum <u>20</u>	% Cover of Biotic Crust <u>0</u>			
Remarks:				

Sampling Point: AF-1

HYDROLOGY

Arid West – Version 2.0

Attachment 4. Photographic Log

This page intentionally left blank.



Photograph 1: (36.686279, -121.656684) AR-01 flowing just east of the project SITE, with a cement-lined v-ditch on the right-hand side of the photo. View facing north.



Photograph 2: (36.686279, -121.656684) View of the eastern portion of the project site with AR-01 in the foreground. View facing northwest.



Photograph 3: (36.687023, -121.657468) Typical view of the project site with maintained non-native grassland vegetation cover. View looking north.



Photograph 4: (36.686362, -121.656581) Cement-lined V-ditch that drains uplands west towards AR-01. View facing east.



Sustainability in Action

February 20, 2026.

Aaron Barger

Casentini Street Family Apartment Project

Development Project Manager

RE: Site Plan Review Enclosure Designs

Casentini Street Family Apartment Project

Dear Aaron Barger,

Pursuant to your request and the requirements of the City of Salinas I have reviewed the site plan and the proposed enclosure characteristics of the aforementioned project.

The enclosure design specifications indicate that accommodations have been made for both recycling and trash containers at the above mentioned location.

Inasmuch as there will be no additional operational impact, the service requirements of Republic and the City of Salinas appear to have been met.

Chris Nottenkamper

Operations Manager


Republic Services of Salinas, CA.

1120 Madison Ln

Salinas, CA. 93907.


C 707 364-1620

E cnottenkamper@republicservices.com



North

AB 2097 Vicinity Map



200 CASENTINI STREET

Exhibit “J”

DENSITY BONUS APPLICATION CONCESSION AND WAIVER REQUEST CASENTINI STREET FAMILY APARTMENTS

Milestone Housing Group in partnership with the Monterey County Housing Authority proposes to develop a currently vacant parcel along Casentini Street as an affordable large family apartment community on a 4.9-acre site comprised of one parcel (APN: 003-161-030) with an address of 200 Casentini Street, Salinas, CA. The Monterey County Housing Authority is the current owner of the project property.

The project sponsor proposes to regrade the vacant property and construct a new 100% affordable multi-family residential apartment community and a new day care center. The residential community portion of the project will consist of five (5) new, 3-story apartment buildings and will include eighty-eight (88) apartment units with a mix of 1-bedroom, 2-bedroom, and 3-bedroom apartments. The residential community will also include a leasing/amenity building, a tot lot, and sport court, a dog park area, walking paths, and a mix of covered and surface parking spaces totaling 152 parking spaces.

There is a total of eighty-eight (88) residential apartment units, which includes 87 low income or subsidized housing units and one (1) Manager's Unit. The unit mix is broken down in the Table below and reflects twenty-four (24) one-bedroom units (27.3%), twenty-four (24) two-bedroom units (27.3%), and forty (40) three-bedroom units (45.4%). This unit mix allows for this project to be considered as a large family project. The project also includes a leasing/amenity building with indoor fitness, business/computer room, and a community room. Exterior amenities include a sport court with a basketball hoop for all residents of the project and a tot lot for children up to nine (9) years of age.

The Day Care Center, measuring roughly 4,335 square feet, will provide services to children from newborn age up to 5 years of age. The building will be divided into two classrooms with one room for children 0-24 months and the second classroom for children 24 months to 60 months. Each classroom will have their own secure outdoor play area. The building will include bathrooms, offices for staff, a breakroom, and a kitchen for meal preparation. The Daycare Center will have their own access into the property off Casentini Street and will include 16 parking spaces.

The project will be 100% affordable for households with income at or below 60% of Area Median Income (AMI). The Average AMI level for the project is roughly 49%. The breakdown of AMI levels, unit mix, and number of subsidized units are found in the Table below:

**CASENTINI STREET FAMILY APARTMENTS
UNIT MIX AMI BREAK DOWN**

BEDROOM TYPE	AMI LEVEL	NUMBER OF UNITS
1-BEDROOM	30.00%	3
1-BEDROOM	40.00%	4
1-BEDROOM	50.00%	12
1-BEDROOM	60.00%	7
2-BEDROOM	30.00%	3
2-BEDROOM	40.00%	4
2-BEDROOM	50.00%	12
2-BEDROOM	60.00%	8
3-BEDROOM	30.00%	4
3-BEDROOM	40.00%	6
3-BEDROOM	50.00%	15
3-BEDROOM	60.00%	9

TOTAL UNIT COUNT (SUBSIDIZED)	87
TOTAL UNIT COUNT AT 30% AMI	10
TOTAL UNIT COUNT AT 40% AMI	14
TOTAL UNIT COUNT AT 50% AMI	39
TOTAL UNIT COUNT AT 60% AMI	24
AVERAGE AMI LEVEL	49%

The project seeks on-going rental subsidies in the form of Project-Based Section 8 Vouchers from the Housing Authority of the County of Monterey in addition to tax exempt bond financing and low-income housing tax credits.

To develop the Casentini Street Family Apartments and provide necessary affordable housing to the community, the project requires incentives/concessions and/or waivers as allowed through the State Density Bonus Law. Currently, per our analysis of the City of Salinas Zoning Code, waivers required to allow for the development of the project include removing the restriction on tandem parking spaces, a waiver for not providing 4-bedroom units in our project design, and a waiver requesting a reduction in required open space. Below is a written explanation of the why this 100% affordable large family apartment community could not be developed without these requested waivers.

Waiver Request #1: Article V. Division 2. Parking, Loading, and Outdoor Lighting; Section 37-50.360. Off Street Parking and Loading Spaces Regulations Table 37-50.100:

The project applicant is requesting a waiver of Article V; Division 2; Section 37-50.360; Table 37-50.100 regarding required number of parking spaces per unit type. The project proposes a total of 88 units with 26 One-Bedroom Units, 28 Two-Bedroom Units, and 34 Three Bedroom Units. Per Table 37-50.100 of the City of Salinas Zoning Code Section 37-50.360, based on our unit mix, our required number of parking spaces is 163 spaces. Per the table below, also found in our Project Matrix on Sheet A1.0 of our Site Plan Review Application plan set, we are providing a total of 152 parking spaces. This reflects an eleven (11) stall deficit in the total required number of parking spaces.

Per the State Government Code under Title 7; Division 1; Chapter 4.3 Density Bonus and Other Incentives under Section 65915(p)(1) Law, we are allowed to use a parking ratio of 1 parking stall per every 1-Bedroom Unit, and 1.5 parking stalls per every 2 and 3-Bedroom unit without a requirement to apply for an additional waiver. As reflected in the table below, using the State Density Bonus Law related to parking ratios per bedroom type, our required parking would total 120 stalls. We are providing 152 parking spaces, which exceeds the parking requirements using State Density Bonus Law.

In the light of the above, we respectfully request that the State Density Bonus Law parking ratios be applied as part of our application. In addition, as part of our Waiver Request, if we are required to add eleven (11) parking stalls to meet the City parking requirements, we would be required to remove an entire building section, which would equate to losing four (4) stacks of units or a total of twelve (12) much-needed affordable housing units.

Bedroom Type	Number of Units	Parking Required per Unit Type	Parking Required Total	Parking Required Per State Density Bonus Law	Total Parking Provided	Parking Provided Per Unit Type	Total Parking Provided
1-BEDROOM	3	1.5	4.5	1	3	1	3
1-BEDROOM	4	1.5	6	1	4	1	4
1-BEDROOM	12	1.5	18	1	12	1	12
1-BEDROOM	7	1.5	10.5	1	7	1	7
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
2-BEDROOM	12	2	24	1.5	18	2	24
2-BEDROOM	8	2	16	1.5	12	2	16
3-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	6	2	12	1.5	9	2	12
3-BEDROOM	15	2	30	1.5	22.5	2	30
3-BEDROOM	9	2	18	1.5	13.5	2	18
MANAGER UNIT - 2-BEDROOM	1	2	2	2	2	2	4
TOTAL	88	1.85	163	1.36	120	1.73	152

Waiver Request #2: Section 20-18.020 – Prohibition of Oversized Vehicle Parking (Tandem Parking Stalls):

The Project Applicant is requesting a waiver of Article XVIII – Regulating the Parking of Over-Size Vehicles under Section 20-18.020 prohibiting the ability to park vehicles exceeding 20 feet in length. Per Sheet A1.0: Site Plan, of our Site Plan Review Application plan set, our project data section reflects a total of 152 proposed parking stalls for our residential community. The table below reflects the total number of parking stalls, the breakdown of parking stalls provided per unit type, and the breakdown of tandem parking stalls as part of the 152 total parking spaces provided. As such, of the 152 total parking spaces provided, there is a total of sixty-four (64) tandem parking spaces. This is separated as 40 tandem stalls in our parking garages within the residential buildings and another 24 tandem stalls in our surface parking areas.

In review of our project plan and building layout, losing 64 parking spaces would have a significant impact on the number of affordable units provided in the project. Based on calculating the current number of parking spaces provided and removing the 64 tandem spaces, it leaves the project with a total of 91 parking spaces. Based on the parking ratio of what is provided at 1.73 stalls per unit, we would lose roughly 35 much-needed affordable residential units.

CASENTINI STREET FAMILY APARTMENTS PARKING BREAKDOWN		
PARKING TYPE	TANDEM SPACES	TOTAL SPACES
TANDEM GARAGE	40	80
TANDEM OPEN STALL	24	48
SINGLE GARAGE	0	9
OPEN SPACE - SINGLE	0	15
TOTAL UNIT COUNT (SUBSIDIZED)	64	152

Bedroom Type	Number of Units	Parking Required per Unit Type	Parking Required Total	Parking Required Per State Density Bonus Law	Total Parking Provided	Parking Provided Per Unit Type	Total Parking Provided
1-BEDROOM	3	1.5	4.5	1	3	1	3
1-BEDROOM	4	1.5	6	1	4	1	4
1-BEDROOM	12	1.5	18	1	12	1	12
1-BEDROOM	7	1.5	10.5	1	7	1	7
2-BEDROOM	3	2	6	1.5	4.5	2	6
2-BEDROOM	4	2	8	1.5	6	2	8
2-BEDROOM	12	2	24	1.5	18	2	24
2-BEDROOM	8	2	16	1.5	12	2	16
3-BEDROOM	4	2	8	1.5	6	2	8
3-BEDROOM	6	2	12	1.5	9	2	12
3-BEDROOM	15	2	30	1.5	22.5	2	30
3-BEDROOM	9	2	18	1.5	13.5	2	18
MANAGER UNIT - 2-BEDROOM	1	2	2	2	2	2	4
TOTAL	88	1.85	163	1.36	120	1.73	152

Waiver Request #3: Section 37-30.170; Table 37-30.80 – Bedrooms per Dwelling Unit (Percent of total dwelling units):

Our proposed large family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 of the Zoning code under Table 37-30.80 requires that 10% of all dwelling units in our project include 4 or more bedrooms. As reflected above in our unit and AMI breakdown, our project includes a total of 87 apartment units. With the manager unit, we have a total of 88 units. This would require that we would include nine (9) 4-bedroom units. This requirement would require an adjustment to the building and unit design to reduce the number of 1 bedroom, 2 bedroom, and 3-bedroom units to incorporate the 4-bedroom units. This adjustment to include 10% of the total unit count would result in a loss of 15 units (including the manager's unit) of much-needed affordable residential units

Waiver Request #4: Section 37-30.170; Table 37-30.80 – Usable Open Space Area per Dwelling Unit - Minimum:

Our proposed large family project at 200 Casentini Street is zoned for Residential High Density. Section 37-30.170 under Table 37-30.80 of the Zoning code Development Regulations requires that we provide a minimum of 500 square feet of usable open space per dwelling unit. Our project proposes 88 residential units which equate to a minimum of 44,000 Square Feet of required usable open space. Per Sheet A1.2 Common Open Space of our Site Plan Review Application Plan Set, our project is currently providing 27,305.93 square feet of usable open space.

Our Open Space exhibit reflects six (6) Open Space areas where our calculation derives from. Although there is a substantial amount of excess land on our 4.9-acre parcel, a large area of the site has slopes greater than a 10% slope and cannot be considered for usable open space. The Usable Open Space being provided, 27,306, equates to roughly 310 square feet per unit or a deficiency of roughly 190 square feet per unit. In order for our project to increase our usable open space, we need to reduce our residential building area by 16,694 square feet. Our current residential building area is roughly 121,240 square feet or roughly 1,378 square feet per unit (gross). Reducing the building area by roughly 17,000 square feet, our unit count would reduce from 88 units down to 75 units. Without our requested waiver for this development regulation, the project would lose roughly 13 much-need affordable residential units.

If City Staff would like additional information related to this Waiver Request and analysis stated above, please contact Aaron Barger at abarger@milestonehousing.com or at 408-640-1100 to discuss further.

DAY CARE CENTER DAILY OPERATIONAL AND SAFETY/SECURITY/EVACUATION PLAN
CASENTINI STREET FAMILY APARTMENTS PUD2025-003; SPR 2025-014; CUP 2025-025
COMMENT REPSONSE 18. DAY CARE CENTER

City of Salinas
Community Development Department
65 West Alisal Street
Salinas, CA 92901
(831) 758-7206

OPERATIONAL / ENVIRONMENTAL STATEMENT

It is important that this statement accurately describes the proposed project. Please fill in the following blanks accordingly (Attach additional sheets if necessary):

1. Please provide the following:
 - a. Assessor's Parcel Number (APN) 003-161-030-000
 - b. Site Address Casentini Street (near Intersection with Rico) - vacant land.
 - c. Parcel size (square feet and/or acres) 4.90 acres
2. Describe the nature of your operation (please be specific). Day Care operation for children 1 month to 5 years. Will have two separate classrooms with one classroom for children 0-24 months and then the second classroom for children from 24 months to 5 years of age. Services will include food provisions for breakfast, lunch, and snacks, outdoor playtime, and classroom functions for learning. Remainder of property used for multifamily housing.
3. What is the existing (or previous) use of the property? Vacant land with no structures on site.
4. What products will be produced by the operation? What materials will be used? Will assembly of the product occur on-site? Will these products be sold on-site? Development of site as stated in Project Description is proposed as a new 100% affordable large family rental apartment community with approximately 88 apartment homes with associated parking and amenities. A Day Care Center, run by a third party operator, is also included in the proposed development application for children from Newborn to Five (45) years old. No products will be produced. Construction materials will include wood, stucco, concrete, siding, window glazing, paint, asphalt for driveways, and playground equipment.
5. What are the proposed hours of operation? Months (if seasonal)? Days per week? Hours (from 5:30 AM to 5:00 PM)? Total hours per day? Only closed on national holidays (10 days). Hours of operation - Ag Famililes - 5:30am - 5pm rest of year is 7am to 5pm
6. Describe any special activities or events. Frequency? Fall/Harvest Festival; 1 x a month there is a parent meeting; Seasonal festivities (Winter Festival Promotional events for graduation
7. How many customers/visitors are expected per day on average? kid drop off and pick up (7am-8am) pick up 3:30-5pm
8. How many employees will there be? Are additional employees anticipated? What hours do they work? Do any live on-site (as a caretaker)? Approximately six (6) full time Employees that will work from 5:30AM through 5:00PM. There are no employees that will live on site.
9. What equipment, materials, or supplies will be used, and how will they be stored? Playground on site; Prepare some food on site; Stored in cabinets Janitorial items are stored in a shed or a dedicated closet not accessible to students; school supplies
10. Will there be any service or delivery vehicles? Number? Frequency? Food is weekly delivered; Janitorial and office supplies 1 x per motnhr
11. What are the total number of parking spaces on-site? Residential Parking spaces provide in the open air parking lots total 64 spaces. Parking for the Day Care is provide in an open parking lot and includes 16 parking stalls. The re
12. How will access be provided to the site (street name(s))? Driveway at project frontage along Casentini Street provides access to the residential buildings. There is a second driveway that provides separate access to the day

Exhibit L

13. Is there any existing landscaping or fencing? Is any proposed? There is current cyclone fencing around the property except on east boundary near storm culvert with gate entry along Casentini.

Proposed development will include fencing on all sides with request to include cyclone fence along storm culvert. Proposed landscaping includes 4,175 sf for tot lot, sport court, and BBQ Terrace; a 2,727 sf dog park; and 1,873 sf pocket park. Day Care tot lots total 4,662 sf.

14. Will existing buildings be used or will new buildings be constructed? Indicate which building(s) or portion(s) will be used, and describe the type or construction materials, height, color, etc. Provide floor plan and exterior elevations.

There are no buildings on the project site currently. Project proposes to add residential buildings (including parking), a main leasing/amenity building, and a day care center.

The buildings will range from 2-3 stories in height under construction type V-A. There is a mix of materials including stucco and stone veneer with earth tone colors. The architectural planning sheets attached reflect the color palette and materials used.

15. What are the surrounding land uses to the north, south, east and west? There is an apartment community to the west, a condominium community to the north,

an apartment community to the east across the storm culvert, and Mariners Village Apartment

16. Is this part of a larger project that was previously reviewed by the City? If so, identify previous permit number(s).

No. This is a vacant lot owned by the Monterey County Housing Authority.

17. What is the total floor area of the building(s) on site, (including additional stories)? Total Building Gross area is 127,975 sf. See architecture plans for full breakdown.

Building A is roughly 13,440sf. Building B (4 Buildings) totals 26,950sf per Building or a total of

18. (Residential projects only) – Identify type, size, and number of dwelling units. Project density. Range of sale prices or rents. The proposed project is a 100% affordable family project with rents based on an average AMI at 40%. Approximately 27% of the units are 1-bedroom (24), 27% at 2-bedroom (24), and roughly 45% at 3-bedroom (40).

The average one bedroom unit size is 641 sf; 2-bedroom units average 900 sf; and 3-bedroom

■ IF BOX IS CHECKED, COMPLETE REMAINING QUESTIONS (ENVIRONMENTAL REVIEW).

19. Will the operation or equipment used generate noise greater than other parcels in the area? No. This is a proposed housing community and is similar to all surrounding uses.

20. On a daily basis, estimate how much water will be used by the development? Preliminary estimates of water consumption for the residential project (including landscape) is 14,900 gallons per day and the Day Care is estimated at 1,400 gallons per day.

21. On a daily basis, estimate how much wastewater will be generated? Preliminary estimates reflect roughly 14,100 gallons per day of sewage for residential uses and 1,300 gallons per day for the day care.

22. On a weekly basis, estimate how much solid waste (garbage) will be generated, and how will it be disposed of? Preliminary estimates for solid waste generated is approximately 66 cubic yards or 13,200 gallons of solid waste per week.

23. Will there be any grading on-site? Will it change existing drainage patterns? Yes. There will be grading on site. It will not change existing drainage patterns.

24. Does the property contain any archaeological or historic sites? Per our Phase I Environmental Assessment, the property does not contain archaeological or historical sites.

25. Show on the site plan all bodies of water on, through, or adjacent to the site. Please see Planning Package for identification of adjacent bodies of water.

26. Will any hazardous materials or waste be involved in the operation? If so, how will it be disposed of? No.

27. Will the operation require a substantial increase in public services (schools, police, fire protection)? No. As a family project, there will be children living in our community that will attend area schools.

28. Will the project generate dust, ash, smoke, fumes, or other odors? The construction project will generate typical construction dust, but our construction program will have mitigation measures in places to prevent dust from spreading in the air or on public streets.

29. How do you see this development impacting the surrounding area? The project will be similar to all surrounding properties as a residential multi family community. There will be a benefit of bringing additional children to area schools and providing a day care to future and existing families.

30. Will the project create a substantial demand for energy? No. The project will increase electricity demand with the new residential units and the day care, but demand is minimal.

EMERGENCY DISASTER PLAN FOR CHILD CARE CENTERS

INSTRUCTIONS:

Post a copy in a prominent location in facility, near telephone.
 Licensee is responsible for updating information as required.
 Return a copy to the licensing office.

NAME OF FACILITY MAOF Acosta Early Lernig Center		ADMINISTRATOR OF FACILITY Dina Lozoya Director, Rozghar Aziz, Sandra Fletes ,	
FACILITY ADDRESS (NUMBER, STREET, 461 Cesar Chavez St	CITY, Soledad	STATE, CA	ZIP CODE) TELEPHONE NUMBER (831) 678-0742

I. ASSIGNMENTS DURING AN EMERGENCY (USE REVERSE SIDE IF ADDITIONAL SPACE IS REQUIRED)

NAME(S) OF STAFF	TITLE	ASSIGNMENT
1. Yolanda Delena	Site Supervisor	DIRECT EVACUATION AND PERSON COUNT
2. All teachers	Teachers	HANDLE FIRST AID
3. Lourdes Casillas,	Teacher/ Supportive Staff	TELEPHONE EMERGENCY NUMBERS
4. All Teachers / Home maker	TA, Home Maker	TRANSPORTATION
5. Site Supervisor and Custodian	Site Supervisor Custodian	OTHER (DESCRIBE) Remain whitn childrer
6.		untill parent arrive

II. EMERGENCY NAMES AND TELEPHONE NUMBERS (IN ADDITION TO 9-1-1)

POLICE OR SHERIFF 911 or (831) 678-1332 or 755-5111 Fire departmen	OFFICE OF EMERGENCY SERVICES
RED CROSS (831) 424-4824	POISON CONTROL (800) 876-4766
HOSPITAL(S) (831) 385-6000	OTHER AGENCY/PERSON Dina Lozoya (Program Director 831-214-5129
CHILD PROTECTIVE SERVICES (831) 678-2682	Rozghar Aziz (Program Manager) 831- 214-5731
Fire Department (831) 223-5100	MAOF Main Office (323) 890-9600 or (323) 890-1555

III. FACILITY EXIT LOCATIONS (USING A COPY OF THE FACILITY SKETCH [LIC 999] INDICATE EXITS BY NUMBER)

1. Main Estrance	2. Exit to Toddler outdoor play area
3. Exit to Preschool outdoor play area	4. Exit by kitchen

IV. TEMPORARY RELOCATION SITE(S) (IF AVAILABLE, SUBMIT LETTER OF PERMISSION FROM RENTER/LEASSOR/MANAGER/PROPERTY OWNER)

NAME Housing HDC Development	ADDRESS 425 Benito Street Soledad CA 93960	TELEPHONE NUMBER (831) 678-8852
NAME	ADDRESS	TELEPHONE NUMBER ()

V. UTILITY SHUT—OFF LOCATIONS (INDICATE LOCATION(S) ON THE FACILITY SKETCH [LIC 999])

ELECTRICITY Southwest side of structure near kitchen
WATER Southwest side of structure near kitchen
GAS

VI. FIRST AID KIT (LOCATION)

VII. EQUIPMENT

SMOKE DETECTOR LOCATION (IF REQUIRED) 1 in each office , 2 in each classroom 1 Lounch Room, 2 Hallway
FIRE EXTINGUISHER LOCATION (IF REQUIRED) 1 Hallway outside of women's restroom, 1 kitchen 1 each in classroom
TYPE OF FIRE ALARM SOUNDING DEVICE (IF REQUIRED) Bell Sound
LOCATION OF DEVICE Control Panel in office

VIII. AFFIRMATION STATEMENT

AS ADMINISTRATOR OF THIS FACILITY, I ASSUME RESPONSIBILITY FOR THIS PLAN FOR PROVIDING EMERGENCY SERVICES AS INDICATED BELOW. I SHALL INSTRUCT ALL CLIENTS/RESIDENTS, AGE AND ABILITIES PERMITTING, ANY STAFF AND/OR HOUSEHOLD MEMBERS AS NEEDED IN THEIR DUTIES AND RESPONSIBILITIES UNDER THIS PLAN.

SIGNATURE	DATE 12-20-24
-----------	------------------



Daily Schedule	Salinas Child Care	Infant 1
6:00-7:45	Arrival /Sign in/Health Check, Rest Time, Play Time Llegada / Registrarse / Chequeo de salud, Tiempo de descanso, Tiempo de juego en el interior	
7:45-8:00	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
8:00-8:30	Breakfast / Desayuno	
8:30-9:30	Indoor Play Time/Read Aloud/Music Tiempo de juego en el interior /Lectura en voz alta/Música	
9:30-9:45	Diapering/Handwashing Cambio de pañales/lavado de manos	
9:45-10:45	Outdoor Play Time/ Tiempo de juego al aire libre	
10:45-11:00	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
11:00-11:30	Lunch Time/ Hora del almuerzo	
11:30-11:45	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
11:45-1:45	Nap Time/ Hora de la siesta	
1:45-2:00	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
2:00-2:30	Snack/ Bocado	
2:30-2:45	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
2:45-3:45	Outdoor Play Time/ Tiempo de juego al aire libre	
3:45-4:00	Diapering/Handwashing/ Cambio de pañales/lavado de manos	
4:00- 5:30	Indoor Play Time /Read Aloud/ Departure Tiempo de juego en el interior / Salida	

*This schedule subject to be modified due to weather condition

DAY CARE CENTER DAILY OPERATIONAL AND SAFETY/SECURITY/EVACUATION PLAN: CASENTINI STREET FAMILY APARTMENTS PUD2025-003; SPR 2025-014; CUP 2025-025
COMMENT REPSONSE 18. DAY CARE CENTER - INFANT OPERATIONAL SCHEDULE



Daily Schedule Salinas Child Care Preschool 1 & 2

6:00-8:00 Arrival, Sign-In, Health Checklist, Rest time, Restroom, Handwashing

8:00-8:30 Breakfast

8:30-8:45 Group Meeting (Large Group)

8:45- 9:05 Small Group

9:05-10:05 Choice Time

10:05-10:15 Read Aloud (AM)

10:15-11:15 Outdoor Choice Time

11:15-11:30 Clean-up, Restroom/Handwashing

11:30-12:00 Lunch Time

12:00-2:00 Rest Time/Restroom/Handwashing

2:00-2:30 Nap

2:30-2:45 Read Aloud (PM)

2:45-3:45 Outdoor Choice Time

3:45-4:30 Choice Time/Departure

